PROJECT NO.	SHEET NO.	TOTAL NO.
I-5736 & I-5767	11	

S U M M A R Y O F Q U A N T I T I E S

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	INCIDENTAL STONE BASE TONS	MILLING ASPHALT PAVEMENT, 2½" DEPTH SY	MILLING ASPHALT PAVEMENT, 3" DEPTH SY	MILLING ASPHALT PAVEMENT, 1½" DEPTH SY	MILLING ASPHALT PAVEMENT, 0" TO 1 1/2" DEPTH SY	INCIDENTAL MILLING SY	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0D TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5D TON	ASPHALT BINDER FOR PLANT MIX TONS	POLYMER MODIFIED ASPHALT BINDER FOR PLANT MIX TONS	OPEN-GRADED ASPHALT FRICTION COURSE, TYPE FC-2 MODIFIED TON	PATCHING EXISTING PAVEMENT TONS	ASPHALT SURFACE TREATMENT, MAT COAT, #67 STONE SY	EMULSION FOR ASPHALT SURFACE TREATMENT GAL	MILLED RUMBLE STRIPS LF	NON-WOVEN GEOTEXTILE PAVEMENT INTERLAYER SY	PORTABLE LIGHTING LS	TRENCHING (UNPAVED) (1)(2") LF	JUNCTION BOX (STANDARD SIZE) EA	2" RISER W/ WEATHERHEAD EA	INDUCTIVE LOOP SAW CUT LF	LEAD-IN CABLE (14-2) LF
53010.3.1	Forsyth	29	I-74 EASTBOUND/US 311 SOUTHBOUND (19.08 - 28.27)	I-40 EASTBOUND TO GUILFORD COUNTY LINE (19.08 - 28.27)	1	2		NO	NO	0.569	24	406	8,012				533	1,152	901	52	74	376				96,150.00		0.50					
		"	"		1	2		NO	NO	0.06	43		1,505					217	181	10	15	70											
		"	"		1	2		NO	NO	0.154	39		3,532					505	358	23	30	163											
		"	"		1	2		NO	NO	0.351	24		4,947				533	710	556	32	46	232											
		"	"	SKIP BRIDGE #396		2		NO	NO	0.042	24																						
		"	"		1	2		NO	NO	0.03	24		427				533	61	47	3	4	20											
		"	"		1	2		NO	NO	0.122	30		2,150					308	313	14	24	108											
		"	"	OH BRIDGE #394	1	2		NO	NO	0.478	24		6,733				1,333	967	757	44	62	316											
		"	"		1	2		NO	NO	0.024	44		611					89	69	4	6	27											
		"	"		1	2		NO	NO	0.061	52		1,849					266	169	12	14	70											
		"	"		1	2		NO	NO	0.162	38		3,610					517	352	23	29	150											
		"	"		1	2		NO	NO	1.373	24		19,333				533	2,779	2,174	125	179	908											
		"	"	SKIP PROJECT UNION CROSS ROAD		2		NO	NO	0.913	24																						
		"	"	OH BRIDGE #401	1	2		NO	NO	0.532	24		7,485				2,276	1,077	842	48	69	352											
		"	"	OH BRIDGE #400	1	2		NO	NO	0.473	24		6,653				1,351	957	749	43	62	313											
		"	"		1	2		NO	NO	0.251	30		4,417					634	571	29	46	222											
		"	"		1	2		NO	NO	1.298	24		18,280				1,911	2,627	2,055	118	170	859											
		"	"	OVER HEAD BRIDGE #398	1	2		NO	NO	0.532	24		7,493					1,077	842	48	69	352											
		"	"		1	2		NO	NO	0.111	30		1,950					280	302	13	23	98											
		"	"		1	2		NO	NO	0.206	24		2,907					417	326	19	27	136											
		"	"	OH BRIDGE #19	2	2		NO	NO	0.053	36		1,120			218	2,384	160	152	7	12	63											
		"	"		1	2		NO	NO	0.179	30		3,150					452	372	20	31	166											
		"	"		1	2		NO	NO	0.101	24		1,427					204	160	9	13	67											
		"	"		1	2		NO	NO	0.241	30		4,250					609	619	27	48	214											
		"	"		1	2		NO	NO	0.538	24		7,573					1,089	852	49	70	356											
		"	"		1	2		NO	NO	0.126	30		2,218					318	237	14	20	103											
		"	"		1	2		NO	NO	0.125	30		2,200					316	321	14	25	111											
TOTAL FOR MAP NO. 29										**9.105**		**406**	**123,832**			**218**	**11,387**	**17,788**	**14,277**	**800**	**1,168**	**5,852**				**96,150.00**		**0.50**					
53010.3.1	Forsyth	30	EASTBOUND ON RAMP FROM WESTBOUND 1-40 TO EASTBOUND I-74	EASTBOUND ON RAMP FROM WESTBOUND 1-40 TO EASTBOUND I-74	3	2		NO	NO	0.008	28	48				33	467		11		1			131	41								
		"	"		4	2		NO	NO	0.019	51					78			48		3			568	196								
		"	"	OH BRIDGE #432	4	2		NO	NO	0.116	52					476	3,000		298		17			3,539	1,246								
		"	"		5	2		NO	NO	0.027	46								61		3			729	272								
		"	"		5	2		NO	NO	0.104	40								206		12			2,441	929								
		"	"		5	2		NO	NO	0.194	34								326		19			3,870	1,471								
TOTAL FOR MAP NO. 30										**0.468**		**48**				**587**	**3,467**		**950**		**55**			**11,278**	**4,155**								
53010.3.1	Forsyth	31	EASTBOUND OFF RAMP FROM I-74 EASTBOUND TO SR 2698 (RIDGEWOOD RD)	OFF RAMP FROM I-74 EASTBOUND TO SR 2698 (RIDGEWOOD RD)	3	2		NO	NO	0.157	21	58					175		163		9			1,934	736								
TOTAL FOR MAP NO. 31										**0.157**		**58**					**175**		**163**		**9**			**1,934**	**736**								
53010.3.1	Forsyth	32	EASTBOUND ON RAMP FROM SR 2698 (RIDGEWOOD RD) TO EASTBOUND I-74	ON RAMP FROM SR2698 (RIDGEWOOD RD) TO EASTBOUND I-74	3	2		NO	NO	0.294	20	65					167		292		17			3,450	1,276								
TOTAL FOR MAP NO. 32										**0.294**		**65**					**167**		**292**		**17**			**3,450**	**1,276**								
53010.3.1	Forsyth	33	EASTBOUND OFF RAMP FROM I-74 EASTBOUND TO SR1003 (HIGH POINT RD)	OFF RAMP FROM I-74 EASTBOUND TO SR1003 (HIGH POINT RD)	4	2		NO	NO	0.181	18	62							162		9			1,911	726								
		"	"		4	2		NO	NO	0.018	23								21		1			243	90								
		"	"		4	2		NO	NO	0.028	27								37		2			444	171								
		"	"		4	2		NO	NO	0.009	34								15		1			180	64								
		"	"		5	2		NO	NO	0.011	39						325		21		1			252	99								
TOTAL FOR MAP NO. 33										**0.247**		**62**					**325**		**256**		**14**			**3,030**	**1,150**								
53010.3.1	Forsyth	34	EASTBOUND ON RAMP FROM SR1003 (HIGH POINT RD) TO EASTBOUND I-74	EASTBOUND ON RAMP FROM SR1003 (HIGH POINT RD) TO EASTBOUND I-74	4	2		NO	NO	0.019	68	62					567		64		4			758	287								
		"	"		4	2		NO	NO	0.229	20								227		13			2,687	996								
TOTAL FOR MAP NO. 34										**0.248**		**62**					**567**		**291**		**17**			**3,445**	**1,283**								
53010.3.1	Forsyth	35	EASTBOUND OFF RAMP FROM EASTBOUND I-74 TO NC 66	EASTBOUND OFF RAMP FROM EASTBOUND I-74 TO NC 66	4	2		NO	NO	0.231	21	63							240		14			2,846	1,082								
		"	"		4	2		NO	NO	0.025	34								42		2			499	187								
		"	"		4	2		NO	NO	0.005	46						383		11		1			135	49								
TOTAL FOR MAP NO. 35										**0.261**		**63**					**383**		**293**		**17**			**3,480**	**1,318**								
53010.3.1	Forsyth	36	RAMP FROM NC66 SOUTHBOUND TO	EASTBOUND ON RAMP FROM NC66 SOUTHBOUND TO EASTBOUND I-74	11	2		NO	NO	0.156	23				2,105				178		10												
TOTAL FOR MAP NO. 36										**0.156**					**2,105**				**178**		**10**												
53010.3.1	Forsyth	37	EASTBOUND ON RAMP FROM NORTHBOUND NC66 TO EASTBOUND I-74	EASTBOUND ON RAMP FROM NORTHBOUND NC66 TO EASTBOUND I-74	3	2		NO	NO	0.016	45	64					375		36		2			422	160								
		"	"		3	2		NO	NO	0.272	20								270		15			3,191	1,181								
TOTAL FOR MAP NO. 37										**0.288**		**64**					**375**		**306**		**17**			**3,613**	**1,341**								