PROJECT NO.	SHEET NO.	TOTAL NO.
I-5736 & I-5767	13	

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	4688000000-E 6" X 90 M WHITE THERMO LF	4688000000-E 6" X 90 M YELLOW THERMO LF	4690000000-E 6" X 120 M WHITE THERMO LF	4695000000-E 8" X 90 M WHITE THERMO LF	4700000000-E 12" X 90 M WHITE THERMO LF	4710000000-E 24" X 120 M WHITE THERMO LF	4721000000-E THERMO MSG ONLY 120 M EA	4725000000-E THERMO RT ARROW 90 M EA	4725000000-E THERMO MERGE LEFT ARROW 90 M EA	4725000000-E THERMO STR ARROW 90 M EA	4725000000-E THERMO RAMP ARROW EA	4725000000-E THERMO LT ARROW 90 M EA	4725000000-E THERMO STR & LT ARROW 90 M EA	4725000000-E THERMO STR & RT ARROW 90 M EA	4725000000-E THERMO MERGE RIGHT ARROW 90 M EA	4815000000-E 6" WHITE PAINT LF	4815000000-E 6" YELLOW PAINT LF	4820000000-E 8" WHITE PAINT LF	4825000000-E 12" WHITE PAINT LF	4835000000-E 24" WHITE PAINT LF	4840000000-N PAINT MSG ONLY EA	4845000000-N PAINT RT ARROW EA	4845000000-N PAINT MERGE LEFT ARROW EA	4845000000-N PAINT STR ARROW EA	4845000000-N PAINT LT ARROW EA	4845000000-N PAINT STR & LT ARROW EA	4845000000-N PAINT STR & RT ARROW EA	4845000000-N PAINT MERGE RIGHT ARROW EA	4905000000-N SNOWPLOWABLE PAVEMENT MARKERS EA
52018.3.1	Guilford	1	I-74 EASTBOUND/US 31 SOUTHBOUND (0.0 - 7.63)	FROM FORSYTH COUNTY LINE TO I-85 BUS (0.0 - 7.63)	1	2	MD	7.53	28-91	39,750	39,750	18,927		10,020		24	12	13							117,354	79,500		20,040		24	6	13						1,610
TOTAL FOR MAP NO. 1								**7.53**		**39,750**	**39,750**	**18,927**		**10,020**		**24**	**12**	**13**							**117,354**	**79,500**		**20,040**		**24**	**6**	**13**						**1,610**
52018.3.1	Guilford	2	EASTBOUND OFF RAMP SR 1009 (N. MAIN ST)	EASTBOUND OFF RAMP SR 1009 (N. MAIN ST)	3	2		0.3	33-45	1,585	1,585	556			40		3		6	2					2,141	1,585			40.00		3		6					53
TOTAL FOR MAP NO. 2								**0.3**		**1,585**	**1,585**	**556**			**40**		**3**		**6**	**2**					**2,141**	**1,585**			**40.00**		**3**		**6**					**53**
52018.3.1	Guilford	3	EASTBOUND ON RAMP FROM SR 1009 (N. MAIN STREET)	EASTBOUND ON RAMP FROM SR 1009 (N. MAIN STREET)	4	2		0.45	31-53	2,350	2,350	745	160					3							3,255	2,350	160					3						43
TOTAL FOR MAP NO. 3								**0.45**		**2,350**	**2,350**	**745**	**160**					**3**							**3,255**	**2,350**	**160**					**3**						**43**
52018.3.1	Guilford	4	EASTBOUND OFF RAMP TO JOHNSON STREET	EASTBOUND OFF RAMP TO JOHNSON STREET	3	2		0.2	24-29	1,045	1,045	100			40		1			1	1				1,145	1,045			40.00		1			1				17
TOTAL FOR MAP NO. 4								**0.2**		**1,045**	**1,045**	**100**			**40**		**1**			**1**	**1**				**1,145**	**1,045**			**40.00**		**1**			**1**				**17**
52018.3.1	Guilford	5	EASTBOUND ON RAMP FROM JOHNSON STREET	EASTBOUND ON RAMP FROM JOHNSON STREET	3	2		0.192	23	1,015	1,015														1,015	1,015												
TOTAL FOR MAP NO. 5								**0.192**		**1,015**	**1,015**														**1,015**	**1,015**												
52018.3.1	Guilford	6	MAP DELETED - U-5169 PROJECT	MAP DELETED - U-5169 PROJECT		2		0.193	44																												
TOTAL FOR MAP NO. 6								**0.193**																													
52018.3.1	Guilford	7	MAP DELETED - U-5169 PROJECT	MAP DELETED - U-5169 PROJECT		2		0.121	28																												
TOTAL FOR MAP NO. 7								**0.121**																													
52018.3.1	Guilford	8	EASTBOUND OFF RAMP TO SR 1486 (GREENSBORO STREET)	EASTBOUND OFF RAMP TO SR 1486 (GREENSBORO STREET)	5	2		0.21	26-32	1,105	1,105	80			71		2			1		2			1,185	1,105			71.00		2				2			17
TOTAL FOR MAP NO. 8								**0.21**		**1,105**	**1,105**	**80**			**71**		**2**			**1**		**2**			**1,185**	**1,105**			**71.00**		**2**				**2**			**17**
52018.3.1	Guilford	9	EASTBOUND ON RAMP FROM SR 1486 (GREENSBORO ROAD)	EASTBOUND ON RAMP FROM SR 1486 (GREENSBORO ROAD)	3	2		0.127	34	670	670	178													848	670												9
TOTAL FOR MAP NO. 9								**0.127**		**670**	**670**	**178**													**848**	**670**												**9**
52018.3.1	Guilford	10	EASTBOUND OFF RAMP TO SR 1113 (KIVETT DRIVE)	EASTBOUND OFF RAMP TO SR 1113 (KIVETT DRIVE)	5	2		0.2	26-38		1,060	310			42		2			1	4				310	1,060			42.00		2			4				32
TOTAL FOR MAP NO. 10								**0.2**			**1,060**	**310**			**42**		**2**			**1**	**4**				**310**	**1,060**			**42.00**		**2**			**4**				**32**
52018.3.1	Guilford	11	EASTBOUND ON RAMP FROM SR 1113 (KIVETT DRIVE)	EASTBOUND ON RAMP FROM SR 1113 (KIVETT DRIVE)	8	2		0.084	18	1,475	1,475														1,475	1,475												
		"	"		3	2		0.195	21																												
TOTAL FOR MAP NO. 11								**0.279**		**1,475**	**1,475**														**1,475**	**1,475**												
52018.3.1	Guilford	12	EASTBOUND OFF RAMP TO SR 1300 (GREEN DRIVE)	EASTBOUND OFF RAMP TO SR 1300 (GREEN DRIVE)	3	2		0.18	29-34	950	950	160			45		2			1	2				1,110	950			45.00		2			2				26
TOTAL FOR MAP NO. 12								**0.18**		**950**	**950**	**160**			**45**		**2**			**1**	**2**				**1,110**	**950**			**45.00**		**2**			**2**				**26**
52018.3.1	Guilford	13	EASTBOUND ON RAMP FROM SR 1300 (GREEN DRIVE)	EASTBOUND ON RAMP FROM SR 1300 (GREEN DRIVE)	3	2		0.44	22-32	2,315	2,315	157						3							2,472	2,315						3						6
TOTAL FOR MAP NO. 13								**0.44**		**2,315**	**2,315**	**157**						**3**							**2,472**	**2,315**						**3**						**6**
52018.3.1	Guilford	14	EASTBOUND OFF RAMP TO I-85 BUS	EASTBOUND OFF RAMP TO I-85 BUS	3	2		0.44	24-45	2,340	2,340	258			60				4	1			2		2,598	2,340			60.00				4		2		32
TOTAL FOR MAP NO. 14								**0.44**		**2,340**	**2,340**	**258**			**60**				**4**	**1**			**2**		**2,598**	**2,340**			**60.00**				**4**		**2**		**32**
52018.3.1	Guilford	15	I-74 WESTBOUND/US311 NORTH BOUND (4.21 - 11.84)	I-74 WESTBOUND/US311 NORTH BOUND (4.21 - 11.84)	1	2	MD	7.58	37-91	41,130	40,015	17,795		12,740		24	9	15					2		117,850	40,015		25,480		24	9	15			2		1,635
TOTAL FOR MAP NO. 15								**7.58**		**41,130**	**40,015**	**17,795**		**12,740**		**24**	**9**	**15**					**2**		**117,850**	**40,015**		**25,480**		**24**	**9**	**15**			**2**		**1,635**
52018.3.1	Guilford	16	WESTBOUND ON RAMP FROM I-85 BUS	WESTBOUND ON RAMP FROM I-85 BUS	3	2		0.43	25-34	2,245	2,245	189						3							2,434	2,245						3						8
TOTAL FOR MAP NO. 16								**0.43**		**2,245**	**2,245**	**189**						**3**							**2,434**	**2,245**						**3**						**8**
52018.3.1	Guilford	17	WESTBOUND OFF RAMP TO SR 1300 (GREEN DRIVE)/SR 1193 (TRIANGLE LAKE ROAD)	WESTBOUND OFF RAMP TO SR 1300 (GREEN DRIVE)/SR 1193 (TRIANGLE LAKE ROAD)	3	2		0.34	22-33	1,785	1,785	144			37		2			1	2				1,929	1,785			37.00		2			2				20
TOTAL FOR MAP NO. 17								**0.34**		**1,785**	**1,785**	**144**			**37**		**2**			**1**	**2**				**1,929**	**1,785**			**37.00**		**2**			**2**				**20**
52018.3.1	Guilford	18	WESTBOUND ON RAMP FROM SR 1300 (GREEN DRIVE)/SR 1193 (TRIANGLE LAKE ROAD	WESTBOUND ON RAMP FROM SR 1300 (GREEN DRIVE)/SR 1193 (TRIANGLE LAKE ROAD	3	2		0.106	27	560	560														560	560												
TOTAL FOR MAP NO. 18								**0.106**		**560**	**560**														**560**	**560**												
52018.3.1	Guilford	19	WESTBOUND OFF RAMP TO SR 1113 (KIVETT DRIVE)	WESTBOUND OFF RAMP TO SR 1113 (KIVETT DRIVE)	5	2		0.25	24-33	1,345	1,345	90					2			1	2				1,435	1,345					2			2				17
TOTAL FOR MAP NO. 19								**0.25**		**1,345**	**1,345**	**90**					**2**			**1**	**2**				**1,435**	**1,345**					**2**			**2**				**17**
52018.3.1	Guilford	20	WESTBOUND ON RAMP FROM SR 1113 (KIVETT DRIVE)	WESTBOUND ON RAMP FROM SR 1113 (KIVETT DRIVE)	7	2		0.18	15-26		925															925											
TOTAL FOR MAP NO. 20								**0.18**			**925**															**925**											
52018.3.1	Guilford	21	WESTBOUND OFF RAMP TO SR 1486 (GREENSBORO ROAD)	WESTBOUND OFF RAMP TO SR 1486 (GREENSBORO ROAD)	3	2		0.155	30	820	820	205			65					2	2		2		1,025	820			65.00					2		2		39
TOTAL FOR MAP NO. 21								**0.155**		**820**	**820**	**205**			**65**					**2**	**2**		**2**		**1,025**	**820**			**65.00**					**2**		**2**		**39**
52018.3.1	Guilford	22	WESTBOUND ON RAMP FROM SR 1486 (GREENSBORO ROAD)	WESTBOUND ON RAMP FROM SR 1486 (GREENSBORO ROAD)	3	2		0.148	24	780	780														780	780												
TOTAL FOR MAP NO. 22								**0.148**		**780**	**780**														**780**	**780**												
52018.3.1	Guilford	23	MAP DELETED - U-5169 PROJECT	MAP DELETED - U-5169 PROJECT		2		0.204	28																												
TOTAL FOR MAP NO. 23								**0.204**																													
52018.3.1	Guilford	24	MAP DELETED - U-5169 PROJECT	MAP DELETED - U-5169 PROJECT		2		0.14	29																												
TOTAL FOR MAP NO. 24								**0.14**																													
52018.3.1	Guilford	25	WESTBOUND OFF RAMP TO JOHNSON STREET	WESTBOUND OFF RAMP TO JOHNSON STREET	3	2		0.21	24-33	1,090	1,090	130			58		2			1	2				1,220	1,090			58.00		2			2				50
TOTAL FOR MAP NO. 25								**0.21**		**1,090**	**1,090**	**130**			**58**		**2**			**1**	**2**				**1,220**	**1,090**			**58.00**		**2**			**2**				**50**
52018.3.1	Guilford	26	BOUND ON RAMP FROM JOHNSON S	WESTBOUND ON RAMP FROM JOHNSON STREET	3	2		0.119	23	630	630														630	630												
TOTAL FOR MAP NO. 26								**0.119**		**630**	**630**														**630**	**630**												
52018.3.1	Guilford	27	WESTBOUND OFF RAMP TO SR 1009 (N. MAIN STREET)	WESTBOUND OFF RAMP TO SR 1009 (N. MAIN STREET)	5	2		0.57	33-40	2,995	2,995	829			42				3	2	3		3		3,824	2,995			42.00				3	3		3		79
TOTAL FOR MAP NO. 27								**0.57**		**2,995**	**2,995**	**829**			**42**				**3**	**2**	**3**		**3**		**3,824**	**2,995**			**42.00**				**3**	**3**		**3**		**79**
52018.3.1	Guilford	28	WESTBOUND ON RAMP FROM SR 1009 (N. MAIN STREET)	WESTBOUND ON RAMP FROM SR 1009 (N. MAIN STREET)	3	2		0.75	33	3,980	3,980	995													4,975	3,980												50
TOTAL FOR MAP NO. 28								**0.75**		**3,980**	**3,980**	**995**													**4,975**	**3,980**												**50**
TOTAL FOR PROJ NO. 52018.3.1								**22.044**		**111,960**	**112,830**	**41,848**	**160**	**22,760**	**500**	**48**	**37**	**37**	**13**	**14**	**18**	**2**	**9**		**271,570**	**152,580**	**160**	**45,520**	**500.00**	**48**	**31**	**37**	**13**	**18**	**2**	**9**		**3,743**
										224,790									**130**						**424,150**						**110**						