PROJECT NO.	SHEET NO.	TOTAL NO.
I-5309, I-5836	6	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	INCIDENTAL STONE BASE TONS	MILLING ASPHALT PAVEMENT, 2"DEPTH SY	MILLING ASPHALT PAVEMENT, 1½" DEPTH SY	MILLING ASPHALT PAVEMENT, 1 1/2" TO 4" DEPTH SY	INCIDENTAL MILLING SY	ASPHALT CONC SURFACE COURSE, TYPE S9.5C TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5D TON	ASPHALT BINDER FOR PLANT MIX TONS	POLYMER MODIFIED ASPHALT BINDER FOR PLANT MIX TONS	OPEN-GRADED ASPHALT FRICTION COURSE, TYPE FC-2 MODIFIED TON	PATCHING EXISTING PAVEMENT TONS	FOG SEAL SY	FLOWABLE FILL (EXCAVATABLE) CY	REMOVE AND REPLACE CONCRETE APRON EA	ADJ. OF MANHOLES EA	PORTABLE LIGHTING LS	JUNCTION BOX (STANDARD SIZE) EA	2" RISER W/ WEATHERHEAD EA	INDUCTIVE LOOP SAW CUT LF
I-5309	Alamance	1	I-40 EASTBOUND/I-85 NORTHBOUND	FROM E. OF GUILFORD COUNTY LINE TO EAST OF NC 49 (0.795-6.62)	1	4	MD	NO	NO	0.214	48		6,026					677		55	272	171	2,578	11	4		0.50			
		"			1	4		NO	NO	0.121	56		3,975					447		36	179		2,062							
		"			1	4		NO	NO	0.158	48		4,449					500		41	200		1,951							
		"			1	4		NO	NO	0.026	62		946					106		9	43		563							
		"			1	4		NO	NO	0.014	60		493					55		5	22		127							
		"			1	4		NO	NO	0.031	60		1,091					123		10	49		290							
		"			1	4		NO	NO	0.039	60		1,373					154		13	62		364							
		"			1	4		NO	NO	0.034	60		1,197					134		11	54		300							
		"			1	4		NO	NO	0.062	54		1,964					221		18	88		640							
		"			1	4		NO	NO	0.037	48		1,042					117		10	47		450							
		"			1	4		NO	NO	0.063	63		2,329					261		21	105		1,240							
		"			1	4		NO	NO	0.007	61		251					28		2	11		66							
		"			1	4		NO	NO	0.106	60		3,731					419		34	168		1,056							
		"			1	4		NO	NO	0.058	54		1,837					206		17	83		648							
		"			1	4		NO	NO	0.036	48		1,014					114		9	46		443							
		"			2	4		NO	NO	0.257	48			7,237		2,400		610		55	326		3,164							
		"			2	4		NO	NO	0.109	58			3,709				312		28	167		1,658							
		"			2	4		NO	NO	0.291	48			8,195				690		62	369		3,586							
		"			2	4		NO	NO	0.082	63			3,031				255		23	137		1,107							
		"			2	4		NO	NO	0.119	60			4,189				353		32	189		1,155							
		"			2	4		NO	NO	0.069	54			2,186				184		16	98		804							
		"				4		NO	NO	1.084	48			30,525				2,571		230	1,375		13,351							
		"			2	4		NO	NO	0.108	56			3,548				299		27	160		1,995							
		"			2	4		NO	NO	0.093	48			2,619				221		20	118		1,143							
		"				4		NO	NO	0.03	48																			
		"			2	4		NO	NO	0.171	48			4,815	12,500			406		36	217		2,112							
		"				4		NO	NO	0.059	62			2,146				181		16	97		896							
		"			2	4		NO	NO	0.134	60			4,717				397		36	212		1,183							
		"			2	4		NO	NO	0.059	54			1,869				157		14	84		637							
		"			2	4		NO	NO	1.34	48			37,734				3,178		285	1,700		16,513							
		"			2	4		NO	NO	0.186	54			5,893				496		44	265		4,474							
		"			2	4		NO	NO	0.104	48			2,929				247		22	132		1,276							
		"			2	4		NO	NO	0.042	62			1,528				129		12	69		759							
		"				4		NO	NO	0.034	60																			
		"			2	4		NO	NO	0.148	60			5,210				439		39	235		1,481							
		"			2	4		NO	NO	0.048	54			1,521				128		11	69		540							
		"			2	4		NO	NO	0.066	62			2,401				202		18	108		1,326							
		"			2	4		NO	NO	0.092	60			3,238				273		24	146		864							
		"			2	4		NO	NO	0.074	54			2,344				197		18	106		804							
		"			2	4		NO	NO	0.011	48			310				26		2	14		136							
TOTAL FOR MAP NO. 1										**5.816**			**31,718**	**141,894**	**12,500**	**2,400**		**15,513**		**1,361**	**7,822**	**171**	**73,742**	**11**	**4**		**0.50**			
I-5309	Alamance	2	1 - OFF RAMP TO UNIVERSITY DRIVE	FROM I-40EB/I-85NB TO UNIVERSITY DRIVE	3	2		NO	NO	0.162	16	64		1,521			129		8				855							650
		"			3	2		NO	NO	0.036	27			570			48		3				84							
		"			3	2		NO	NO	0.019	43			479			40		2				146							
		"			3	2		NO	NO	0.04	48			1,126			95		6				305							
		"			3	2		NO	NO	0.01	48			282			24		1				48							
		"			3	2		NO	NO	0.016	73			685			58		3											
TOTAL FOR MAP NO. 2										**0.283**		**64**		**4,663**			**394**		**23**				**1,438**							**650**
I-5309	Alamance	3	1 - ON RAMP SB UNIVERSITY DRIVE	FROM SB UNIVERSITY DRIVE TO I-40EB/I-85NB	3	2		NO	NO	0.013	18	13		137			12		1				50							
		"			3	2		NO	NO	0.167	17			1,666			141		8				500							
TOTAL FOR MAP NO. 3										**0.18**		**13**		**1,803**			**153**		**9**				**550**							
I-5309	Alamance	4	1 - ON RAMP FROM NB UNIVERSITY	FROM NB UNIVERSITY TO I-40EB/I-85NB	3	2		NO	NO	0.002	98	33		115			10		1											
		"			3	2		NO	NO	0.013	53			404			34		2											
		"			3	2		NO	NO	0.057	16			535			45		3				300							
		"			3	2		NO	NO	0.019	16			178			15		1				100							
		"			3	2		NO	NO	0.064	16			601			51		3				604							
TOTAL FOR MAP NO. 4										**0.155**		**33**		**1,833**			**155**		**10**				**1,004**							
I-5309	Alamance	5	1 - OFF RAMP TO HUFFMAN MILL ROAD	FROM I-40EB/I-85NB TO HUFFMAN MILL ROAD	3	2		NO	NO	0.042	20	5		493			42		2				196			1		1		425
		"			3	2		NO	NO	0.034	28			559			47		3				200							
		"			3	2		NO	NO	0.025	36			528			45		3				144							
		"			3	2		NO	NO	0.009	56			296			25		1				20							
		"			3	2		NO	NO	0.002	90			106			9		1				4							
TOTAL FOR MAP NO. 5										**0.112**		**5**		**1,982**			**168**		**10**				**564**			**1**		**1**		**425**
I-5309	Alamance	6	1 - ON RAMP FROM HUFFMAN MILL ROAD	FROM HUFFMAN MILL ROAD TO I-40EB/I-85NB	3	2		NO	NO	0.038	37	25		825			70		4											
		"			3	2		NO	NO	0.066	32			1,239			104		6				233							
		"			3	2		NO	NO	0.047	25			689			58		3				222							
		"			3	2		NO	NO	0.013	18			137			12		1				62							
TOTAL FOR MAP NO. 6										**0.164**		**25**		**2,890**			**244**		**14**				**517**							
46264.3.1	Alamance	7	1 - OFF RAMP TO NC 62	FROM I-40EB/I-85NB TO NC 62	3	2		NO	NO	0.028	18	20		296			25		1				133							425
		"			3	2		NO	NO	0.02	27			317			27		2				93							
		"			3	2		NO	NO	0.047	36			993			84		5				222							
		"			3	2		NO	NO	0.002	36			42			4						9							
		"			3	2		NO	NO	0.006	38			134			11		1				13							
		"			3	2		NO	NO	0.006	75			264			22		1											
TOTAL FOR MAP NO. 7										**0.109**		**20**		**2,046**			**173**		**10**				**470**							**425**
I-5309	Alamance	8	1 - ON RAMP FROM NC 62	FROM NC 62 TO I-40EB/I-85NB	3	2		NO	NO	0.176	16			1,652			140		8				620							
TOTAL FOR MAP NO. 8										**0.176**				**1,652**			**140**		**8**				**620**							
46264.3.1	Alamance	9	1 - OFF RAMP TO NC 49	FROM I-40EB/I-85NB TO NC 49	3	2		NO	NO	0.033	12	25		232			20		1				292					1		650
		"			3	2		NO	NO	0.009	14			74			6						83							
		"			3	2		NO	NO	0.033	17			329			28		2				292							
		"			3	2		NO	NO	0.018	21			222			19		1				158							
		"			3	2		NO	NO	0.037	30			651			55		3				152							
		"			3	2		NO	NO	0.01	38			223			19		1				61							
		"			3	2		NO	NO	0.005	61			179			15		1				24							
TOTAL FOR MAP NO. 9										**0.145**		**25**		**1,910**			**162**		**9**				**1,062**					**1**		**650**
I-5309	Alamance	10	1 - ON RAMP SB NC 49	FROM SB NC 49 TO I-40EB/I-85NB	3	2		NO	NO	0.099	20			1,162			98		6				233							
TOTAL FOR MAP NO. 10										**0.099**				**1,162**			**98**		**6**				**233**							
I-5309	Alamance	11	1 - ON RAMP NB NC49	FROM NB NC49 TO I-40EB/I-85NB	3	2		NO	NO	0.024	12	25		169			14		1											
		"			3	2		NO	NO	0.006	24			85			7						200							
		"			3	2		NO	NO	0.014	21			173			15		1				83							
		"			3	2		NO	NO	0.208	17			2,075			176		10				978							
TOTAL FOR MAP NO. 11										**0.252**		**25**		**2,502**			**212**		**12**				**1,261**							