STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

PROJ. REFERENCE NO.	SHEET NO.
B-5300	X-1A

Approximate quantities only. Unclassified excavation, fine grading, clearing and grubbing, and removal of existing pavement will be paid for at the lump sum price for "Grading".

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
16+00.00	0	0
16+50.00	5	52
17+00.00	9	108
17+50.00	9	120
18+00.00	13	136
18+28.81	5	84

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
19+26.19	0	0
19+50.00	5	10
20+00.00	13	31
20+50.00	12	46
21+00.00	9	27

Station Dr1	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+00.00	0	0
10+50.00	0	3
11+00.00	0	39
11+29.20	0	43