8/17/99

REVISIONS

PROJECT REFERENCE NO.	SHEET NO.
2016CPT.02.27.20071.3	4

SUMMARY OF QUANTITIES

PROJECT	COUNTY	MAP	ROUTE	DESCRIPTION	TYP	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	BORROW EXCAVATION	INCIDENTAL STONE BASE	SHOULDER RECONSTRUCTION	INCIDENTAL MILLING	SURFACE COURSE, SF9.5A	ASPHALT BINDER FOR PLANT MIX	TEMPORARY SILT FENCE	WATTLE	SEED & MULCHING	RESPONSE FOR EROSION CONTROL
NO		NO			NO					MI	FT	CY	TONS	SMI	SY	TONS	TONS	LF	LF	AC	EA
2016CPT.02.27.20071.3	Beaufort	1	SR 1625	FROM JOINT AT NC 99 TO SR 1626	1	2	2WU	NO	NO	2.715	20.5	2,655	300	5.43	140	3,954	265	1,000	400	2.60	4
TOTAL FOR MAP NO. 1										**2.715**		**2,655**	**300**	**5.43**	**140**	**3,954**	**265**	**1,000**	**400**	**2.60**	**4**
2016CPT.02.27.20071.3	Beaufort	2	SR 1626	FROM SR 1625 TO SR 1621	1	2	2WU	NO	NO	1.324	20	1,295	200	2.65		1,893	127	400	200	1.30	4
TOTAL FOR MAP NO. 2										**1.324**		**1,295**	**200**	**2.65**		**1,893**	**127**	**400**	**200**	**1.30**	**4**
2016CPT.02.27.20071.3	Beaufort	3	SR 1621	FROM SR 1626 TO JOINT AT SR 1624	1	2	2WU	NO	NO	0.868	20	850	200	1.74	115	1,285	86	200	80	0.85	4
TOTAL FOR MAP NO. 3										**0.868**		**850**	**200**	**1.74**	**115**	**1,285**	**86**	**200**	**80**	**0.85**	**4**
TOTAL FOR PROJ NO. 2016CPT.02.27.20071.3										**4.907**		**4,800**	**700**	**9.82**	**255**	**7,132**	**478**	**1,600**	**680**	**4.75**	**12**
GRAND TOTAL										**4.907**		**4,800**	**700**	**9.82**	**255**	**7,132**	**478**	**1,600**	**680**	**4.75**	**12**

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT	COUNTY	MAP	ROUTE	DESCRIPTION	TYP	LANES	LANE TYPE	LENGTH	WIDTH	4413000000-E WORK ZONE ADVANCE/GENERAL WARNING SIGNING	4457000000-N TEMPORARY TRAFFIC CONTROL
NO		NO			NO					SF	LS
2016CPT.02.27.20071.3	Beaufort	1	SR 1625	FROM JOINT AT NC 99 TO SR 1626	1	2	2WU	2.715	20.5	305	0.55
TOTAL FOR MAP NO. 1								**2.715**		**305**	**0.55**
2016CPT.02.27.20071.3	Beaufort	2	SR 1626	FROM SR 1625 TO SR 1621	1	2	2WU	1.324	20	148	0.27
TOTAL FOR MAP NO. 2								**1.324**		**148**	**0.27**
2016CPT.02.27.20071.3	Beaufort	3	SR 1621	FROM SR 1626 TO JOINT AT SR 1624	1	2	2WU	0.868	20	98	0.18
TOTAL FOR MAP NO. 3								**0.868**		**98**	**0.18**
TOTAL FOR PROJ NO. 2016CPT.02.27.20071.3								**4.907**		**551**	**1.00**
GRAND TOTAL								**4.907**		**551**	**1.00**

$$$$$$$SYSTIME$$$$$
$$$$$$$USERNAME$$$$$
$$$$$$$DGN$$$$$$$$$$$$$$$$$$$$$