



**PAVEMENT TIE-IN DETAIL**

PAVEMENT SCHEDULE	
C1	PROP. APPROX. 1.25" ASPHALT CONCRETE SURFACE COURSE, TYPE SF9.5A, AT AN AVERAGE RATE OF 138 LBS. PER SQ. YD.
F1	ASPHALT SURFACE TREATMENT, MAT COAT WITH #6M STONE
S	AGGREGATE SHOULDER BORROW
U	EXISTING PAVEMENT.