| PROJECT REFERENCE NO. | SHEET NO |
|-----------------------|----------|
| B-4751 | /A |

ROADWAY DESIGN 020111

EFF. 01-17-2012

REV. 10-30-2012

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

GENERAL NOTES:

GRADING AND SURFACING:

THE GRADE LINES SHOWN DENOTE THE FINISHED ELEVATION OF THE PROPOSED SURFACING AT GRADE POINTS SHOWN ON THE TYPICAL SECTIONS. GRADE LINES MAY BE ADJUSTED AT THEIR BEGINNING AND ENDING AND AT STRUCTURES AS DIRECTED BY THE ENGINEER IN ORDER TO SECURE A PROPER TIE-IN.

2012 SPECIFICATIONS

EFFECTIVE: 01-17-2012

REVISED: 10-31-2014

CLEARING:

CLEARING ON THIS PROJECT SHALL BE PERFORMED TO THE LIMITS ESTABLISHED BY METHOD III.

SUPERELEVATION:

ALL CURVES ON THIS PROJECT SHALL BE SUPERELEVATED IN ACCORDANCE WITH STD. NO. 225.04 USING THE RATE OF SUPERELEVATION AND RUNOFF SHOWN ON THE PLANS. SUPERELEVATION IS TO BE REVOLVED ABOUT THE GRADE POINTS SHOWN ON THE TYPICAL SECTIONS.

SHOULDER CONSTRUCTION:

ASPHALT, EARTH, AND CONCRETE SHOULDER CONSTRUCTION ON THE HIGH SIDE OF SUPERELEVATED CURVES SHALL BE IN ACCORDANCE WITH STD. NO. 560.01

SIDE ROADS:

THE CONTRACTOR WILL BE REQUIRED TO DO ALL NECESSARY WORK TO PROVIDE SUITABLE CONNECTIONS WITH ALL ROADS, STREETS, AND DRIVES ENTEREING THIS PROJECT. THIS WORK WILL BE PAID FOR AT THE CONTRACT UNIT PRICE FOR THE PARTICULAR ITEMS INVOL VED.

GUARDRAIL:

THE GUARDRAIL LOCATIONS SHOWN ON THE PLANS MAY BE ADJUSTED DURING CONSTRUCTION AS DIRECTED BY THE ENGINEER. THE CONTRACTOR SHOULD CONSULT WITH THE ENGINEER PRIOR TO ORDERING GUARDRAIL MATERIAL.

TEMPORARY SHORING:

SHORING REQUIRED FOR THE MAINTENANCE OF TRAFFIC WILL BE PAID FOR AS "EXTRA WORK" IN ACCORDANCE WITH SECTION 104-7.

SUBSURFACE PLANS:

NO SUBSURFACE PLANS ARE AVAILABLE ON THIS PROJECT. THE CONTRACTOR SHOULD MAKE HIS OWN INVESTIGATION AS TO THE SUBSURFACE CONDITIONS.

END BENTS:

THE ENGINEER SHALL CHECK THE STRUCTURE END BENT PLANS, DETAILS, AND CROSS-SECTION PRIOR TO SETTING OF THE SLOPE STAKES FOR THE EMBANKMENT OR EXCAVATION APPROACHING A BRIDGE.

UTILITIES:

UTILITY OWNERS ON THIS PROJECT ARE AT&T AND DUKE ENERGY.

ANY RELOCATION OF EXISTING UTILITIES WILL BE ACCOMPLISHED BY OTHERS.

RIGHT-OF-WAY MARKERS:

ALL RIGHT-OF-WAY MARKERS ON THIS PROJECT SHALL BE PLACED BY OTHERS.

INDEX OF SHEETS

SHEET

TITLE SHEET

SHEET NUMBER

1 A INDEX OF SHEETS, GENERAL NOTES, AND

LIST OF STANDARD DRAWINGS

1B CONVENTIONAL SYMBOLS

1C-1 THRU 1C-2 SURVEY CONTROL SHEETS

2A-1 PAVEMENT SCHEDULE AND TYPICAL SECTIONS

3B-1 PAVEMENT REMOVAL SUMMARY, SUMMARY OF EARTHWORK, SHOULDER BERM GUTTER, AND

GUARDRAIL SUMMARY

PAVEMENT MARKING PLAN

CROSS-SECTION SUMMARY SHEET

CROSS-SECTIONS

3D-1 SUMMARY OF PIPE 48" AND UNDER

3G-1 GEOTECHNICAL SUMMARIES

PLAN AND PROFILE SHEET

TMP-1 THRU TMP-3 TRAFFIC MANAGEMENT PLANS

PMP-1

X-1

X-2 THRU X-8

EC-1 THRU EC-5 EROSION CONTROL PLANS

SIGN-1 SIGNING PLAN

UO-1 THRU UO-2 UTILITY BY OTHERS PLANS

STRUCTURE PLANS S-1 THRU S-19

2012 ROADWAY ENGLISH STANDARD DRAWINGS

The following Roadway Standards as appear in "Roadway Standard Drawings" Highway Design Branch - N. C. Department of Transportation - Raleigh, N. C., Dated January, 2012 are applicable to this project and by reference hereby are considered a part of these plans:

STD.NO. TITLE

DIVISION 2 - EARTHWORK

200.03 Method of Clearing - Method III

225.02 Guide for Grading Subgrade - Secondary and Local

225.04 Method of Obtaining Superelevation - Two Lane Pavement

DIVISION 3 - PIPE CULVERTS

300.01 Method of Pipe Installation

DIVISION 4 - MAJOR STRUCTURES

422.11 Reinforced Bridge Approach Fills - Sub Regional Tier

DIVISION 5

560.01 Method of Shoulder Construction - High Side of Superelevated Curve - Method I

DIVISION 6 - ASPHALT BASES AND PAVEMENTS

654.01 Pavement Repairs

DIVISION 8 - INCIDENTALS

840.00 Concrete Base Pad for Drainage Structures

840.25 Anchorage for Frames - Brick or Concrete or Precast

840.29 Frames and Narrow Slot Flat Grates

840.35 Traffic Bearing Grated Drop Inlet – for Cast Iron Double Frame and Grates

840.46 Traffic Bearing Precast Drainage Structure

840.66 Drainage Structure Steps

846.01 Concrete Curb, Gutter and Curb & Gutter

846.04 Drop Inlet Installation in Shoulder Berm Gutter

862.01 Guardrail Placement

862.02 Guardrail Installation

862.03 Structure Anchor Units

Rip Rap in Channels

876.02 Guide for Rip Rap at Pipe Outlets