

PROJECT NO.	SHEET NO.	TOTAL NO.
I-5784	12	
53025.3.1		

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	UNDERCUT EXCAVATION CY	REMOVAL EXISTING CONCRETE SLABS SY	GEOTEXTILE FOR SOIL STABILIZATION SY	AGGREGATE BASE COURSE TONS	1" MILLING SY	0" TO 1.5" MILLING SY	INCIDENTAL MILLING SY	BASE COURSE, B25.0C TONS	INTERMEDIATE COURSE, I19.0C TONS	SURFACE COURSE, S9.5C TONS	ASPHALT CONC SURFACE COURSE, TYPE S9.5D TON	ASPHALT BINDER FOR PLANT MIX TONS	POLYMER MODIFIED ASPHALT BINDER FOR PLANT MIX TONS	OGAFC, TYPE FC-1 MOD TON	OGAFC, TYPE FC-2 MOD TON	SEALING EXISTING PAVEMENT LB	MILLED RUMBLE STRIPS LF	DROP INLET REPAIR EA	5" MONOLITHIC CONCRETE ISLAND SY	PORTABLE LIGHTING LS	INDUCTIVE LOOP LF							
53025.3.1	Johnston	1	I-95 NORTHBOUND	FROM MM 84 TO US 70 BRIDGE		2	MD	YES	NO	12.8	32	500.00	500.00	500.00	425	240,299	5,500	888	200	100		19,002	14	1,726		10,533		135,170	20		1								
TOTAL FOR MAP NO. 1										12.8		500.00	500.00	500.00	425	240,299	5,500	888	200	100		19,002	14	1,726		10,533		135,170	20										
53025.3.1	Johnston	2	I-95 SOUTHBOUND	US HWY 70 TO MM84		2	MD	YES	NO	12.8	32	500.00	500.00	500.00	425	240,299	5,500	888	200	100		20,264	14	1,816		10,835		135,170				*							
TOTAL FOR MAP NO. 2										12.8		500.00	500.00	500.00	425	240,299	5,500	888	200	100		20,264	14	1,816		10,835		135,170											
53025.3.1	Johnston	3	NORTHBOUND EXIT RAMP	I-95 TO US HWY 70		2		NO	NO	0.379	22										413		24	1	10							*	200						
TOTAL FOR MAP NO. 3										0.379											413		24	1	10													200	
53025.3.1	Johnston	4	NORTHBOUND ENTRANCE LOOP	US HWY 70 TO NB I-95		2		NO	NO	0.341	22										372		22	1	10							*							
TOTAL FOR MAP NO. 4										0.341											372		22	1	10														
53025.3.1	Johnston	5	NORTHBOUND ENTRANCE RAMP	US HWY 70 TO NB I-95		2		NO	NO	0.379	22										4,892		16	1	10							*							
TOTAL FOR MAP NO. 5										0.379											4,892		16	1	10														
53025.3.1	Johnston	6	SOUTHBOUND EXIT RAMP	I-95 SB TO US HWY 70		2		NO	NO	0.379	22										413		24	1	10							*	200						
TOTAL FOR MAP NO. 6										0.379											413		24	1	10													200	
53025.3.1	Johnston	7	SOUTHBOUND ENTRANCE LOOP	US HWY 70 TO SB I-95		2		NO	NO	0.36	22										4,646		23	1	10							*							
TOTAL FOR MAP NO. 7										0.36											4,646		23	1	10														
53025.3.1	Johnston	8	SOUTHBOUND ENTRANCE RAMP	US HWY 70 TO SB I-95		2		NO	NO	0.322	22										4,156		21	1	10							*							
TOTAL FOR MAP NO. 8										0.322											4,156		21	1	10														
53025.3.1	Johnston	9	NORTHBOUND EXIT RAMP	I-95 TO US HWY 70 BUS		2		NO	NO	0.492	22										6,350		32	1	10			11,610				1,466.00	*						
TOTAL FOR MAP NO. 9										0.492											6,350		32	1	10			11,610						1,466.00					
53025.3.1	Johnston	10	NORTHBOUND ENTRANCE LOOP	US HWY 70 BUS TO I-95 NB		2		NO	NO	0.398	22										5,137		26	1	10			28,240				471.00	*						
TOTAL FOR MAP NO. 10										0.398											5,137		26	1	10			28,240						471.00					
53025.3.1	Johnston	11	NORTHBOUND ENTRANCE RAMP	US HWY 70 BUS TO I-95 NB		2		NO	NO	0.322	22										4,156		21	1	10							*							
TOTAL FOR MAP NO. 11										0.322											4,156		21	1	10														
53025.3.1	Johnston	12	SOUTHBOUND ENTRANCE RAMP	US HWY 70 BUS TO I-95 SB		2		NO	NO	0.379	22										4,892		24	1	10							22.00	*						
TOTAL FOR MAP NO. 12										0.379											4,892		24	1	10										22.00				
53025.3.1	Johnston	13	NORTHBOUND ENTRANCE RAMP	SR 1007 TO I-95 NB		2		NO	NO	0.455	22										5,873		29	1	10							419.00	*						
TOTAL FOR MAP NO. 13										0.455											5,873		29	1	10									419.00					
53025.3.1	Johnston	14	NORTHBOUND EXIT LOOP	I-95 NB TO SR 1007		2		NO	NO	0.322	22										4,156		21	1	10							*							
TOTAL FOR MAP NO. 14										0.322											4,156		21	1	10														
53025.3.1	Johnston	15	SOUTHBOUND EXIT LOOP	I-95 SB TO SR1007		2		NO	NO	0.303	22										3,911		19	1	10							*							
TOTAL FOR MAP NO. 15										0.303											3,911		19	1	10														
53025.3.1	Johnston	16	SOUTHBOUND ENTRANCE RAMP	SR1007 TO I-95 SB		2		NO	NO	0.417	22										5,382		27	1	10							262.00	*						
TOTAL FOR MAP NO. 16										0.417											5,382		27	1	10									262.00					
53025.3.1	Johnston	17	NORTHBOUND EXIT RAMP	I-95 NB TO US HWY 701		2		NO	NO	0.208	22										2,685		13	1	10			3,180				98.63	*						
TOTAL FOR MAP NO. 17										0.208											2,685		13	1	10			3,180						98.63					
53025.3.1	Johnston	18	NORTHBOUND ENTRANCE RAMP	SR 1009 TO I-95 NB		2		NO	NO	0.303	22										3,911		19	1	10							510.00	*						
TOTAL FOR MAP NO. 18										0.303											3,911		19	1	10									510.00					
53025.3.1	Johnston	19	SOUTHBOUND EXIT LOOP	I-95 SB TO US HWY 301 / 701		2		NO	NO	0.36	22										4,646		23	1	10							*							
TOTAL FOR MAP NO. 19										0.36											4,646		23	1	10														
53025.3.1	Johnston	20	SOUTHBOUND ENTRANCE RAMP	US HWY 301 TO I-95 SB		2		NO	NO	0.448	22										5,782		29	2	40			11,070				737.00	*						
TOTAL FOR MAP NO. 20										0.448											5,782		29	2	40			11,070						737.00					
53025.3.1	Johnston	21	SOUTHBOUND EXIT RAMP	I-95 SB TO SR 1178		2		NO	NO	0.322	22										4,156		21	1	10							*							
TOTAL FOR MAP NO. 21										0.322											4,156		21	1	10														
53025.3.1	Johnston	22	SOUTHBOUND ENTRANCE RAMP	SR 1178 TO I-95 SB		2		NO	NO	0.379	22										4,892		24	1	10							*							
TOTAL FOR MAP NO. 22										0.379											4,892		24	1	10														
53025.3.1	Johnston	23	NORTHBOUND EXIST RAMP	I-95 NB TO SR 1178		2		NO	NO	0.398	22										5,137		26	1	10							*							
TOTAL FOR MAP NO. 23										0.398											5,137		26	1	10														
53025.3.1	Johnston	24	NORTHBOUND ENTRANCE RAMP	SR 1178 TO I-95 NB		2		NO	NO	0.341	22										4,401		22	1	10							*							
TOTAL FOR MAP NO. 24										0.341											4,401		22	1	10														
TOTAL FOR PROJ NO. 53025.3.1										33.607							1,000	1,000	1,000	850	583,944	11,000	1,776	400	200		8,591	39,266	534	3,565	250	21,368	54,100	270,340	20	3,985.63	1	400	
GRAND TOTAL										33.607							1,000	1,000	1,000	850	583,944	11,000	1,776	400	200		8,591	39,266	534	3,565	250	21,368	54,100	270,340	20	3,985.63	1	400	