PROJECT NO.	SHEET NO.	TOTAL NO.
I-5784	13	
53025.3.1		

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	4405000000-E PORTABLE WORK ZONE SIGN SF	4410000000-E BARRICADE MOUNTED WORK ZONE SIGN SF	4415000000-E FLASHING ARROW BOARD EA	4420000000-E PORTABLE CHANGEABLE MESSAGE BOARD EA	4422000000-E PORTABLE CHANGEABLE MESSAGE SIGN (SHORT TERM) DAY	4430000000-E DRUMS EA	4445000000-E TYPE III BARICADE LF	4480000000-N TMA EA	4510000000-N LAW ENFORCEMENT HR	4516000000-N SKINNY DRUMS EA	468800000-E 6" X 90 M YELLOW THERMO LF	468800000-E 6" X 90 M WHITE THERMO LF	4695000000-E 8" X 90 M WHITE THERMO LF	4700000000-E 12" X 90 M WHITE THERMO LF	4710000000-E 24" X 120 M WHITE THERMO LF	4725000000-E THERMO LT ARROW 90 M EA	4725000000-E THERMO RT ARROW 90 M EA	4725000000-E THERMO MERGE ARROW 90 M EA	4725000000-E THERMO RT ARROW 90 M EA	4725000000-E THERMO STR & LT ARROW 90 M EA	4815000000-E 6" WHITE PAINT TEMP LF	4815000000-E 6" YELLOW PAINT TEMP LF	4820000000-E 8" WHITE PAINT TEMP LF	4825000000-E 12" WHITE PAINT TEMP LF	4835000000-E 24" WHITE PAINT TEMP LF	4845000000-N PAINT LT ARROW TEMP EA	4845000000-N PAINT RT ARROW TEMP EA	4845000000-N PAINT MERGE ARROW TEMP EA	4845000000-N PAINT STR & LT ARROW TEMP EA	4905000000-N SNOW PLOWABLE MARKERS EA
53025.3.1	Johnston	1	I-95 NORTHBOUND	FROM MM 84 TO US 70 BRIDGE	1	2	MD	12.8	32	925	85	4	8	87	540	64	2	1,832	80	68,000	85,000										85,000	68,000								850
TOTAL FOR MAP NO. 1								**12.8**		**925**	**85**	**4**	**8**	**87**	**540**	**64**	**2**	**1,832**	**80**	**68,000**	**85,000**										**85,000**	**68,000**								**850**
53025.3.1	Johnston	2	I-95 SOUTHBOUND	US HWY 70 TO MM84	1	2	MD	12.8	32											68,000	85,000										85,000	68,000								850
TOTAL FOR MAP NO. 2								**12.8**												**68,000**	**85,000**										**85,000**	**68,000**								**850**
53025.3.1	Johnston	3	NORTHBOUND EXIT RAMP	I-95 TO US HWY 70	2	2		0.379	22											2,200	2,200	40	600	50	1	1				2,200	2,200	40	600	50	1	1			14
TOTAL FOR MAP NO. 3								**0.379**												**2,200**	**2,200**	**40**	**600**	**50**	**1**	**1**				**2,200**	**2,200**	**40**	**600**	**50**	**1**	**1**			**14**
53025.3.1	Johnston	4	NORTHBOUND ENTRANCE LOOP	US HWY 70 TO NB I-95	2	2		0.341	22											1,800	1,800		510				3			1,800	1,800		510				3		
TOTAL FOR MAP NO. 4								**0.341**												**1,800**	**1,800**		**510**				**3**			**1,800**	**1,800**		**510**				**3**		
53025.3.1	Johnston	5	NORTHBOUND ENTRANCE RAMP	US HWY 70 TO NB I-95	2	2		0.379	22											2,000	2,000		540				3			2,000	2,000		540				3		
TOTAL FOR MAP NO. 5								**0.379**												**2,000**	**2,000**		**540**				**3**			**2,000**	**2,000**		**540**				**3**		
53025.3.1	Johnston	6	SOUTHBOUND EXIT RAMP	I-95 SB TO US HWY 70	2	2		0.379	22											2,000	2,000		600	50				2	2	2,000	2,000		600	50		2		2	
TOTAL FOR MAP NO. 6								**0.379**												**2,000**	**2,000**		**600**	**50**				**2**	**2**	**2,000**	**2,000**		**600**	**50**		**2**		**2**	
53025.3.1	Johnston	7	SOUTHBOUND ENTRANCE LOOP	US HWY 70 TO SB I-95	2	2		0.36	22											1,900	1,900		600				3			1,900	1,900		600				3		
TOTAL FOR MAP NO. 7								**0.36**												**1,900**	**1,900**		**600**				**3**			**1,900**	**1,900**		**600**				**3**		
53025.3.1	Johnston	8	SOUTHBOUND ENTRANCE RAMP	US HWY 70 TO SB I-95		2		0.322	22											1,700	1,700		520				3			1,700	1,700		520				3		
TOTAL FOR MAP NO. 8								**0.322**												**1,700**	**1,700**		**520**				**3**			**1,700**	**1,700**		**520**				**3**		
53025.3.1	Johnston	9	NORTHBOUND EXIT RAMP	I-95 TO US HWY 70 BUS	2	2		0.492	22											2,600	2,600	40	600	32						2,600	2,600	40	600	32					14
TOTAL FOR MAP NO. 9								**0.492**												**2,600**	**2,600**	**40**	**600**	**32**						**2,600**	**2,600**	**40**	**600**	**32**					**14**
53025.3.1	Johnston	10	NORTHBOUND ENTRANCE LOOP	US HWY 70 BUS TO I-95 NB	2	2		0.398	22											2,100	2,100		340				3			2,100	2,100		340				3		
TOTAL FOR MAP NO. 10								**0.398**												**2,100**	**2,100**		**340**				**3**			**2,100**	**2,100**		**340**				**3**		
53025.3.1	Johnston	11	NORTHBOUND ENTRANCE RAMP	US HWY 70 BUS TO I-95 NB	2	2		0.322	22											1,700	1,700		530				3			1,700	1,700		530				3		
TOTAL FOR MAP NO. 11								**0.322**												**1,700**	**1,700**		**530**				**3**			**1,700**	**1,700**		**530**				**3**		
53025.3.1	Johnston	12	SOUTHBOUND ENTRANCE RAMP	US HWY 70 BUS TO I-95 SB	2	2		0.379	22											2,000	2,000						3			2,000	2,000						3		
TOTAL FOR MAP NO. 12								**0.379**												**2,000**	**2,000**						**3**			**2,000**	**2,000**						**3**		
53025.3.1	Johnston	13	NORTHBOUND ENTRANCE RAMP	SR 1007 TO I-95 NB	2	2		0.455	22											2,400	2,400		400				3			2,400	2,400		400				3		
TOTAL FOR MAP NO. 13								**0.455**												**2,400**	**2,400**		**400**				**3**			**2,400**	**2,400**		**400**				**3**		
53025.3.1	Johnston	14	NORTHBOUND EXIT LOOP	I-95 NB TO SR 1007	2	2		0.322	22											1,700	1,780	40		25						1,780	1,700	40		25					14
TOTAL FOR MAP NO. 14								**0.322**												**1,700**	**1,780**	**40**		**25**						**1,780**	**1,700**	**40**		**25**					**14**
53025.3.1	Johnston	15	SOUTHBOUND EXIT LOOP	I-95 SB TO SR1007	2	2		0.303	22											1,600	2,060	40	250	20						2,060	1,600	40	250	20					14
TOTAL FOR MAP NO. 15								**0.303**												**1,600**	**2,060**	**40**	**250**	**20**						**2,060**	**1,600**	**40**	**250**	**20**					**14**
53025.3.1	Johnston	16	SOUTHBOUND ENTRANCE RAMP	SR1007 TO I-95 SB	2	2		0.417	22											2,200	2,200		360				3			2,200	2,200		360				3		
TOTAL FOR MAP NO. 16								**0.417**												**2,200**	**2,200**		**360**				**3**			**2,200**	**2,200**		**360**				**3**		
53025.3.1	Johnston	17	NORTHBOUND EXIT RAMP	I-95 NB TO US HWY 701	2	2		0.208	22											1,100	1,100	40	425	50						1,100	1,100	40	425	50					14
TOTAL FOR MAP NO. 17								**0.208**												**1,100**	**1,100**	**40**	**425**	**50**						**1,100**	**1,100**	**40**	**425**	**50**					**14**
53025.3.1	Johnston	18	NORTHBOUND ENTRANCE RAMP	SR 1009 TO I-95 NB	2	2		0.303	22											1,600	1,600		500				3			1,600	1,600		500				3		
TOTAL FOR MAP NO. 18								**0.303**												**1,600**	**1,600**		**500**				**3**			**1,600**	**1,600**		**500**				**3**		
53025.3.1	Johnston	19	SOUTHBOUND EXIT LOOP	I-95 SB TO US HWY 301 / 701	2	2		0.36	22											2,200	2,200	40	280							2,200	2,200	40	280						14
TOTAL FOR MAP NO. 19								**0.36**												**2,200**	**2,200**	**40**	**280**							**2,200**	**2,200**	**40**	**280**						**14**
53025.3.1	Johnston	20	SOUTHBOUND ENTRANCE RAMP	US HWY 301 TO I-95 SB	2	2		0.448	22											2,400	2,400		480				3			2,400	2,400		480				3		
TOTAL FOR MAP NO. 20								**0.448**												**2,400**	**2,400**		**480**				**3**			**2,400**	**2,400**		**480**				**3**		
53025.3.1	Johnston	21	SOUTHBOUND EXIT RAMP	I-95 SB TO SR 1178	2	2		0.322	22											1,700	1,700	40	730	55						1,700	1,700	40	730	55					14
TOTAL FOR MAP NO. 21								**0.322**												**1,700**	**1,700**	**40**	**730**	**55**						**1,700**	**1,700**	**40**	**730**	**55**					**14**
53025.3.1	Johnston	22	SOUTHBOUND ENTRANCE RAMP	SR 1178 TO I-95 SB	2	2		0.379	22											2,000	2,000		460				3			2,000	2,000		460				3		
TOTAL FOR MAP NO. 22								**0.379**												**2,000**	**2,000**		**460**				**3**			**2,000**	**2,000**		**460**				**3**		
53025.3.1	Johnston	23	NORTHBOUND EXIST RAMP	I-95 NB TO SR 1178	2	2		0.398	22											2,100	2,100	40	700							2,100	2,100	40	700						14
TOTAL FOR MAP NO. 23								**0.398**												**2,100**	**2,100**	**40**	**700**							**2,100**	**2,100**	**40**	**700**						**14**
53025.3.1	Johnston	24	NORTHBOUND ENTRANCE RAMP	SR 1178 TO I-95 NB	2	2		0.341	22											1,800	1,800		510				3			1,800	1,800		510				3		
TOTAL FOR MAP NO. 24								**0.341**												**1,800**	**1,800**		**510**				**3**			**1,800**	**1,800**		**510**				**3**		
TOTAL FOR PROJ NO. 53025.3.1								**33.607**		**925**	**85**	**4**	**8**	**87**	**540**	**64**	**2**	**1,832**	**80**	**178,800**	**213,340**	**320**	**9,935**	**282**	**1**	**1**	**39**	**2**	**2**	**213,340**	**178,800**	**320**	**9,935**	**282**	**1**	**3**	**39**	**2**	**1,812**
																				392,140							**45**			**392,140**						**45**		
GRAND TOTAL								**33.607**		**925**	**85**	**4**	**8**	**87**	**540**	**64**	**2**	**1,832**	**80**	**178,800**	**213,340**	**320**	**9,935**	**282**	**1**	**1**	**39**	**2**	**2**	**213,340**	**178,800**	**320**	**9,935**	**282**	**1**	**3**	**39**	**2**	**1,812**
																				392,140							**45**			**392,140**						**45**		