

PROJECT NO.	SHEET NO.	TOTAL NO.
2016CPT.08.11.20621, 2016CPT.08.11.10771 2016CPT.08.11.20771,	10	

### SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	AGGREGATE SHOULDER BORROW TON	SHOULDER RECONSTRUCTION SMI	1.5" MILLING SY	1.25" MILLING SY	INCIDENTAL MILLING SY	SURFACE COURSE, S9.5B TONS	SURFACE COURSE, SF9.5A TONS	ASPHALT BINDER FOR PLANT MIX TONS	PATCHING EXISTING PAVEMENT TONS	ASPHALT SURFACE TREATMENT, SINGLE SEAL SY	EMULSION FOR ASPHALT SURFACE TREATMENT GAL	
2016CPT.08.11.20621	Montgomery	1	SR 1318 (SHILOH CHURCH RD)	FROM SR 1138 (SHILOH RD) TO S JT. OF BRIDGE# 130	1	2	2WU	NO	NO	1.281	24					267	1,675		101		18,100.00	6,350	
<b>TOTAL FOR MAP NO. 1</b>										<b>1.281</b>						<b>267</b>	<b>1,675</b>		<b>101</b>		<b>18,100.00</b>	<b>6,350</b>	
2016CPT.08.11.20621	Montgomery	2	SR 1318 (SHILOH CHURCH RD)	FROM PAVEMENT JT. N OF BRIDGE# 130 TO PAVEMENT JT. N OF SR 1319 (CORBETT RD)	1	2	2WU	NO	NO	0.257	22					300	310		19		3,300.00	1,200	
<b>TOTAL FOR MAP NO. 2</b>										<b>0.257</b>						<b>300</b>	<b>310</b>		<b>19</b>		<b>3,300.00</b>	<b>1,200</b>	
2016CPT.08.11.20621	Montgomery	3	SR 1118 (HAYWOOD RD)	FROM NC HWY 73 TO SR 1115 (GADDY FARM RD)	1	2	2WU	NO	NO	1.823	21			233		760	2,090		125		22,500.00	7,900	
<b>TOTAL FOR MAP NO. 3</b>										<b>1.823</b>				<b>233</b>		<b>760</b>	<b>2,090</b>		<b>125</b>		<b>22,500.00</b>	<b>7,900</b>	
<b>TOTAL FOR PROJ NO. 2016CPT.08.11.20621</b>										<b>3.361</b>				<b>233</b>		<b>1,327</b>	<b>4,075</b>		<b>245</b>		<b>43,900.00</b>	<b>15,450</b>	
2016CPT.08.11.10771	Richmond	4	US 1	FROM PVT. JOINT 0.44 MI SOUTH OF THE BEGINNING OF 3 LANE SECTION TO PVT. JOINT 0.32 MILES SOUTH OF SR 1001 (MARSTON RD)	2	2	MU	NO	NO	3.5	36	1,070.00	7.00				7,070		424		76,460.00	26,765	
<b>TOTAL FOR MAP NO. 4</b>										<b>3.5</b>		<b>1,070.00</b>	<b>7.00</b>				<b>7,070</b>		<b>424</b>		<b>76,460.00</b>	<b>26,765</b>	
<b>TOTAL FOR PROJ NO. 2016CPT.08.11.10771</b>										<b>3.5</b>		<b>1,070.00</b>	<b>7.00</b>				<b>7,070</b>		<b>424</b>		<b>76,460.00</b>	<b>26,765</b>	
2016CPT.08.11.20771	Richmond	5	SR 1005 (CARTLEDGE CREEK RD)	FROM SR 1303 (DAVE KINGS RD) TO SR 1307 (BURTON RD)	3	2	2WU	NO	NO	2.6	22	740.00	5.20			700	3,400		204	90			
<b>TOTAL FOR MAP NO. 5</b>										<b>2.6</b>		<b>740.00</b>	<b>5.20</b>			<b>700</b>	<b>3,400</b>		<b>204</b>	<b>90</b>			
2016CPT.08.11.20771	Richmond	6	SR 1665 (COLLEGE DR)	FROM US 74 BUS. TO US 74 BUS.	4.5	2	2WU	NO	NO	0.62	32	300.00	1.07		3,055	100		870	58				
<b>TOTAL FOR MAP NO. 6</b>										<b>0.62</b>		<b>300.00</b>	<b>1.07</b>		<b>3,055</b>	<b>100</b>		<b>870</b>	<b>58</b>				
<b>TOTAL FOR PROJ NO. 2016CPT.08.11.20771</b>										<b>3.22</b>		<b>1,040.00</b>	<b>6.27</b>		<b>3,055</b>	<b>800</b>	<b>3,400</b>	<b>870</b>	<b>262</b>	<b>90</b>			
<b>GRAND TOTAL</b>										<b>10.081</b>		<b>2,110.00</b>	<b>13.27</b>		<b>233</b>	<b>3,055</b>	<b>2,127</b>	<b>14,545</b>	<b>870</b>	<b>931</b>	<b>90</b>	<b>120,360.00</b>	<b>42,215</b>