

PROJECT NO.	SHEET NO.	TOTAL NO.
2016CPT.08.11.20621, 2016CPT.08.11.10771 2016CPT.08.11.20771,	11	

### THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	441300000-E	445700000-N	468500000-E	468600000-E			469500000-E		469700000-E	471000000-E	472100000-E	472500000-E				490000000-N		490500000-N		
										WORK ZONE ADVANCE/GENERAL WARNING SIGNING	TEMPORARY TRAFFIC CONTROL	4" X 90 M WHITE THERMO	4" X 120 M WHITE THERMO	4" X 120 M YELLOW THERMO	8" X 90 M WHITE THERMO	8" X 90 M YELLOW THERMO	8" X 120 M WHITE THERMO	24" X 120 M WHITE THERMO	THERMO MSG STOP 120 M	THERMO LT ARROW 90 M	THERMO STR ARROW 90 M	THERMO RT ARROW 90 M	YELLOW & YELLOW MARKERS	CRYSTAL & RED MARKERS	SNOW PLOWABLE MARKERS Y & Y MARKERS	SNOW PLOWABLE MARKERS C & R MARKERS			
										SF	LS	LF	LF	LF	LF	LF	LF	EA	EA	EA	EA	EA	EA	EA	EA	EA			
2016CPT.08.11.20621	Montgomery	1	SR 1318 (SHILOH CHURCH RD)	FROM SR 1138 (SHILOH RD) TO S JT. OF BRIDGE# 130	1	2	2WU	1.281	24	150		13,785		13,785															
<b>TOTAL FOR MAP NO. 1</b>										<b>150</b>		<b>13,785</b>		<b>13,785</b>															
2016CPT.08.11.20621	Montgomery	2	SR 1318 (SHILOH CHURCH RD)	FROM PAVEMENT JT. N OF BRIDGE# 130 TO PAVEMENT JT. N OF SR 1319 (CORBETT RD)	1	2	2WU	0.257	22	30	*	2,770		2,770															
<b>TOTAL FOR MAP NO. 2</b>										<b>30</b>		<b>2,770</b>		<b>2,770</b>															
2016CPT.08.11.20621	Montgomery	3	SR 1118 (HAYWOOD RD)	FROM NC HWY 73 TO SR 1115 (GADDY FARM RD)	1	2	2WU	1.823	21	205		19,620		19,620											120				
<b>TOTAL FOR MAP NO. 3</b>										<b>205</b>		<b>19,620</b>		<b>19,620</b>											<b>120</b>				
<b>TOTAL FOR PROJ NO. 2016CPT.08.11.20621</b>										<b>385</b>	<b>1</b>	<b>36,175</b>		<b>36,175</b>											<b>120</b>				
														<b>36,175</b>											<b>120</b>				
2016CPT.08.11.10771	Richmond	4	US 1	FROM PVT. JOINT 0.44 MI SOUTH OF THE BEGINNING OF 3 LANE SECTION TO PVT. JOINT 0.32 MILES SOUTH OF SR 1001 (MARSTON RD)	2	2	MU	3.5	36	392	*	37,500	1,190	38,150	645	235	185	80		74	5					400	81		
<b>TOTAL FOR MAP NO. 4</b>										<b>392</b>		<b>37,500</b>	<b>1,190</b>	<b>38,150</b>	<b>645</b>	<b>235</b>	<b>185</b>	<b>80</b>		<b>74</b>	<b>5</b>				<b>400</b>	<b>81</b>			
<b>TOTAL FOR PROJ NO. 2016CPT.08.11.10771</b>										<b>392</b>	<b>1</b>	<b>37,500</b>	<b>1,190</b>	<b>38,150</b>	<b>645</b>	<b>235</b>	<b>185</b>	<b>80</b>		<b>74</b>	<b>5</b>				<b>400</b>	<b>81</b>			
														<b>39,340</b>		<b>880</b>				<b>79</b>					<b>481</b>				
2016CPT.08.11.20771	Richmond	5	SR 1005 (CARTLEDGE CREEK RD)	FROM SR 1303 (DAVE KINGS RD) TO SR 1307 (BURTON RD)	3	2	2WU	2.6	22	292	*	28,060		26,860											186				
<b>TOTAL FOR MAP NO. 5</b>										<b>292</b>		<b>28,060</b>		<b>26,860</b>											<b>186</b>				
2016CPT.08.11.20771	Richmond	6	SR 1665 (COLLEGE DR)	FROM US 74 BUS. TO US 74 BUS.	4,5	2	2WU	0.62	32	70	*	5,400	1,000	6,625		130		70	12	11		5		63	20				
<b>TOTAL FOR MAP NO. 6</b>										<b>70</b>		<b>5,400</b>	<b>1,000</b>	<b>6,625</b>		<b>130</b>		<b>70</b>	<b>12</b>	<b>11</b>		<b>5</b>		<b>63</b>	<b>20</b>				
<b>TOTAL FOR PROJ NO. 2016CPT.08.11.20771</b>										<b>362</b>		<b>33,460</b>	<b>1,000</b>	<b>33,485</b>		<b>130</b>		<b>70</b>	<b>12</b>	<b>11</b>		<b>5</b>		<b>249</b>	<b>20</b>				
												<b>34,485</b>		<b>130</b>						<b>16</b>			<b>269</b>						
<b>GRAND TOTAL</b>										<b>10,081</b>	<b>1</b>	<b>107,135</b>	<b>2,190</b>	<b>107,810</b>	<b>645</b>	<b>365</b>	<b>185</b>	<b>150</b>	<b>12</b>	<b>85</b>	<b>5</b>	<b>5</b>	<b>369</b>	<b>20</b>	<b>400</b>	<b>81</b>			
													<b>110,000</b>		<b>1,010</b>					<b>95</b>			<b>389</b>		<b>481</b>				