

PROJECT NO.	SHEET NO.	TOTAL NO.
2016CPT.08.12.20471, etc	12	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	BORROW EXCAVATION CY	AGGREGATE SHOULDER BORROW TON	INCIDENTAL STONE BASE TONS	SHOULDER RECONSTRUCTION SMI	1.5" MILLING SY	INCIDENTAL MILLING SY	BASE COURSE, B25.0B TONS	SURFACE COURSE, S9.5B TONS	SURFACE COURSE, SF9.5A TON	ASPHALT BINDER FOR PLANT MIX TONS	PATCHING EXISTING PAVEMENT TONS	ADJ. OF MAN-HOLES EA	ADJ. OF METER OR VALVE BOXES EA	TEMP. SILT FENCE LF	WATTLE LF	SEED & MULCHING AC	
2016CPT.08.12.20471	Hoke	1	SR 1422 (PHILLIPI CHURCH RD)	FROM SR 1432 (GOLF COURSE ROAD) TO SR 1412 (POSEY FARM RD)	1	2	2WU	NO	NO	0.508	22	125			1.02		110	440		575	58	40			105	20	0.74	
2016CPT.08.12.20471	Hoke	2	SR 1302 (DOC BROWN RD)	FROM US 401 TO SR 1303 (SCULL RD)	2	2	2WU	NO	NO	3.735	27.5	2,200		525	7.48		365			5,515	370	75			760	140	5.43	
TOTAL FOR PROJ NO. 2016CPT.08.12.20471										4.243		2,325		525	8.50		475	440		6,090	428	115			865	160	6.17	
2016CPT.08.12.10831	Scotland	3	US 401	FROM DIVIDED HWY TO SR 1424 (SALLY MCNAIR RD)	3	2	2WU	NO	NO	2.3	28					40,375			3,735		224							
2016CPT.08.12.10831	Scotland	4	US 401	FROM END OF WIDENING PASS SR 1407 (AIRBASE RD) TO CONSTRUCTION JOINT AT BRIDGE OVER LUMBER RIVER	3,4	2	MU	NO	NO	2.4	28-54					54,500			5,050		303		6	7				
TOTAL FOR PROJ NO. 2016CPT.08.12.10831										4.7						94,875			8,785		527		6	7				
2016CPT.08.12.20831	Scotland	5	SR 1628 (TARTAN RD)	FROM US 401 TO END OF STATE MAINTENANCE	5	2	2WU	NO	NO	0.93	20-24		261		1.86		100			1,260	84			1				
2016CPT.08.12.20831	Scotland	6	SR 1319 (OLD WIRE RD)	FROM CONSTRUCTION JOINT AT US 74 TO CONSTRUCTION JOINT AT NC 144	6	2	2WU	NO	NO	0.67	24-40		216		1.34		270		925		56			1				
TOTAL FOR PROJ NO. 2016CPT.08.12.20831										1.6			477		3.20		370		925	1,260	140			1				
GRAND TOTAL										10.543		2,325	477	525	11.70	94,875	845	440	9,710	7,350	1,095	115	6	8	865	160	6.17	

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP	LANES	LANE TYPE	LENGTH	WIDTH	4413000000	44570000	4685000000	4686000000-E			4695000000	46970000	4705000000-E	47100000	4721000000-E		4725000000-E		4810000000-E		49000000	4905000000-N		
										WORK ZONE ADVANCE/GENERAL WARNING SIGNING SF	TEMP. TRAFFIC CONTROL LS	4" X 90 M WHITE THERMO LF	4" X 120 M WHITE THERMO LF	4" X 120 M YELLOW THERMO LF	8" X 90 M YELLOW THERMO LF	8" X 120 M WHITE THERMO LF	16" X 120 M WHITE THERMO LF	24" X 120 M WHITE THERMO LF	THERMO MSG SCHOOL 120 M EA	THERMO RXR 120 M EA	THERMO LT ARROW 90 M EA	THERMO RT ARROW 90 M EA	4" YELLOW PAINT LF	4" WHITE PAINT LF	YELLOW & YELLOW MARKERS EA	SNOW PLOWABLE MARKERS EA	SNOW PLOWABLE MARKERS EA		
2016CPT.08.12.20471	Hoke	1	SR 1422 (PHILLIPI CHURCH RD)	FROM SR 1432 (GOLF COURSE ROAD) TO SR 1412 (POSEY FARM RD)	1	2	2WU	0.508	22	57	*	5,365		4,295															
2016CPT.08.12.20471	Hoke	2	SR 1302 (DOC BROWN RD)	FROM US 401 TO SR 1303 (SCULL RD)	2	2	2WU	3.735	27.5	419		39,450		33,550					40										
TOTAL FOR PROJ NO. 2016CPT.08.12.20471								4.243		476		44,815		37,845					40										
2016CPT.08.12.10831	Scotland	3	US 401	FROM DIVIDED HWY TO SR 1424 (SALLY MCNAIR RD)	3	2	2WU	2.3	28	258	*	25,000	450	13,900	100							6			14,000			22	195
2016CPT.08.12.10831	Scotland	4	US 401	FROM END OF WIDENING PASS SR 1407 (AIRBASE RD) TO CONSTRUCTION JOINT AT BRIDGE OVER LUMBER RIVER	3,4	2	MU	2.4	28-54	269	*	21,700	800	17,400	200	220	250	275	12	10	12	7		17,600			80	250	
TOTAL FOR PROJ NO. 2016CPT.08.12.10831								4.7		527		46,700	1,250	31,300	300	220	250	275	12	10	18	7		31,600			102	445	
2016CPT.08.12.20831	Scotland	5	SR 1628 (TARTAN RD)	FROM US 401 TO END OF STATE MAINTENANCE	5	2	2WU	0.93	20-24	105	*	9850		8250													65		
2016CPT.08.12.20831	Scotland	6	SR 1319 (OLD WIRE RD)	FROM CONSTRUCTION JOINT AT US 74 TO CONSTRUCTION JOINT AT NC 144	6	2	2WU	0.67	24-40	76	*	7075	1375	6850	60	50	35		2							56			
TOTAL FOR PROJ NO. 2016CPT.08.12.20831								1.6		181		16,925	1,375	15,100	60	50	35		2							121			
GRAND TOTAL								10.543		1,184	1	108,440	2,625	84,245	300	280	300	350	12	12	18	7		31,600		121	102	445	
GRAND TOTAL													86,870							24	25			31,600			102	547	