

**STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS**

PROJ. REFERENCE NO.	SHEET NO.
B-5396	X-1A
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED	

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
-L- (Phase I) RT		
12+50.00	0	0
13+00.00	10	8
13+50.00	7	19
14+00.00	0	36
14+50.00	0	109
15+00.00	0	212
15+50.00	0	284
16+00.00	1	331
16+50.00	3	418

Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
-L- (Phase I) LT		
12+50.00	0	0
13+00.00	0	20
13+50.00	0	20
14+00.00	0	13

Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
-L- (Phase II) LT		
14+00.00	0	0
14+50.00	0	10
15+00.00	0	10
15+50.00	8	19
16+00.00	28	18
16+50.00	57	4

Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
-L- LT		
17+50.00	0	0
18+00.00	27	12
18+20.00	4	10

Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
-L- RT		
17+50.00	0	0
18+00.00	58	65
18+20.00	26	0

Note: Approximate quantities only. Unclassified Excavation, Fine Grading, Clearing and Grubbing, and Removal of Existing Pavement will be paid for at the contract lump sum price for grading.