R:\Roadway\XSC\nbldet_X-0sheetear.log

PROJ. REFERENCE NO.	SHEET NO.
B-5123	X-1A

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

Approximate quantities only. Unclassified excavation, fine grading, clearing and grubbing, and removal of existing pavement will be paid for at the lump sum price for "Grading".

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

Station Det2	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
12+00.00	0	0
12+25.00	5	51
12+50.00	2	116
12+75.00	1	211
13+00.00	1	316
13+25.00	1	354
13+50.00	1	365
13+75.00	0	440
14+00.00	0	517
14+25.00	0	572
14+33.00	0	190

Station Det2	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
17+23.00	0	0
17+25.00	0	66
17+50.00	0	794
17+75.00	0	613
18+00.00	0	337
18+25.00	0	151
18+50.00	0	74
18+75.00	0	51
19+00.00	2	40
19+25.00	13	20
19+50.00	49	2
19+75.00	89	2
20+00.00	115	2

Station L (Lt)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
13+00.00	0	0
13+50.00	63	0
13+79.27	56	0
14+00.00	33	0
14+50.00	70	0
15+00.00	59	0
15+50.00	25	0
16+00.00	1	0
16+50.00	1	93
17+00.00	0	136
17+50.00	0	106
18+00.00	0	177
18+50.00	0	252
19+00.00	0	307
19+50.00	0	561
20+00.00	0	852
20+29.92	0	731

Station L (Lt)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
22+49.92	0	0
23+00.00	0	310
23+50.00	0	211
24+00.00	0	116
24+50.00	0	42
25+00.00	0	15
25+50.00	44	7
25+75.00	46	2
26+00.00	69	1
26+50.00	156	1
26+97.25	97	0
27+00.00	4	0
27+50.00	81	0
28+00.00	67	4
28+50.00	50	5
29+00.00	36	6
29+50.00	19	8
29+73.38	4	3
30+00.00	4	2

Station Srvrd	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
11+14.00	0	0
11+50.00	18	1
12+00.00	67	2
12+50.00	79	0
13+00.00	71	0
13+50.00	74	0
14+00.00	72	0
14+50.00	69	0
15+00.00	81	0
15+50.00	128	0
16+00.00	93	21
16+50.00	21	30
17+00.00	15	8
17+25.00	2	0

Station L (Rt)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
13+00.00	0	0
13+50.00	5	6
13+79.27	6	3
14+00.00	5	1
14+50.00	17	2
15+00.00	22	0
15+50.00	14	2
16+00.00	3	19
16+50.00	0	52
17+00.00	0	87
17+50.00	0	219
18+00.00	0	350

Station L (Rt)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
18+50.00	0	422
19+00.00	0	543
19+50.00	0	651
20+00.00	0	752
20+38.29	0	631

Station L (Rt)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
22+58.29	0	0
23+00.00	0	976
23+50.00	0	528
24+00.00	0	319
24+50.00	0	187
25+00.00	0	113
25+50.00	0	77
25+75.00	0	27
26+00.00	0	29
26+50.00	0	57
26+97.25	0	55
27+00.00	0	2
28+00.00	3	4
28+50.00	6	9
29+00.00	5	17
29+50.00	5	26
29+73.38	3	10
30+00.00	4	4

Station L (Med)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
13+00.00	0	0
13+50.00	9	6
13+79.27	7	4
14+00.00	4	10
14+50.00	6	41
15+00.00	7	38
15+50.00	6	40
16+00.00	2	53
16+50.00	0	78
17+00.00	0	111
17+50.00	0	145
18+00.00	0	169
18+50.00	0	184
19+00.00	0	191
19+50.00	0	192
20+00.00	0	194
20+34.11	0	133

Station L (Med)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
22+54.11	0	0
23+00.00	0	181
23+50.00	0	167
24+00.00	0	155
24+50.00	0	135
25+00.00	0	120
25+50.00	0	112
25+75.00	0	53
26+00.00	0	51
26+50.00	0	95
26+97.25	1	68
27+00.00	0	2
28+50.00	1	4
29+00.00	2	8
29+50.00	2	9
29+73.38	2	4
30+00.00	4	3

Station L (Shld Lt) (Det2 Remove)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
16+07.46	0	0
17+00.00	52	93
17+50.00	219	95
18+00.00	606	68
18+50.00	724	41
19+00.00	703	19
19+28.54	449	0

Station L (Shld Lt) (Det2 Remove)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
22+18.54	0	0
22+50.00	856	0
23+00.00	869	0
23+50.00	260	6
24+00.00	104	27
24+50.00	37	74
25+00.00	8	136
26+36.01	10	224

INDEX OF SHEETS

LINE	STATIONS	SHEETS
-L- w/-DET-	STA 13+00.00 TO STA 21+50.00	X-1 THRU X-5
-L- w/-DET-	STA 22+00.00 TO STA 30+00.00	X-6 THRU X-9
-SRVRD-	STA 11+50.00 TO STA 17+00.00	X-10 THRU X-13