PROJECT NO.	SHEET NO.	TOTAL NO.
2016CPT.12.05.10181	18	
2016CPT.12.05.20181		

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	AGGREGATE SHOULDER BORROW TON	INCIDENTAL STONE BASE TONS	SHOULDER RECONSTRUCTION SMI	1½" MILLING SY	3" MILLING SY	INCIDENTAL MILLING SY	BASE COURSE, B25.0B TONS	SURFACE COURSE, S9.5B TONS	LEVELING COURSE, S9.5B TONS	SURFACE COURSE, S9.5C TONS	LEVELING COURSE, S9.5C TONS	SURFACE COURSE, SF9.5A TONS	LEVELING COURSE, SF9.5A TON	ASPHALT BINDER FOR PLANT MIX TONS	PATCHING EXISTING PAVEMENT TONS	AST MAT COAT #67 STONE SY	AST MAT COAT #78M STONE SY	EMULSION FOR ASPHALT SURFACE TREATMENT GAL	RETROFIT EXST. CONC. CURB RAMP EA.	CONC. CURB RAMPS EA	DROP INLET EA	MANHOLES EA	METER OR VALVE BOX EA	PORTABLE LIGHTING LS	INDUCTIVE LOOP LF	LEAD-IN CABLE (14-2) LF
2016CPT.12.05.10181	Catawba	1	US70	FROM SR 2959 TO SR 1005	1-6,9	2	MU	NO	NO	2.65	vars.60-84	200		2.30	117,177		500		10,352	800					673	1,200				2		1	10	11	1	7,500	500
2016CPT.12.05.10181	Catawba	2	NC 127	FROM SR 1176 TO SR 2959	6-8,10	2	MU	NO	NO	3.77	vars. 36-60	200	80	2.30	12,000	16,750	5,400		9,710	500					615	1,850				30	1	1	6	7		2,500	250
2016CPT.12.05.10181	Catawba	3	US 321	FROM SR 1361 TO SR 1306	11	2	MD	NO	NO	0.57	vars. 60-72		40		23,732						2,097	100			130	200				2	3				*	1,000	100
2016CPT.12.05.10181	Catawba	4	NC 16	FROM NC 16 BUS. TO SR 1746	12	2	MD	NO	NO	2.28	48				78,342						6,924	300			428	500								1		4,000	400
2016CPT.12.05.10181	Catawba	5	US 321 BUS.	FROM NC 10 TO US 70	8	2	MU	NO	NO	2.70	vars. 60-72						200		8,920	400					561	600							20	20			
TOTAL FOR PROJ NO. 2016CPT.12.05.10181										**11.97**		**400**	**120**	**4.60**	**231,251**	**16,750**	**6,100**		**28,982**	**1,700**	**9,021**	**400**			**2,407**	**4,350**				**34**	**4**	**2**	**36**	**39**	**1**	**15,000**	**1,250**
2016CPT.12.05.20181	Catawba	6	SR 1453 (SPRINGS RD NE)	FROM SR 1516 TO PAVING JT. 150' W. OF SR 1504	14	2	2WU	NO	NO	2.45	24	375	100	4.90			250		3,204	300					212	200	34,496		13,799								
2016CPT.12.05.20181	Catawba	7	SR 1815 (LITTLE MTN. RD)	FROM SR 1849 TO SR 1818	13	2	2WU	NO	NO	3.10	20	475	120	6.20			525	2,950	3,382	775					383	175											
2016CPT.12.05.20181	Catawba	8	SR 1490 (HERMAN SIPE RD)	FROM SR 1007 TO SR 1484	8,14,15	2	2WU	NO	NO	2.43	vars.22-36	375	80	4.88			625		3,157	150					199	325	33,991		13,597								
2016CPT.12.05.20181	Catawba	9	SR 1128 (MTN. GROVE RD)	FROM NC 127 TO SR 1124	7	2	2WU	NO	NO	1.86	20	275	80	3.72			200		2,029	200					135	650								2			
2016CPT.12.05.20181	Catawba	10	SR 1814 (CALDWELL RD)	FROM NC 16 TO SR 1003	7	2	2WU	NO	NO	2.11	20	325	80	4.22			200		2,130	650					170	200											
2016CPT.12.05.20181	Catawba	11	SR 1172 (15TH AVE SE)	FROM CULDESAC TO EOM	16,18	2	2WU	NO	NO	0.58	vars. 18-20		40										375	20	26	50											
2016CPT.12.05.20181	Catawba	12	SR 1680 (22ND ST NE)	FROM SR 1507 TO CUL-DE-SAC	16	2	2WU	NO	NO	0.42	18		40										294	25	21	75											
2016CPT.12.05.20181	Catawba	13	SR 1681 (23RD ST NE)	FROM SR 1683 TO CUL-DE-SAC	16	2	2WU	NO	NO	0.08	18		10										76	5	5	10											
2016CPT.12.05.20181	Catawba	14	SR 1682 (24 ST PL NE)	FROM SR 1574 TO EOM	16	2	2WU	NO	NO	0.22	18		20										141	10	10	25											
2016CPT.12.05.20181	Catawba	15	SR 1683 (40TH AVE CT)	FROM SR 1682 TO CUL-DE-SAC	16	2	2WU	NO	NO	0.22	18		20										165	10	12	25											
2016CPT.12.05.20181	Catawba	16	SR 1574 (25TH ST NE)	FROM SR 1507 TO EOM	16	2	2WU	NO	NO	0.28	19		20										190	10	13	20											
2016CPT.12.05.20181	Catawba	17	SR 1987 (MURRAY LN)	FROM SR 1003 TO EOM	16	2	2WU	NO	NO	0.29	18		20										186	40	15	20											
2016CPT.12.05.20181	Catawba	18	SR 2122 (PEANUTS LN)	FROM SR 2013 TO EOM	17	2	2WU	NO	NO	0.13	18		10										83	10	6	35		1,373	549								
2016CPT.12.05.20181	Catawba	19	SR 2074 (KILLIAN AVE)	FROM SR 2014 TO EOM	16	2	2WU	NO	NO	0.12	20		10										86	20	7	10											
2016CPT.12.05.20181	Catawba	20	SR 2321 (SMITHFIELD DR)	FROM NC 16 TO SR 2357	16	2	2WU	NO	NO	0.10	18		10										64	5	5	10							3	1			
2016CPT.12.05.20181	Catawba	21	SR 2357 (SMITHFIELD DR)	FROM SR 2321 TO CUL-DE-SAC	16	2	2WU	NO	NO	0.16	18		10										103	20	8	10											
2016CPT.12.05.20181	Catawba	22	SR 1130 (DICKINSON RD)	FROM NC 127 TO EOM	19	2	2WU	NO	NO	0.22	18		10										141	5	10	5											
2016CPT.12.05.20181	Catawba	23	SR 2952 (PINEWINDS DR)	FROM NC 127 TO SR 2953	17	2	2WU	NO	NO	0.32	18		20										205	35	16	80		3,379	1,351					1			
2016CPT.12.05.20181	Catawba	24	SR 2953 (SWEETBRIAR LN)	FROM CUL-DE-SAC TO CUL-DE-SAC	17	2	2WU	NO	NO	0.34	18		20										267	35	20	80		4,390	1,756								
2016CPT.12.05.20181	Catawba	25	SR 2964 (GREENFIELD CT)	FROM SR 2953 TO CULDESAC	16	2	2WU	NO	NO	0.05	18		5										54	5	4	5								2			
2016CPT.12.05.20181	Catawba	26	SR 2397 (THOREAU RD)	FROM SR 1515 TO CUL-DE-SAC	17	2	2WU	NO	NO	0.40	19		20										295	5	20	30		4,859	1,944					3			
2016CPT.12.05.20181	Catawba	27	SR 2398 (WORDSWORTH RD)	FROM SR 2397 TO SR 2397	17	2	2WU	NO	NO	0.30	18		20										193	20	14	50		3,168	1,267								
2016CPT.12.05.20181	Catawba	28	SR 1557 (WINEBARGER ST)	FROM SR 1517 TO EOM	17	2	2WU	NO	NO	0.37	20		20										264	40	20	100		4,341	1,737								
2016CPT.12.05.20181	Catawba	29	SR 1996 (HUNSUCKER RD)	FROM SR 1729 TO SR 2638	16	2	2WU	NO	NO	0.36	19		20										244	10	17	30											
2016CPT.12.05.20181	Catawba	30	SR 2463 (BASIL DR)	FROM SR 1996 TO EOM	16	2	2WU	NO	NO	0.05	18		5										32	5	2	5											
2016CPT.12.05.20181	Catawba	31	SR 2638 (RICHARD ST)	FROM SR 1996 TO EOM	16	2	2WU	NO	NO	0.17	18		10										109	5	8	10											
2016CPT.12.05.20181	Catawba	32	SR 1676 (3RD AVE SE)	FROM SR 1468 TO EOM	16,19	2	2WU	NO	NO	0.23	18		10										148	10	10	25								0			
2016CPT.12.05.20181	Catawba	33	SR 1677 (22ND ST CT SE)	FROM SR 1676 TO EOM	19	2	2WU	NO	NO	0.05	18		5										32	5	2	5								1			
2016CPT.12.05.20181	Catawba	34	SR 1469 (5TH AVE SE)	FROM SR 1468 TO EOM	19	2	2WU	NO	NO	0.15	18		10										96	10	7	15											
2016CPT.12.05.20181	Catawba	35	SR 2269 (14TH AVE CIR SE)	FROM SR 1468 TO SR 1468	17,20	2	2WU	NO	NO	0.23	20		20										156	20	12	50		2,669	1,080								
2016CPT.12.05.20181	Catawba	36	SR 2377 (COUNTRY HOLLOW RD)	FROM NC 16 TO CUL-DE-SAC	16	2	2WU	NO	NO	0.08	18		10										76	10	6	20											
TOTAL FOR PROJ NO. 2016CPT.12.05.20181										**17.87**		**1,825**	**875**	**23.92**			**1,800**	**2,950**	**13,902**	**2,075**			**4,075**	**395**	**1,395**	**2,350**	**68,487**	**24,179**	**37,080**				**3**	**10**			
GRAND TOTAL										**29.84**		**2,225**	**995**	**28.52**	**231,251**	**16,750**	**7,900**	**2,950**	**42,884**	**3,775**	**9,021**	**400**	**4,075**	**395**	**3,802**	**6,700**	**68,487**	**24,179**	**37,080**	**34**	**4**	**2**	**39**	**49**	**1**	**15,000**	**1,250**