



PAVEMENT SCHEDULE	
C	PROP. APPROX. 1" ASPHALT CONCRETE SURFACE COURSE, TYPE S 4.75A, TO BE APPLIED AT AN AVERAGE RATE OF 100 LBS PER SQ. YD.
C1	PROP. APPROX. 1 1/2" ASPHALT CONCRETE SURFACE COURSE, TYPE SF9.5A, TO BE APPLIED AT AN AVERAGE RATE OF 165 LBS PER SQ. YD.
C2	PROP. APPROX. 1 3/4" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, TO BE APPLIED AT AN AVERAGE RATE OF 196 LBS PER SQ. YD.
C3	PROP. APPROX. 1 1/2" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5C, TO BE APPLIED AT AN AVERAGE RATE OF 168 LBS PER SQ. YD.
M1	MILL ASPHALT PAVEMENT, 1 1/2" DEPTH
S	SHOULDER RECONSTRUCTION (SEE DETAIL)
U	EXISTING PAVEMENT