PROJECT NO.	SHEET NO.	TOTAL NO.
2016CPT.09.22.10341.1, 2016CPT.09.23.20341.1	16	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	NON-TRACKING HOT APPLIED TACK COAT	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	BORROW EXCAVATION CY	INCIDENTAL STONE BASE TONS	SHOULDER RECONSTRUCTION SMI	FINE MILLING, 5/8"DEPTH SY	FINE MILLING, 7/8"DEPTH SY	MILLING ASPHALT PAVEMENT, 1 1/2"DEPTH SY	MILLING ASPHALT PAVEMENT, 0"TO 1 1/2" DEPTH SY	INCIDENTAL MILLING SY	BASE COURSE, B25.0B TONS	SURFACE COURSE, S9.5B TONS	SURFACE COURSE, S9.5C TONS	SURFACE COURSE, SF9.5A TONS	ASPHALT BINDER FOR PLANT MIX TONS	POLYMER MODIFIED ASPHALT BINDER FOR PLANT MIX TONS	OGAFC, TYPE FC-2 MOD TONS	ULTRA-THIN BONDED WEARING COURSE TON	MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE) LF	DIAMOND GRINDING SY	ADJ. OF MANHOLES EA	ADJ. OF METER OR VALVE BOX EA	PORTABLE LIGHTING LS	TEMPORARY SILT FENCE LF	WATTLE LF
2016CPT.09.22.10341.1	Forsyth	1	US 52/NC 8 NORTH BOUND	BEGIN NORTH BOUND AT PAVEMENT JT. AT EXIT# 110B TO PAVEMENT JT NORTH OF BRIDGE # 247 OVERPASS	1	2	MD	YES	NO	NO	1.006	26				16,452										50		967					1		
		1	US 52/NC 8 SOUTH BOUND	BEGIN SOUTHBOUND AT PAVEMENT JT. NORTH OF BRIDGE # 247 LIBERTY ST. OVERPASS TO PAVEMENT JT. SOUTH OF BRIDGE # 218 OVERPASS	1	2	MD	YES	NO	NO	1.008	26				17,772										54		1,045					*		
TOTAL FOR MAP NO. 1											**2.014**					**34,224**										**104**		**2,012**							
2016CPT.09.22.10341.1	Forsyth	2	I-40 BUS/US421 NORTH BOUND	NORTHBOUND FROM BRIDGE #264 OVER CRAFTON ST. TO GRASS GORE AT I-40 WEST BOUND/US421 NORTH BOUND RAMP EXIT 1	2	2	MD	YES	NO	NO	4.011	26					87,199									294	4,816		14,890				*		
		2	I-40 BUS/US421 SOUTH BOUND	SOUTHBOUND FROM PAVEMENT JT AT ON RAMP FROM WEST BOUND I-40 TO BRIDGE #264 OVER CRAFTON ST.	2	2	MD	YES	NO	NO	3.845	26					82,057									276	4,532		13,728				*		
TOTAL FOR MAP NO. 2											**7.856**						**169,256**									**570**	**9,348**		**28,618**						
TOTAL FOR PROJ NO. 2016CPT.09.22.10341.1											**9.87**					**34,224**	**169,256**									**674**	**9,348**	**2,012**	**28,618**				**1**		
2016CPT.09.23.20341.1	Forsyth	3	SR 4000 UNIVERSITY PARKWAY/SR 1725 CHERRY ST-NORTH BOUND	NORTHBOUND FROM PAVEMENT JT. NEAR COLISEUM ENTRANCE TO PAVEMENT JT. AT N. CHERRY ST. EXT., INCLUDES POLO ROAD RAMPS	3,4	2	MD	YES	NO	NO	1.778	24						1,953					182		11					32,844	8	3	*		
		3	SR 4000 UNIVERSITY PARKWAY/ SR1770 N. MARSHALL ST-SOUTH BOUND	SOUTHBOUND FROM PAVEMENT JT AT N. CHERRY ST. EXT. TO PAVEMENT JT. NEAR COLISEUM ENTRANCE, NCLUDES POLO ROAD RAMPS	5,5A,6	2	MD	YES	NO	NO	1.978	24						753					71		4					36,109	7	2	*		
TOTAL FOR MAP NO. 3											**3.756**							**2,706**					**253**		**15**					**68,953**	**15**	**5**			
2016CPT.09.23.20341.1	Forsyth	4	SR 4000/SR 1725 UNIVERSITY PARKWAY NORTHBOUND	NORTHBOUND FROM PAVEMENT JT. NEAR COLISEUM ENTRANCE TO PAVEMENT JT. AT N. CHERRY ST. EXT., INCLUDES POLO ROAD RAMPS	5,5A,6	2	MD	YES	NO	NO	3.241	VARIES 24'-70'	131		1.09			70,033					6,493		383						43	9	*	436	44
		4	SR 4000/SR 1725 UNIVERSITY PARKWAY SOUTHBOUND	SOUTHBOUND FROM PAVEMENT JT AT N. CHERRY ST. EXT. TO PAVEMENT JT. NEAR COLISEUM ENTRANCE, NCLUDES POLO ROAD RAMPS	5,5A,6	2	MD	YES	NO	NO	3.242	VARIES 24'-70'	159		1.33			69,510					6,445		380						8	1	*	531	53
TOTAL FOR MAP NO. 4											**6.483**		**290**		**2.42**			**139,543**					**12,938**		**763**						**51**	**10**		**967**	**97**
2016CPT.09.23.20341.1	Forsyth	5	SR 1763 INDIANA AVE	FROM PAVEMENT JT. AT NORTH POINT BLVD. SR 1528 TO PAVEMENT JT. BEFORE RXR AT REYNOLDS BLVD. SR 4001	7,7A	2	MU	YES	NO	NO	1.359	VARIES 24'-58'	28		0.23			38,314					3,549		209						69	14	*	94	10
TOTAL FOR MAP NO. 5											**1.359**		**28**		**0.23**			**38,314**					**3,549**		**209**						**69**	**14**		**94**	**10**
2016CPT.09.23.20341.1	Forsyth	6	SR 1122 JONESTOWN ROAD	FROM COUNTRY CLUB RD. (SR 1001) THROUGH INTERSECTION TO RADIUS AT HANES MALL BLVD. (SR 3153)	8,8A	5	MU	YES	NO	NO	0.646	53	11		0.09			22,740				2,106			126						23	12	*		
TOTAL FOR MAP NO. 6											**0.646**		**11**		**0.09**			**22,740**				**2,106**			**126**						**23**	**12**			
2016CPT.09.23.20341.1	Forsyth	7	SR 1393 SHATTALON RD.	FROM PAVEMENT JT AT YADKINVILLE RD. (SR 1525) TO PAVEMENT JT AT ROBINHOOD RD. (SR 1348)	9,10	2	2WU	YES	NO	NO	2.585	VARIES 22'-34'	310	33	5.17			550	742	1,223		3,544			213						3	1		1,034	103
TOTAL FOR MAP NO. 7											**2.585**		**310**	**33**	**5.17**			**550**	**742**	**1,223**		**3,544**			**213**						**3**	**1**		**1,034**	**103**
2016CPT.09.23.20341.1	Forsyth	8	SR 1001 COUNTRYCLUB RD./SHALLOWFORD RD.	FROM PAVEMENT JT. EAST OF BRIDGE #96 TO PAVEMENT JT. AT SIMS DRIVE (SR 1539)	10	2	2WU	YES	NO	NO	0.357	22	43		0.71			152		489		494			30									143	14
TOTAL FOR MAP NO. 8											**0.357**		**43**		**0.71**			**152**		**489**		**494**			**30**									**143**	**14**
2016CPT.09.23.20341.1	Forsyth	9	SR 2693 SAWMILL RD.	FROM EOP PAVEMENT JT AT UNION CROSS RD. (SR 2643) TO PAVEMENT JT NEAR DIER LANE (SR 4361)	11	2	2WU	YES	NO	NO	1.149	21	138	96	2.30						571			1,300	112									460	46
TOTAL FOR MAP NO. 9											**1.149**		**138**	**96**	**2.30**						**571**			**1,300**	**112**									**460**	**46**
TOTAL FOR PROJ NO. 2016CPT.09.23.20341.1											**16.335**		**820**	**129**	**10.93**			**204,005**	**742**	**1,712**	**571**	**6,144**	**16,740**	**1,300**	**1,468**					**68,953**	**161**	**42**		**2,698**	**270**
GRAND TOTAL											**26.205**		**820**	**129**	**10.93**	**34,224**	**169,256**	**204,005**	**742**	**1,712**	**571**	**6,144**	**16,740**	**1,300**	**1,468**	**674**	**9,348**	**2,012**	**28,618**	**68,953**	**161**	**42**	**1**	**2,698**	**270**