



Transportation

PAT McCRORY
Governor

NICHOLAS J. TENNYSON
Secretary

April 8, 2016

Addendum No. 1

RE: Contract # C203725

WBS # 34845.3.3

STATE FUNDED

Forsyth County (U-2707)

SR-3000 (Idols Road) From SR-2999 (Hampton Road) To US-158 (Clemmons Road)

April 19, 2016 Letting

To Whom It May Concern:

Reference is made to the proposal form furnished to you on this project.

The following revisions have been made to the proposal:

| Page No. | Revisions |
|----------------|--|
| Proposal Cover | Note added that reads "Includes Addendum No. 1 Dated 04-08-16" |
| EC-35 | Revised the second paragraph of Section (B) Stream Excavation/Ditch Filling within the project special provision entitled "Site Grading For Mitigation" to include the estimated earthwork |

Please void Page EC-35 in your proposal and replace with the revised Page EC-35.

The contract will be prepared accordingly.

Sincerely,

R. A. Garriss, PE
Contract Officer

RAG/jag

- cc: Mr. Ron Hancock, PE
- Mr. Pat Ivey PE
- Mr. Rodger Rochelle, PE
- Mr. R.E. Davenport, PE
- Mr. Ken Kennedy, PE
- Ms. Jaci Kincaid
- Project File (2)
- Mr. Ray Arnold, PE
- Ms. Theresa Canales, PE
- Ms. Marsha Sample
- Mr. Mike Gwyn
- Ms. Penny Higgins
- Ms. Lori Strickland



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH, N.C.

PROPOSAL

INCLUDES ADDENDUM No. 1 DATED 04-08-16

DATE AND TIME OF BID OPENING: **APRIL 19, 2016 AT 2:00 PM**

CONTRACT ID C203725
WBS 34845.3.3

FEDERAL-AID NO. STATE FUNDED

COUNTY FORSYTH

T.I.P. NO. U-2707

MILES 2.093

ROUTE NO. SR 3000

LOCATION SR-3000 (IDOLS RD) FROM SR-2999 (HAMPTON RD) TO US-158
(CLEMMONS RD).

TYPE OF WORK GRADING, DRAINAGE, PAVING, SIGNALS, AND STRUCTURES.

NOTICE:

ALL BIDDERS SHALL COMPLY WITH ALL APPLICABLE LAWS REGULATING THE PRACTICE OF GENERAL CONTRACTING AS CONTAINED IN CHAPTER 87 OF THE GENERAL STATUTES OF NORTH CAROLINA WHICH REQUIRES THE BIDDER TO BE LICENSED BY THE N.C. LICENSING BOARD FOR CONTRACTORS WHEN BIDDING ON ANY NON-FEDERAL AID PROJECT WHERE THE BID IS \$30,000 OR MORE, EXCEPT FOR CERTAIN SPECIALTY WORK AS DETERMINED BY THE LICENSING BOARD. BIDDERS SHALL ALSO COMPLY WITH ALL OTHER APPLICABLE LAWS REGULATING THE PRACTICES OF ELECTRICAL, PLUMBING, HEATING AND AIR CONDITIONING AND REFRIGERATION CONTRACTING AS CONTAINED IN CHAPTER 87 OF THE GENERAL STATUTES OF NORTH CAROLINA. NOTWITHSTANDING THESE LIMITATIONS ON BIDDING, THE BIDDER WHO IS AWARDED ANY FEDERAL - AID FUNDED PROJECT SHALL COMPLY WITH CHAPTER 87 OF THE GENERAL STATUTES OF NORTH CAROLINA FOR LICENSING REQUIREMENTS WITHIN 60 CALENDAR DAYS OF BID OPENING.

BIDS WILL BE RECEIVED AS SHOWN BELOW:

THIS IS A ROADWAY PROPOSAL

5% BID BOND OR BID DEPOSIT REQUIRED

Payment will be made under:

| Pay Item | Pay Unit |
|--------------------------|-----------------|
| Streambank Reforestation | Acre |

SITE GRADING FOR MITIGATION:

Description

The Contractor shall perform grading as necessary to attain final surface elevations as shown on the plans and in the details.

Construction Methods

(A) Site Grading

The Contractor shall perform grading as necessary to attain final surface elevations as shown on the plans and in the details. Field modifications shall be approved by the Engineer. Final grades shall meet the plan and stream dimensions within a tolerance of +/- 0.2 feet (2.4 inches).

(B) Stream Excavation/Ditch Filling

In areas where ditches are to be filled, the Contractor shall comply with the requirements of Subarticle 235-3(C) of the *Standard Specifications* to obtain a minimum 95% compaction rate. Lift thickness shall not exceed 1 ft. and compaction shall be achieved by use of mechanical compaction equipment only. Fill material shall be such that the Plasticity Index (PI) shall be equal to or greater than that of the PI in each surrounding soil strata. Organic material shall not exceed 10% of the total volume of the fill material used. No compaction shall be performed for graded areas unless directed.

Excess material shall be disposed of as shown on the plans or as directed. **Estimated earthwork quantities: Excavation= 4,005 CY, Fill = 2,520 CY, Waste= 1,485 CY.**

Measurement and Payment

All work completed under this section will be paid for as lump sum for *Site Grading for Mitigation*.

The above prices and payments will be full compensation for all work covered by this section.

Payment will be made under:

| Pay Item | Pay Unit |
|-----------------------------|-----------------|
| Site Grading for Mitigation | Lump Sum |