

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
GEOTECHNICAL ENGINEERING UNIT

STRUCTURE
SUBSURFACE INVESTIGATION

CONTENTS

<u>SHEET</u>	<u>DESCRIPTION</u>
1	Title Sheet
2	Legend
3	Site Plan
4	Profile
5 - 11	Cross Sections
12 - 33	Bore Logs, Core Logs and Core Photos
34	Soil Test Results
35 - 36	Rock Test Results
37	Site Photographs

PROJ. REFERENCE NO. 34845.1.1 (U-2707) F.A. PROJ. STP-3000(1)
 COUNTY FORSYTH
 PROJECT DESCRIPTION CLEMMONS - (SR3000 (IDOLS ROAD EXTENSION))
FROM (SR2999 (HAMPTON ROAD)) TO US-158 (CLEMMONS ROAD)

SITE DESCRIPTION BRIDGE NO. 656 ON -L- (SR3000 (IDOLS ROAD
EXTENSION)) OVER MUDDY CREEK

INVENTORY

CAUTION NOTICE

THE SUBSURFACE INFORMATION AND THE SUBSURFACE INVESTIGATION ON WHICH IT IS BASED WERE MADE FOR THE PURPOSE OF STUDY, PLANNING, AND DESIGN, AND NOT FOR CONSTRUCTION OR PAY PURPOSES. THE VARIOUS FIELD BORING LOGS, ROCK CORES, AND SOIL TEST DATA AVAILABLE MAY BE REVIEWED OR INSPECTED IN RALEIGH BY CONTACTING THE N.C. DEPARTMENT OF TRANSPORTATION, GEOTECHNICAL ENGINEERING UNIT AT (919) 707-6850. NEITHER THE SUBSURFACE PLANS AND REPORTS, NOR THE FIELD BORING LOGS, ROCK CORES, OR SOIL TEST DATA ARE PART OF THE CONTRACT.

GENERAL SOIL AND ROCK STRATA DESCRIPTIONS AND INDICATED BOUNDARIES ARE BASED ON A GEOTECHNICAL INTERPRETATION OF ALL AVAILABLE SUBSURFACE DATA AND MAY NOT NECESSARILY REFLECT THE ACTUAL SUBSURFACE CONDITIONS BETWEEN BORINGS OR BETWEEN SAMPLED STRATA WITHIN THE BOREHOLE. THE LABORATORY SAMPLE DATA AND THE IN SITU ON-PLACE TEST DATA CAN BE RELIED ON ONLY TO THE DEGREE OF RELIABILITY INHERENT IN THE STANDARD TEST METHOD. THE OBSERVED WATER LEVELS OR SOIL MOISTURE CONDITIONS INDICATED IN THE SUBSURFACE INVESTIGATIONS ARE AS RECORDED AT THE TIME OF THE INVESTIGATION. THESE WATER LEVELS OR SOIL MOISTURE CONDITIONS MAY VARY CONSIDERABLY WITH TIME ACCORDING TO CLIMATIC CONDITIONS INCLUDING TEMPERATURES, PRECIPITATION, AND WIND, AS WELL AS OTHER NON-CLIMATIC FACTORS.

THE BIDDER OR CONTRACTOR IS CAUTIONED THAT DETAILS SHOWN ON THE SUBSURFACE PLANS ARE PRELIMINARY ONLY AND IN MANY CASES THE FINAL DESIGN DETAILS ARE DIFFERENT. FOR BIDDING AND CONSTRUCTION PURPOSES, REFER TO THE CONSTRUCTION PLANS AND DOCUMENTS FOR FINAL DESIGN INFORMATION ON THIS PROJECT. THE DEPARTMENT DOES NOT WARRANT OR GUARANTEE THE SUFFICIENCY OR ACCURACY OF THE INVESTIGATION MADE, NOR THE INTERPRETATIONS MADE, OR OPINION OF THE DEPARTMENT AS TO THE TYPE OF MATERIALS AND CONDITIONS TO BE ENCOUNTERED. THE BIDDER OR CONTRACTOR IS CAUTIONED TO MAKE SUCH INDEPENDENT SUBSURFACE INVESTIGATIONS AS HE DEEMS NECESSARY TO SATISFY HIMSELF AS TO CONDITIONS TO BE ENCOUNTERED ON THIS PROJECT. THE CONTRACTOR SHALL HAVE NO CLAIM FOR ADDITIONAL COMPENSATION OR FOR AN EXTENSION OF TIME FOR ANY REASON RESULTING FROM THE ACTUAL CONDITIONS ENCOUNTERED AT THE SITE DIFFERING FROM THOSE INDICATED IN THE SUBSURFACE INFORMATION.

PERSONNEL

 J. BRANDSEN

 E. MAYR

 B. RATTI

 M.B. MOSELEY


 M.G. MOSELEY

INVESTIGATED BY S&ME, INC.

CHECKED BY A.F. RIGGS, JR.

SUBMITTED BY S&ME, INC.

DATE JUNE 2012



PROJECT: 34845.1.1 ID: U-2707

DRAWN BY: B. RATTI

NOTE - THE INFORMATION CONTAINED HEREIN IS NOT IMPLIED OR GUARANTEED BY THE N.C. DEPARTMENT OF TRANSPORTATION AS BEING ACCURATE NOR IS IT CONSIDERED TO BE PART OF THE PLANS, SPECIFICATIONS, OR CONTRACT FOR THE PROJECT.





NOTE - BY HAVING REQUESTED THIS INFORMATION THE CONTRACTOR SPECIFICALLY WAIVES ANY CLAIMS FOR INCREASED COMPENSATION OR EXTENSION OF TIME BASED ON DIFFERENCES BETWEEN THE CONDITIONS INDICATED HEREIN AND THE ACTUAL CONDITIONS AT THE PROJECT SITE.



**NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
GEOTECHNICAL ENGINEERING UNIT**

SUBSURFACE INVESTIGATION


SOIL AND ROCK LEGEND, TERMS, SYMBOLS, AND ABBREVIATIONS

PROJECT REFERENCE NO. 34845.11(U-2707) SHEET NO. 2

SOIL DESCRIPTION		GRADATION		ROCK DESCRIPTION		TERMS AND DEFINITIONS	
SOIL IS CONSIDERED TO BE THE UNCONSOLIDATED, SEMI-CONSOLIDATED, OR WEATHERED EARTH MATERIALS THAT CAN BE PENETRATED WITH A CONTINUOUS FLIGHT POWER AUGER, AND YIELD LESS THAN 100 BLOWS PER FOOT ACCORDING TO STANDARD PENETRATION TEST (ASTM D-1586). SOIL CLASSIFICATION IS BASED ON THE AASHTO SYSTEM. BASIC DESCRIPTIONS GENERALLY SHALL INCLUDE: CONSISTENCY, COLOR, TEXTURE, MOISTURE, AASHTO CLASSIFICATION AND OTHER PERTINENT FACTORS SUCH AS MINERALOGICAL COMPOSITION, ANGULARITY, STRUCTURE, PLASTICITY, ETC. EXAMPLE: <i>VERY STIFF, GRN, SILTY CLAY, MOST WITH INTERBEDDED FINE SAND LAYERS, HIGH PLASTIC, A-7-6</i>		WELL GRADED - INDICATES A GOOD REPRESENTATION OF PARTICLE SIZES FROM FINE TO COARSE. UNIFORM - INDICATES THAT SOIL PARTICLES ARE ALL APPROXIMATELY THE SAME SIZE. (ALSO POORLY GRADED) GAP-GRADED - INDICATES A MIXTURE OF UNIFORM PARTICLES OF TWO OR MORE SIZES. THE ANGULARITY OR ROUNDNESS OF SOIL GRAINS IS DESIGNATED BY THE TERMS: ANGULAR, SUBANGULAR, SUBROUNDED, OR ROUNDED.		HARD ROCK IS NON-COASTAL PLAIN MATERIAL THAT IF TESTED, WOULD YIELD SPT REFUSAL. AN INFERRED ROCK LINE INDICATES THE LEVEL AT WHICH NON-COASTAL PLAIN MATERIAL WOULD YIELD SPT REFUSAL. SPT REFUSAL IS PENETRATION BY A SPLIT SPOON SAMPLER EQUAL TO OR LESS THAN 60 BLOWS. IN NON-COASTAL PLAIN MATERIAL, THE TRANSITION BETWEEN SOIL AND ROCK IS OFTEN REPRESENTED BY A ZONE OF WEATHERED ROCK. ROCK MATERIALS ARE TYPICALLY DIVIDED AS FOLLOWS: WEATHERED ROCK (WR)  NON-COASTAL PLAIN MATERIAL THAT WOULD YIELD SPT N VALUES > 100 BLOWS PER FOOT IF TESTED. CRYSTALLINE ROCK (CR)  FINE TO COARSE GRAIN IGNEOUS AND METAMORPHIC ROCK THAT WOULD YIELD SPT REFUSAL IF TESTED. ROCK TYPE INCLUDES GRANITE, GNEISS, GABBRO, SCHIST, ETC. NON-CRYSTALLINE ROCK (NCR)  FINE TO COARSE GRAIN METAMORPHIC AND NON-COASTAL PLAIN SEDIMENTARY ROCK THAT WOULD YIELD SPT REFUSAL IF TESTED. ROCK TYPE INCLUDES PHYLLITE, SLATE, SANDSTONE, ETC. COASTAL PLAIN SEDIMENTARY ROCK (CPS)  COASTAL PLAIN SEDIMENTS CEMENTED INTO ROCK, BUT MAY NOT YIELD SPT REFUSAL. ROCK TYPE INCLUDES LIMESTONE, SANDSTONE, CEMENTED SHELL BEDS, ETC.		ALLUVIUM (ALLUV.) - SOILS THAT HAVE BEEN TRANSPORTED BY WATER. ADUIFIER - A WATER BEARING FORMATION OR STRATA. ARENACEOUS - APPLIED TO ROCKS THAT HAVE BEEN DERIVED FROM SAND OR THAT CONTAIN SAND. ARGILLACEOUS - APPLIED TO ALL ROCKS OR SUBSTANCES COMPOSED OF CLAY MINERALS, OR HAVING A NOTABLE PROPORTION OF CLAY IN THEIR COMPOSITION, AS SHALE, SLATE, ETC. ARTESIAN - GROUND WATER THAT IS UNDER SUFFICIENT PRESSURE TO RISE ABOVE THE LEVEL AT WHICH IT IS ENCOUNTERED, BUT WHICH DOES NOT NECESSARILY RISE TO OR ABOVE THE GROUND SURFACE. CALCAREOUS (CALC.) - SOILS THAT CONTAIN APPRECIABLE AMOUNTS OF CALCIUM CARBONATE. COLLUVIUM - ROCK FRAGMENTS MIXED WITH SOIL DEPOSITED BY GRAVITY ON SLOPE OR AT BOTTOM OF SLOPE. CORE RECOVERY (REC.) - TOTAL LENGTH OF ALL MATERIAL RECOVERED IN THE CORE BARREL DIVIDED BY TOTAL LENGTH OF CORE RUN AND EXPRESSED AS A PERCENTAGE. DIKE - A TABULAR BODY OF IGNEOUS ROCK THAT CUTS ACROSS THE STRUCTURE OF ADJACENT ROCKS OR CUTS MASSIVE ROCK. DIP - THE ANGLE AT WHICH A STRATUM OR ANY PLANAR FEATURE IS INCLINED FROM THE HORIZONTAL. DIP DIRECTION (DIP AZIMUTH) - THE DIRECTION OR BEARING OF THE HORIZONTAL TRACE OF THE LINE OF DIP, MEASURED CLOCKWISE FROM NORTH. FAULT - A FRACTURE OR FRACTURE ZONE ALONG WHICH THERE HAS BEEN DISPLACEMENT OF THE SIDES RELATIVE TO ONE ANOTHER PARALLEL TO THE FRACTURE. FISSILE - A PROPERTY OF SPLITTING ALONG CLOSELY SPACED PARALLEL PLANES. FLOAT - ROCK FRAGMENTS ON SURFACE NEAR THEIR ORIGINAL POSITION AND DISLOADED FROM PARENT MATERIAL. FLOOD PLAIN (FP) - LAND BORDERING A STREAM, BUILT OF SEDIMENTS DEPOSITED BY THE STREAM. FORMATION (FM) - A MAPPABLE GEOLOGIC UNIT THAT CAN BE RECOGNIZED AND TRACED IN THE FIELD. JOINT - FRACTURE IN ROCK ALONG WHICH NO APPRECIABLE MOVEMENT HAS OCCURRED. LEDGE - A SHELF-LIKE RIDGE OR PROJECTION OF ROCK WHOSE THICKNESS IS SMALL COMPARED TO ITS LATERAL EXTENT. LENS - A BODY OF SOIL OR ROCK THAT THINS OUT IN ONE OR MORE DIRECTIONS. MOTTLED (MOT) - IRREGULARLY MARKED WITH SPOTS OF DIFFERENT COLORS. MOTTLING IN SOILS USUALLY INDICATES POOR AERATION AND LACK OF GOOD DRAINAGE. PERCHED WATER - WATER MAINTAINED ABOVE THE NORMAL GROUND WATER LEVEL BY THE PRESENCE OF AN INTERVENING IMPERVIOUS STRATUM. RESIDUAL (RES) SOIL - SOIL FORMED IN PLACE BY THE WEATHERING OF ROCK. ROCK QUALITY DESIGNATION (RQD) - A MEASURE OF ROCK QUALITY DESCRIBED BY TOTAL LENGTH OF ROCK SEGMENTS EQUAL TO OR GREATER THAN 4 INCHES DIVIDED BY THE TOTAL LENGTH OF CORE RUN AND EXPRESSED AS A PERCENTAGE. SAPROLITE (SAP) - RESIDUAL SOIL THAT RETAINS THE RELIC STRUCTURE OR FABRIC OF THE PARENT ROCK. SILL - AN INTRUSIVE BODY OF IGNEOUS ROCK OF APPROXIMATELY UNIFORM THICKNESS AND RELATIVELY THIN COMPARED WITH ITS LATERAL EXTENT, THAT HAS BEEN EMPLACED PARALLEL TO THE BEDDING OR SCHISTOSITY OF THE INTRUDED ROCKS. SLICKENSIDE - POLISHED AND STRIATED SURFACE THAT RESULTS FROM FRICTION ALONG A FAULT OR SLIP PLANE. STANDARD PENETRATION TEST (PENETRATION RESISTANCE) (SPT) - NUMBER OF BLOWS (N OR BPF) OF A 140 LB. HAMMER FALLING 30 INCHES REQUIRED TO PRODUCE A PENETRATION OF 1 FOOT INTO SOIL WITH A 2 INCH OUTSIDE DIAMETER SPLIT SPOON SAMPLER. SPT REFUSAL IS PENETRATION EQUAL TO OR LESS THAN 60 BLOWS. STRATA CORE RECOVERY (SCRC) - TOTAL LENGTH OF STRATA MATERIAL RECOVERED DIVIDED BY TOTAL LENGTH OF STRATUM AND EXPRESSED AS A PERCENTAGE. STRATA ROCK QUALITY DESIGNATION (SRQD) - A MEASURE OF ROCK QUALITY DESCRIBED BY TOTAL LENGTH OF ROCK SEGMENTS WITHIN A STRATUM EQUAL TO OR GREATER THAN 4 INCHES DIVIDED BY THE TOTAL LENGTH OF STRATA AND EXPRESSED AS A PERCENTAGE. TOPSOIL (TS) - SURFACE SOILS USUALLY CONTAINING ORGANIC MATTER. BENCH MARK: NCDOT TRAVERSE STATION REBAR AND CAP (SEE BELOW) ELEVATION: _____ FT. NOTES: FIAD - FILLED IN AFTER DRILLING NCDOT TRAVERSE STATION REBAR AND CAP: 1BL-24) LOCATED AT STA 90+05.76 22.15' RT -L- N 827577 E 1599302 ELEV 698.79 1BL-25) LOCATED AT STA 94+16.45 35.36' RT -L- N 827882 E 1599576 ELEV 705.52 ST-1 SHELBY TUBE	
SOIL LEGEND AND AASHTO CLASSIFICATION				MINERALOGICAL COMPOSITION			
GENERAL CLASS. GRANULAR MATERIALS (<= 35% PASSING #200) SILT-CLAY MATERIALS (> 35% PASSING #200) ORGANIC MATERIALS				MINERAL NAMES SUCH AS QUARTZ, FELDSPAR, MICA, TALC, KAOLIN, ETC. ARE USED IN DESCRIPTIONS WHENEVER THEY ARE CONSIDERED OF SIGNIFICANCE.			
GROUP CLASS. A-1-a, A-1-b, A-2, A-2-4, A-2-5, A-2-6, A-2-7, A-4, A-5, A-6, A-7, A-7-5, A-7-6, A-3				COMPRESSIBILITY			
SYMBOL				SLIGHTLY COMPRESSIBLE LIQUID LIMIT LESS THAN 31 MODERATELY COMPRESSIBLE LIQUID LIMIT EQUAL TO 31-50 HIGHLY COMPRESSIBLE LIQUID LIMIT GREATER THAN 50			
% PASSING # 10, # 40, # 200				PERCENTAGE OF MATERIAL			
LIQUID LIMIT, PLASTIC INDEX				ORGANIC MATERIAL, GRANULAR SOILS, SILT-CLAY SOILS, OTHER MATERIAL			
GROUP INDEX				GROUND WATER			
USUAL TYPES OF MAJOR MATERIALS				WATER LEVEL IN BORE HOLE IMMEDIATELY AFTER DRILLING STATIC WATER LEVEL AFTER 24 HOURS PERCHED WATER, SATURATED ZONE, OR WATER BEARING STRATA SPRING OR SEEP			
GEN. RATING AS A SUBGRADE				MISCELLANEOUS SYMBOLS			
PI OF A-7-5 SUBGROUP IS <= LL - 30; PI OF A-7-6 SUBGROUP IS > LL - 30				ROADWAY EMBANKMENT (RE) WITH SOIL DESCRIPTION SOIL SYMBOL ARTIFICIAL FILL (AF) OTHER THAN ROADWAY EMBANKMENT INFERRED SOIL BOUNDARY INFERRED ROCK LINE ALLUVIAL SOIL BOUNDARY DIP & DIP DIRECTION OF ROCK STRUCTURES			
CONSISTENCY OR DENSENESS				SPT TEST BORING AUGER BORING CORE BORING MONITORING WELL PIEZOMETER INSTALLATION SLOPE INDICATOR INSTALLATION CONE PENETROMETER TEST SOUNDING ROD			
PRIMARY SOIL TYPE, COMPACTNESS OR CONSISTENCY, RANGE OF STANDARD PENETRATION RESISTANCE (N-VALUE), RANGE OF UNCONFINED COMPRESSIVE STRENGTH (TONS/FT ²)				TEST BORING W/ CORE SPT N-VALUE SPT REFUSAL			
TEXTURE OR GRAIN SIZE				ABBREVIATIONS			
U.S. STD. SIEVE SIZE OPENING (MM)				AR - AUGER REFUSAL, BT - BORING TERMINATED, CL - CLAY, CPT - CONE PENETRATION TEST, CSE - COARSE, DMT - DILATOMETER TEST, DPT - DYNAMIC PENETRATION TEST, F - FINE, FOSS - FOSSILIFEROUS, FRAC. - FRACTURED, FRACTURES, FRAGS. - FRAGMENTS, HL - HIGHLY			
BOULDER, COBBLE, GRAVEL, COARSE SAND, FINE SAND, SILT, CLAY				MED. - MEDIUM, MICA - MICACEOUS, MOD. - MODERATELY, NP - NON PLASTIC, ORG. - ORGANIC, PMT - PRESSUREMETER TEST, SAP. - SAPROLITIC, SD. - SAND, SANDY, SL. - SILT, SILTY, SLI. - SLIGHTLY, TCR - TRICONE REFUSAL, W - MOISTURE CONTENT, V - VERY, VST - VANE SHEAR TEST, WE. - WEATHERED, WGT - UNIT WEIGHT, Wd - DRY UNIT WEIGHT			
SOIL MOISTURE - CORRELATION OF TERMS				SAMPLE ABBREVIATIONS			
SOIL MOISTURE SCALE (ATTERBERG LIMITS), FIELD MOISTURE DESCRIPTION, GUIDE FOR FIELD MOISTURE DESCRIPTION				S - BULK, SS - SPLIT SPOON, ST - SHELBY TUBE, RS - ROCK, RT - RECOMPACTED TRIAXIAL, CBR - CALIFORNIA BEARING RATIO			
PLASTICITY				EQUIPMENT USED ON SUBJECT PROJECT			
NONPLASTIC, LOW PLASTICITY, MED. PLASTICITY, HIGH PLASTICITY				DRILL UNITS: MOBILE B, BK-51, CME-45C, CME-550, PORTABLE MOIST, Dierdrich D-50			
COLOR				ADVANCING TOOLS: CLAY BITS, 6" CONTINUOUS FLIGHT AUGER, B" HOLLOW AUGERS, HARD FACED FINGER BITS, TUNG.-CARBIDE INSERTS, CASING W/ ADVANCER, TRICONE STEEL TEETH, TRICONE 2 1/8" TUNG.-CARB., CORE BIT, 3 1/4" H.S.A.			
DESCRIPTORS MAY INCLUDE COLOR OR COLOR COMBINATIONS (TAN, RED, YELLOW-BROWN, BLUE-GRAY). MODIFIERS SUCH AS LIGHT, DARK, STREAKED, ETC. ARE USED TO DESCRIBE APPEARANCE.				HAMMER TYPE: AUTOMATIC, MANUAL CORE SIZE: B, N, H HAND TOOLS: POST HOLE DIGGER, HAND AUGER, SOUNDING ROD, VANE SHEAR TEST			
				FRACTURE SPACING		BEDDING	
				TERM, SPACING		TERM, THICKNESS	
				INDURATION			
				FOR SEDIMENTARY ROCKS, INDURATION IS THE HARDENING OF THE MATERIAL BY CEMENTING, HEAT, PRESSURE, ETC.			
				FRIABLE, MODERATELY INDURATED, INDURATED, EXTREMELY INDURATED			
				RUBBING WITH FINGER FREES NUMEROUS GRAINS; GENTLE BLOW BY HAMMER DISINTEGRATES SAMPLE. GRAINS CAN BE SEPARATED FROM SAMPLE WITH STEEL PROBE; BREAKS EASILY WHEN HIT WITH HAMMER. GRAINS ARE DIFFICULT TO SEPARATE WITH STEEL PROBE; DIFFICULT TO BREAK WITH HAMMER. SHARP HAMMER BLOWS REQUIRED TO BREAK SAMPLE; SAMPLE BREAKS ACROSS GRAINS.			



SKIEW ANGLE FOR BENTS 90° TYPICAL



BORING LOCATION PLAN
 BRIDGE NO. 656 ON -L- (SR3000 (IDOLS ROAD EXTENSION))
 OVER MUDDY CREEK
 STATE PROJ NO. 34845.1.1 TIP NO. U-2707
 FEDERAL I.D. NO. STP-3000(1)
 FORSYTH COUNTY, NORTH CAROLINA


S&ME
 WWW.SMEINC.COM
 NC ENGINEER LICENSE #F-0176
 3201 SPRING FOREST RD, RALEIGH, NC 27616

SCALE: 1" = 50'	APPROVED BY: ARF
DATE: MAY 2012	DRAWN BY: BTR
JOB NO:	SHEET: 3

TO HAMPTON ROAD

TO US-158

GENERALIZED SUBSURFACE PROFILE ALONG -L-




APPROVED BY: AFR
 DRAWN BY: BTR
 DATE: MAY 2012
 JOB NO:



GENERALIZED SUBSURFACE PROFILE ALONG -L-
 BRIDGE NO. 656 ON -L- (SR3000 (DOLS ROAD EXTENSION))
 OVER MUDDY CREEK
 STATE PROJ NO. 34845.1.1 TIP NO. U-2707
 FEDERAL I.D. NO. STP-3000(1)
 FORSYTH COUNTY, NORTH CAROLINA

SHEET: 4

CROSS SECTION THROUGH END BENT 1



NOTE:
GROUND LINE TAKEN FROM TIN FILE "u2707_ls_tin_110418.dgn"

CROSS SECTION THROUGH END BENT 1
 BRIDGE NO. 656 ON -L- (SR3000 (IDOLS ROAD EXTENSION))
 OVER MUDDY CREEK
 STATE PROJ NO. 34845.1.1 TIP NO. U-2707
 FEDERAL I.D. NO. STP-3000(1)
 FORSYTH COUNTY, NORTH CAROLINA



WWW.SMEINC.COM
 NC ENGINEER LICENSE #F-0176
 3201 SPRING FOREST RD, RALEIGH, NC 27616

SCALE: VERT. 1" = 10'
 HOR. 1" = 20'

DATE: MAY 2012


APPROVED BY: AFR

JOB NO:

DRAWN BY: BTR

SHEET: 5

CROSS SECTION THROUGH INTERIOR BENT 1



NOTE:
GROUND LINE TAKEN FROM TIN FILE "u2707_ls_tin_110418.dgn"


CROSS SECTION THROUGH INTERIOR BENT 1
 BRIDGE NO. 656 ON L- (SR3000 (DOLS ROAD EXTENSION))
 OVER MUDDY CREEK
 STATE PROJ NO. 34845.1.1 TIP NO. U-2707
 FEDERAL I.D. NO. STP-3000(1)
 FORSYTH COUNTY, NORTH CAROLINA



WWW.SMEINC.COM
 NC ENGINEER LICENSE #E-0176
 3201 SPRING FOREST RD, RALEIGH, NC 27616

SCALE: VERT. 1" = 10' HOR. 1" = 20'	APPROVED BY: AFR
DATE: MAY 2012	DRAWN BY: BTR
JOB NO:	SHEET: 6

CROSS SECTION THROUGH INTERIOR BENT 2



NOTE:
GROUND LINE TAKEN FROM TIN FILE "u2707_ls_tin_110418.dgn"


CROSS SECTION THROUGH INTERIOR BENT 2
 BRIDGE NO. 656 ON -L- (SR3000 (DOLS ROAD EXTENSION))
 OVER MUDDY CREEK
 STATE PROJ NO. 34845.1.1 TIP NO. U-2707
 FEDERAL I.D. NO. STP-3000(1)
 FORSYTH COUNTY, NORTH CAROLINA



WWW.SMEINC.COM
 NC ENGINEER LICENSE #F-0176
 3201 SPRING FOREST RD, RALEIGH, NC 27616

SCALE: VERT. 1" = 10' HOR. 1" = 20'	APPROVED BY: AFR
DATE: MAY 2012	DRAWN BY: BTR
JOB NO:	SHEET: 7

CROSS SECTION THROUGH INTERIOR BENT 3



NOTES:
 INFERRED STRATIGRAPHY IS DRAWN THROUGH THE BORINGS WITH BOTH PROJECTED ON TO THE CROSS SECTION. GROUND LINE AND -L- CROSS SECTION TAKEN FROM TIN FILE "u2707_is_tin_110418.dgn"

CROSS SECTION THROUGH INTERIOR BENT 3

BRIDGE NO. 656 ON -L- (SR3000 (IDOLS ROAD EXTENSION))

OVER MUDDY CREEK

STATE PROJ NO. 34845.1.1 TIP NO. U-2707

FEDERAL I.D. NO. STP-3000(1)

FORSYTH COUNTY, NORTH CAROLINA



WWW.SMEINC.COM

NC ENGINEER LICENSE #F-0176

3201 SPRING FOREST RD, RALEIGH, NC 27616

SCALE: VERT. 1" = 10'
HOR. 1" = 20'

DATE: MAY 2012

JOB NO:

APPROVED BY: AFR


DRAWN BY: BTR

SHEET: 8

CROSS SECTION THROUGH INTERIOR BENT 4

TO NORTHWEST

TO SOUTHEAST



NOTE:
GROUND LINE TAKEN FROM TIN FILE "u2707_ls_tin_110418.dgn"

CROSS SECTION THROUGH INTERIOR BENT 4

BRIDGE NO. 656 ON -L- (SR3000 (DOLS ROAD EXTENSION))
OVER MUDDY CREEK
STATE PROJ NO. 34845.1.1 TIP NO. U-2707
FEDERAL I.D. NO. STP-3000(1)
FORSYTH COUNTY, NORTH CAROLINA



WWW.SMEINC.COM
NC ENGINEER LICENSE #F-0176
3201 SPRING FOREST RD, RALEIGH, NC 27616

SCALE: VERT. 1" = 10'
HOR. 1" = 20'

DATE: MAY 2012


JOB NO:

APPROVED BY: AFR

DRAWN BY: BTR

SHEET: 9

CROSS SECTION THROUGH INTERIOR BENT 5



NOTE:
GROUND LINE TAKEN FROM TIN FILE "u2707_ls_tin_110418.dgn"


CROSS SECTION THROUGH INTERIOR BENT 5
 BRIDGE NO. 656 ON -L- (SR3000 (DOLS ROAD EXTENSION))
 OVER MUDDY CREEK
 STATE PROJ NO. 34845.1.1 TIP NO. U-2707
 FEDERAL I.D. NO. STP-3000(1)
 FORSYTH COUNTY, NORTH CAROLINA



WWW.SMEINC.COM
 NC ENGINEER LICENSE #0176
 3201 SPRING FOREST RD, RALEIGH, NC 27616

SCALE: VERT. 1" = 10' HOR. 1" = 20'	APPROVED BY: AFR
DATE: MAY 2012	DRAWN BY: BTR
JOB NO:	SHEET: 10

CROSS SECTION THROUGH END BENT 2



NOTE:
GROUND LINE TAKEN FROM TIN FILE "u2707_ls_tin_110418.dgn"

CROSS SECTION THROUGH END BENT 2
 BRIDGE NO. 656 ON -L- (SR3000 (IDOLS ROAD EXTENSION))
 OVER MUDDY CREEK
 STATE PROJ NO. 34845.1.1 TIP NO. U-2707
 FEDERAL I.D. NO. STP-3000(1)
 FORSYTH COUNTY, NORTH CAROLINA



WWW.SMEINC.COM
 NC ENGINEER LICENSE #E-0176
 3201 SPRING FOREST RD, RALEIGH, NC 27616

SCALE: VERT. 1" = 10'
 HOR. 1" = 20'
 DATE: MAY 2012
 JOB NO:
 APPROVED BY: AFR
 DRAWN BY: BTR
 SHEET: 11

WBS 34845.1.1 TIP U-2707 COUNTY FORSYTH GEOLOGIST Brandsen, J.

SITE DESCRIPTION Bridge No. 656 on SR 3000 (Idols Road) Over Muddy Creek GROUND WTR (ft)

BORING NO. EB1-A STATION 88+05 OFFSET 20 ft LT ALIGNMENT -L- 0 HR. N/A

COLLAR ELEV. 689.0 ft TOTAL DEPTH 21.7 ft NORTHING 827,450 EASTING 1,599,140 24 HR. 7.2

DRILL RIG/HAMMER EFF./DATE SME R-2 DIEDRICH D-50 87% 6/2/2011 DRILL METHOD H.S. Augers HAMMER TYPE Automatic

DRILLER Moseley, M. START DATE 03/23/12 COMP. DATE 03/23/12 SURFACE WATER DEPTH N/A

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)		
			0.5ft	0.5ft	0.5ft	0	25	50	75	100						
690														689.0	GROUND SURFACE	0.0
	688.0	1.0		2	2	2									ALLUVIAL Tan and Gray Silty Fine SAND with Some Clay	
685	685.5	3.5		1	2	3										
	683.0	6.0		1	1	1										
680	680.5	8.5		2	1	2								681.0	Gray Fine to Coarse SAND with Trace of Silt	8.0
														677.0	Gray Silty Fine SAND	12.0
675	675.5	13.5		1	1	1								671.0	RESIDUAL Black-Green Silty Fine SAND	18.0
	670.5	18.5		17	26	27								668.5	WEATHERED ROCK (Metadiorite)	20.5
	667.4	21.6												667.4	CRYSTALLINE ROCK (Metadiorite)	21.6
														667.3		21.7
															Boring Terminated with Standard Penetration Test Refusal at Elevation 667.3 ft in Crystalline Rock (Meta-diorite)	

WBS 34845.1.1 TIP U-2707 COUNTY FORSYTH GEOLOGIST Brandsen, J.

SITE DESCRIPTION Bridge No. 656 on SR 3000 (Idols Road) Over Muddy Creek GROUND WTR (ft)

BORING NO. EB1-B STATION 88+05 OFFSET 20 ft RT ALIGNMENT -L- 0 HR. N/A

COLLAR ELEV. 689.0 ft TOTAL DEPTH 25.2 ft NORTHING 827,425 EASTING 1,599,171 24 HR. 7.3

DRILL RIG/HAMMER EFF./DATE SME R-2 DIEDRICH D-50 87% 6/2/2011 DRILL METHOD H.S. Augers HAMMER TYPE Automatic

DRILLER Moseley, M. START DATE 03/23/12 COMP. DATE 03/23/12 SURFACE WATER DEPTH N/A

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)		
			0.5ft	0.5ft	0.5ft	0	25	50	75	100						
690														689.0	GROUND SURFACE	0.0
	688.0	1.0		2	2	2									ALLUVIAL Tan Clayey Fine SAND	
685	685.5	3.5		1	2	3								686.0	Tan and Gray Silty Fine to Coarse SAND with Some Wood Fragments and Trace of Mica	3.0
	683.0	6.0		1	2	3										
680	680.5	8.5		2	2	3										
675	675.5	13.5		1	1	1										
	670.5	18.5		13	23	25								671.5	RESIDUAL Tan-White Silty Fine SAND with Some Rock Fragments and Trace of Mica	17.5
	665.5	23.5												667.0	WEATHERED ROCK (Metadiorite)	22.0
	663.8	25.2												663.8		25.2
															Boring Terminated with Standard Penetration Test Refusal at Elevation 663.8 ft on Crystalline Rock (Meta-diorite)	

NCDOT BORE DOUBLE U2707_GEO_BRDG656_GINT.GPJ_NC_DOT.GDT 5/29/12

WBS 34845.1.1	TIP U-2707	COUNTY FORSYTH	GEOLOGIST Brandsen, J.
SITE DESCRIPTION Bridge No. 656 on SR 3000 (Idols Road) Over Muddy Creek			GROUND WTR (ft)
BORING NO. B1-A	STATION 88+65	OFFSET 16 ft LT	ALIGNMENT -L-
COLLAR ELEV. 688.8 ft	TOTAL DEPTH 45.1 ft	NORTHING 827,494	EASTING 1,599,182
DRILL RIG/HAMMER EFF./DATE SME R-2 DIETRICH D-50 87% 6/2/2011		DRILL METHOD SPT Core Boring	HAMMER TYPE Automatic
DRILLER Moseley, M.	START DATE 03/29/12	COMP. DATE 03/30/12	SURFACE WATER DEPTH N/A

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)		
			0.5ft	0.5ft	0.5ft	0	25	50	75	100						
690														688.8	GROUND SURFACE	0.0
685	687.8	1.0	2	1	2							W	ALLUVIAL Tan-Brown and Tan-Gray Silty Fine to Coarse SAND with Trace of Clay			
680	685.3	3.5	2	2	3							W				
675	682.8	6.0	1	1	2							Sat.				
670	680.3	8.5	1	1	2							Sat.				
665	675.3	13.5	1	15	7							Sat.				
660	670.3	18.5	48	77	33/0.2							RS-1				
655	668.4	20.4												672.8	WEATHERED ROCK (Meta-diorite)	16.0
650														668.4	CRYSTALLINE ROCK (Meta-diorite)	20.4
645														658.2	(Meta-diorite)	30.6
														643.7	Boring Terminated at Elevation 643.7 ft in Crystalline Rock (Meta-diorite)	45.1

- 1) Advanced 3-1/4" HSA to 20.4 Feet.
- 2) Advanced 2-15/16" Tricone to 20.4 Feet.
- 3) Advanced N Casing to 20.4 ft, 22.0 ft total used.
- 4) Advanced NQ Core From 20.4 to 45.1 ft.

NCDOT BORE DOUBLE U2707_GEO_BRD0656_GINT.GPJ NC_DOT_GDT_5/29/12

WBS 34845.1.1	TIP U-2707	COUNTY FORSYTH	GEOLOGIST Brandsen, J.
SITE DESCRIPTION Bridge No. 656 on SR 3000 (Idols Road) Over Muddy Creek			GROUND WTR (ft)
BORING NO. B1-A	STATION 88+65	OFFSET 16 ft LT	ALIGNMENT -L-
COLLAR ELEV. 688.8 ft	TOTAL DEPTH 45.1 ft	NORTHING 827,494	EASTING 1,599,182
DRILL RIG/HAMMER EFF./DATE SME R-2 DIETRICH D-50 87% 6/2/2011		DRILL METHOD SPT Core Boring	HAMMER TYPE Automatic
DRILLER Moseley, M.	START DATE 03/29/12	COMP. DATE 03/30/12	SURFACE WATER DEPTH N/A

ELEV (ft)	RUN ELEV (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	RUN		SAMP. NO.	STRATA		LOG	DESCRIPTION AND REMARKS	DEPTH (ft)
					REC. (%)	RQD (%)		REC. (%)	RQD (%)			
668.4	688.4	20.4	4.7	N=60/0.0 0:10/0.7 1:00/1.0 1:00/1.0 1:00/1.0 1:00/1.0	(0.8)	(0.0)		(3.6)	(1.1)		Begin Coring @ 20.4 ft	20.4
665	663.7	25.1	5.0	1:00/1.0 1:00/1.0 1:00/1.0 1:00/1.0	(2.3)	(1.1)					Moderate Severely Weathered Medium Hard Black-Gray (Meta-diorite) with Very Close Fracture Spacing with 1 joint @ 25° and 3 joints at 50 to 60°	
660	658.7	30.1	5.0	1:00/1.0 1:00/1.0 1:00/1.0 1:00/1.0	(46)	(22)						
655	653.7	35.1	5.0	1:30/1.0 1:30/1.0 1:30/1.0 1:30/1.0	(3.7)	(1.2)		(12.9)	(8.6)		Very Slightly to Moderately Weathered Medium Hard to Hard Black-Gray (Meta-diorite) with Close to Very Close Fracture Spacing with 4 joints @ 15 to 30°, 6 joints @ 60 to 75°, and 8 joints @ 90° qu=1288 KSF Axial R1=7, R2=13, R3=10, R4=12, R5=4 RMR=46 Rock Type E	30.6
650	648.7	40.1	5.0	1:35/1.0 1:35/1.0 1:35/1.0 1:35/1.0	(4.7)	(3.4)	RS-1					
645	643.7	45.1	5.0	1:45/1.0 1:45/1.0 1:45/1.0 1:45/1.0	(5.0)	(4.0)						


- 1) Advanced 3-1/4" HSA to 20.4 Feet.
- 2) Advanced 2-15/16" Tricone to 20.4 Feet.
- 3) Advanced N Casing to 20.4 ft, 22.0 ft total used.
- 4) Advanced NQ Core From 20.4 to 45.1 ft.

NCDOT CORE SINGLE U2707_GEO_BRD0656_GINT.GPJ NC_DOT_GDT_5/29/12

Project No.:34845.1.1	ID No.: U-2707	Location: Clemmons, NC	Boring No.: B1-A
Site Description: Bridge No. 656 on SR 3000 (Idols Road) over Muddy Creek			Driller: M. Moseley
Collar Elev.: 688.8 ft.	Core Size: NQ	Equipment: D-50	Geologist: J. Brandsen
Elev. at T.D.: 643.7 ft.	Total Depth: 45.1 ft.	Total Run: 24.7 ft.	Date: 3/30/12



Box 1 of 2
Top of Box @ 20.4 feet; Bottom of Box @ 35.1 feet



Box 2 of 2
Top of Box @ 35.1 feet; Bottom of Box @ 45.1 feet

WBS 34845.1.1	TIP U-2707	COUNTY FORSYTH	GEOLOGIST Brandsen, J.
SITE DESCRIPTION Bridge No. 656 on SR 3000 (Idols Road) Over Muddy Creek			GROUND WTR (ft)
BORING NO. B1-B	STATION 88+65	OFFSET 16 ft RT	ALIGNMENT -L-
COLLAR ELEV. 688.8 ft	TOTAL DEPTH 48.3 ft	NORTHING 827,473	EASTING 1,599,206
DRILL RIG/HAMMER EFF./DATE SME R-2 DIEDRICH D-50 87% 6/2/2011		DRILL METHOD SPT Core Boring	HAMMER TYPE Automatic
DRILLER Moseley, M.	START DATE 03/27/12	COMP. DATE 03/28/12	SURFACE WATER DEPTH N/A

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)		
			0.5ft	0.5ft	0.5ft	0	25	50	75	100						
690														688.8	GROUND SURFACE	0.0
	687.8	1.0												686.3	ALLUVIAL Tan Clayey Fine SAND with Trace Silt	2.5
685	685.3	3.5	2	4	4										Tan-Brown and Gray Silty Fine to Coarse SAND	
	682.8	6.0	1	1	3											
680	680.3	8.5	2	2	2											
675	675.3	13.5	2	6	12											
670	670.3	18.5	20	49	51/0.3											
665	665.3	23.5	40	53	47/0.3											
660	660.3	28.5	60/0.1													
655																
650																
645																


WBS 34845.1.1	TIP U-2707	COUNTY FORSYTH	GEOLOGIST Brandsen, J.
SITE DESCRIPTION Bridge No. 656 on SR 3000 (Idols Road) Over Muddy Creek			GROUND WTR (ft)
BORING NO. B1-B	STATION 88+65	OFFSET 16 ft RT	ALIGNMENT -L-
COLLAR ELEV. 688.8 ft	TOTAL DEPTH 48.3 ft	NORTHING 827,473	EASTING 1,599,206
DRILL RIG/HAMMER EFF./DATE SME R-2 DIEDRICH D-50 87% 6/2/2011		DRILL METHOD SPT Core Boring	HAMMER TYPE Automatic
DRILLER Moseley, M.	START DATE 03/27/12	COMP. DATE 03/28/12	SURFACE WATER DEPTH N/A

ELEV (ft)	RUN ELEV (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	RUN		SAMP. NO.	STRATA		LOG	DESCRIPTION AND REMARKS	DEPTH (ft)
					REC. (%)	RQD (%)		REC. (%)	RQD (%)			
660.2	680.2	28.6	4.7	1:35/0.7 1:35/1.0 1:35/1.0 1:35/1.0 1:35/1.0	(3.0) 64%	(1.7) 36%		(5.2) 57%	(2.1) 23%		Begin Coring @ 28.6 ft CRYSTALLINE ROCK Very Slight to Moderate Severely Weathered Hard to Medium Hard Black-Gray (Meta-diorite) with Close Fracture Spacing with 3 joints @ 20 to 25°, 2 joint @ 40°, 1 @ 60°, 7 joints @ 90°	28.6
655	655.5	33.3	5.0	1:40/1.0 1:40/1.0 1:40/1.0 1:40/1.0	(2.8) 56%	(1.0) 20%						
650	650.5	38.3	5.0	2:00/1.0 2:00/1.0 2:00/1.0 2:00/1.0	(5.0) 100%	(4.6) 92%		(10.6) 100%	(9.0) 85%		Fresh to Very Slightly Weathered Hard Black-Gray (Meta-diorite) with Close to Moderately Close Fracture Spacing with 7 joints @ 90° and 6 joints @ 60°	37.7
645	645.5	43.3	5.0	2:00/1.0 2:00/1.0 2:00/1.0 2:00/1.0	(5.0) 100%	(3.8) 76%						
	640.5	48.3									Boring Terminated at Elevation 640.5 ft in Crystalline Rock (Meta-diorite)	48.3

Project No.:34845.1.1	ID No.: U-2707	Location: Clemmons, NC	Boring No.: B1-B
Site Description: Bridge No. 656 on SR 3000 (Idols Road) over Muddy Creek			Driller: M. Moseley
Collar Elev.: 688.8 ft.	Core Size: NQ	Equipment: D-50	Geologist: J. Brandsen
Elev. at T.D.: 640.5 ft.	Total Depth: 48.3 ft.	Total Run: 19.7 ft.	Date: 3/28/12



Box 1 of 2
 Top of Box @ 28.6 feet; Bottom of Box @ 38.3 feet



Box 2 of 2
 Top of Box @ 38.3 feet; Bottom of Box @ 48.3 feet


WBS 34845.1.1		TIP U-2707		COUNTY FORSYTH		GEOLOGIST Brandsen, J.										
SITE DESCRIPTION Bridge No. 656 on SR 3000 (Idols Road) Over Muddy Creek							GROUND WTR (ft)									
BORING NO. B2-A		STATION 89+25		OFFSET 16 ft LT		ALIGNMENT -L-										
COLLAR ELEV. 688.9 ft		TOTAL DEPTH 49.9 ft		NORTHING 827,540		EASTING 1,599,220										
DRILL RIG/HAMMER EFF./DATE SME R-2 DIEDRICH D-50 87% 6/2/2011		DRILL METHOD SPT Core Boring		HAMMER TYPE Automatic												
DRILLER Moseley, M.		START DATE 04/02/12		COMP. DATE 04/03/12		SURFACE WATER DEPTH N/A										
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)		
			0.5ft	0.5ft	0.5ft	0	25	50	75	100						
690														688.9	GROUND SURFACE	0.0
	687.9	1.0	1	2	3							M		686.4	ALLUVIAL Brown Silty CLAY	2.5
685	685.4	3.5	2	4	4							M			Tan-Brown and Gray Silty Fine to Coarse SAND with Trace of Mica	
	682.9	6.0	1	1	1							Sat.				
680	680.4	8.5	1	WOH	WOH							Sat.				
	675.4	13.5	2	2	3							Sat.				
675	675.4	13.5	2	2	3									672.4	WEATHERED ROCK (Meta-diorite)	16.5
	670.4	18.5												668.8	CRYSTALLINE ROCK (Meta-diorite)	20.1
	668.8	20.1	100/0.4													
665																
660																
655														654.5	(Meta-diorite)	34.4
650																
645																
640														639.0	Boring Terminated at Elevation 639.0 ft in Crystalline Rock (Meta-diorite)	49.9
															1) Advanced 3-1/4" HSA to 20.1 Feet. 2) Advanced 2-15/16" Tricone to 20.1 Feet. 3) Advanced N Casing to 20.1 ft, 22.0 ft total used. 4) Advanced NQ Core from 20.1 to 49.9 ft.	

WBS 34845.1.1		TIP U-2707		COUNTY FORSYTH		GEOLOGIST Brandsen, J.						
SITE DESCRIPTION Bridge No. 656 on SR 3000 (Idols Road) Over Muddy Creek							GROUND WTR (ft)					
BORING NO. B2-A		STATION 89+25		OFFSET 16 ft LT		ALIGNMENT -L-						
COLLAR ELEV. 688.9 ft		TOTAL DEPTH 49.9 ft		NORTHING 827,540		EASTING 1,599,220						
DRILL RIG/HAMMER EFF./DATE SME R-2 DIEDRICH D-50 87% 6/2/2011		DRILL METHOD SPT Core Boring		HAMMER TYPE Automatic								
DRILLER Moseley, M.		START DATE 04/02/12		COMP. DATE 04/03/12		SURFACE WATER DEPTH N/A						
ELEV (ft)	RUN ELEV (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	RUN		SAMP. NO.	STRATA		LOG	DESCRIPTION AND REMARKS	DEPTH (ft)
					REC. (%)	RQD (%)		REC. (%)	RQD (%)			
668.8	668.8	20.1	4.8	N=60/0.0 0:30/0.8 0:45/1.0 0:45/1.0 0:45/1.0	(0.0)	(0.0)		(0.0)	(0.0)		Begin Coring @ 20.1 ft CRYSTALLINE ROCK No Recovery	20.1
665	664.0	24.9	5.0	0:30/1.0 0:30/1.0 0:30/1.0 0:30/1.0 0:30/1.0	(0.0)	(0.0)						
660	659.0	29.9	5.0	0:30/1.0 0:30/1.0 0:30/1.0 0:30/1.0 0:30/1.0	(0.5)	(0.3)						
655	654.0	34.9	5.0	1:55/1.0 1:55/1.0 1:55/1.0 1:55/1.0 1:55/1.0	(4.6)	(3.3)		(14.9)	(10.8)		Moderate to Very Slightly Weathered Medium Hard to Hard Black-Gray (Meta-diorite) with Close to Moderately Close Fracture Spacing with 4 joints @ 50 to 60°, 4 @ 60 to 70° and 11 joints @ 90°	34.4
650	649.0	39.9	5.0	2:30/1.0 2:30/1.0 2:30/1.0 2:30/1.0 2:30/1.0	(4.8)	(3.0)						
645	644.0	44.9	5.0	4:30/1.0 4:30/1.0 4:30/1.0 4:30/1.0 4:30/1.0	(5.0)	(4.2)						
640	639.0	49.9	5.0	4:30/1.0 4:30/1.0 4:30/1.0 4:30/1.0 4:30/1.0	100%	84%					Boring Terminated at Elevation 639.0 ft in Crystalline Rock (Meta-diorite)	49.9
											1) Advanced 3-1/4" HSA to 20.1 Feet. 2) Advanced 2-15/16" Tricone to 20.1 Feet. 3) Advanced N Casing to 20.1 ft, 22.0 ft total used. 4) Advanced NQ Core from 20.1 to 49.9 ft.	


NCDOT BORE DOUBLE U2707_GEO_BRD0656_GINT.GPJ NC_DOT.GDT 5/29/12

NCDOT CORE SINGLE U2707_GEO_BRD0656_GINT.GPJ NC_DOT.GDT 5/29/12

Project No.:34845.1.1	ID No.: U-2707	Location: Clemmons, NC	Boring No.: B2-A
Site Description: Bridge No. 656 on SR 3000 (Idols Road) over Muddy Creek			Driller: M. Moseley
Collar Elev.: 688.9 ft.	Core Size: NQ	Equipment: D-50	Geologist: J. Brandsen
Elev. at T.D.: 639.0 ft.	Total Depth: 49.9 ft.	Total Run: 29.8 ft.	Date: 4/03/12



Box 1 of 2
Top of Box @ 20.1 feet; Bottom of Box @ 39.9 feet



Box 2 of 2
Top of Box @ 39.9 feet; Bottom of Box @ 49.9 feet

WBS 34845.1.1	TIP U-2707	COUNTY FORSYTH	GEOLOGIST Brandsen, J.
SITE DESCRIPTION Bridge No. 656 on SR 3000 (Idols Road) Over Muddy Creek			GROUND WTR (ft)
BORING NO. B2-B	STATION 89+25	OFFSET 16 ft RT	ALIGNMENT -L-
COLLAR ELEV. 688.9 ft	TOTAL DEPTH 50.1 ft	NORTHING 827,519	EASTING 1,599,245
DRILL RIG/HAMMER EFF./DATE SME R-2 DIETRICH D-50 87% 6/2/2011		DRILL METHOD SPT Core Boring	HAMMER TYPE Automatic
DRILLER Moseley, M.	START DATE 04/03/12	COMP. DATE 04/03/12	SURFACE WATER DEPTH N/A

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)		
			0.5ft	0.5ft	0.5ft	0	25	50	75	100						
690														688.9	GROUND SURFACE	0.0
	687.9	1.0													ALLUVIAL	
	685.4	3.5	4	4	3										Brown and Gray Silty Fine to Coarse SAND with Some Wood Fragments and Little Quartz Gravel	
685	682.9	6.0	4	3	4											
	680.4	8.5	3	3	4											
680	675.4	13.5	1	1	3											
675	670.4	18.5	3	2	4											
670	665.4	23.5	23	35	65/0.3											
	663.5	25.4	56	49	51/0.3											
665	658.8	30.1														
660	653.8	35.1														
655																
650																
645																
640																

ICDOT BORE DOUBLE U2707_GEO_BRD0656_GINT.GPJ_NC_DOT.GDT 5/29/12

Boring Terminated at Elevation 638.8 ft in Crystalline Rock (Meta-diorite)

- 1) Advanced 3-1/4" HSA to 23.5 Feet.
- 2) Advanced 2-15/16" Tricone to 25.4 Feet.
- 3) Advanced N Casing to 25.4 ft, 27.0 ft total used.
- 4) Advanced NQ Core from 25.4 to 50.1 ft.

WBS 34845.1.1	TIP U-2707	COUNTY FORSYTH	GEOLOGIST Brandsen, J.
SITE DESCRIPTION Bridge No. 656 on SR 3000 (Idols Road) Over Muddy Creek			GROUND WTR (ft)
BORING NO. B2-B	STATION 89+25	OFFSET 16 ft RT	ALIGNMENT -L-
COLLAR ELEV. 688.9 ft	TOTAL DEPTH 50.1 ft	NORTHING 827,519	EASTING 1,599,245
DRILL RIG/HAMMER EFF./DATE SME R-2 DIETRICH D-50 87% 6/2/2011		DRILL METHOD SPT Core Boring	HAMMER TYPE Automatic
DRILLER Moseley, M.	START DATE 04/03/12	COMP. DATE 04/03/12	SURFACE WATER DEPTH N/A


ELEV (ft)	RUN ELEV (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	RUN		SAMP. NO.	STRATA		LOG	DESCRIPTION AND REMARKS	DEPTH (ft)
					REC. (%)	RQD (%)		REC. (%)	RQD (%)			
663.5	663.5	25.4	4.7	N=60/0.0 0:30/0.7 0:35/1.0 0:35/1.0 0:35/1.0 0:35/1.0	(0.0)	(0.0)		(0.0)	(0.0)		Begin Coring @ 25.4 ft	
660	658.8	30.1	5.0	N=60/0.1 0:45/1.0 0:45/1.0 0:45/1.0 0:45/1.0	(0.0)	(0.0)					CRYSTALLINE ROCK No Recovery	
655	653.8	35.1	5.0	N=60/0.1 0:50/1.0 1:35/1.0 1:35/1.0 1:35/1.0	(3.5)	(2.9)		(13.5)	(10.7)		Very Slight to Moderately Weathered Hard to Moderately Hard Black-Gray (Meta-diorite) with Close to Moderately Close Fracture Spacing with 2 joints @ 50°, 3 joints @ 60 to 70°, 5 joints @ 70 to 80°, 8 joints @ 90°	
650	648.8	40.1	5.0	2:00/1.0 2:00/1.0 2:00/1.0 2:00/1.0	(5.0)	(3.9)					qu=2515 KSF Axial R1=12, R2=17, R3=10, R4=12, R5=4 RMR=55 Rock Type E	
645	643.8	45.1	5.0	2:00/1.0 2:00/1.0 2:00/1.0	(5.0)	(3.9)	RS-2					
640	638.8	50.1	5.0	2:00/1.0 2:00/1.0 2:00/1.0	(5.0)	(3.9)						

ICDOT CORE SINGLE U2707_GEO_BRD0656_GINT.GPJ_NC_DOT.GDT 5/29/12


Boring Terminated at Elevation 638.8 ft in Crystalline Rock (Meta-diorite)

- 1) Advanced 3-1/4" HSA to 23.5 Feet.
- 2) Advanced 2-15/16" Tricone to 25.4 Feet.
- 3) Advanced N Casing to 25.4 ft, 27.0 ft total used.
- 4) Advanced NQ Core from 25.4 to 50.1 ft.

Project No.: 34845.1.1	ID No.: U-2707	Location: Clemmons, NC	Boring No.: B2-B
Site Description: Bridge No. 656 on SR 3000 (Idols Road) over Muddy Creek			Driller: M. Moseley
Collar Elev.: 688.9 ft.	Core Size: NQ	Equipment: D-50	Geologist: J. Brandsen
Elev. at T.D.: 638.8 ft.	Total Depth: 50.1 ft.	Total Run: 24.7 ft.	Date: 4/03/12



Box 1 of 2
 Top of Box @ 25.4 feet; Bottom of Box @ 45.1 feet



Box 2 of 2
 Top of Box @ 45.1 feet; Bottom of Box @ 50.1 feet

WBS 34845.1.1	TIP U-2707	COUNTY FORSYTH	GEOLOGIST Brandsen, J.
SITE DESCRIPTION Bridge No. 656 on SR 3000 (Idols Road) Over Muddy Creek			GROUND WTR (ft)
BORING NO. B3-A	STATION 90+01	OFFSET 16 ft LT	ALIGNMENT -L-
COLLAR ELEV. 691.3 ft	TOTAL DEPTH 54.8 ft	NORTHING 827,598	EASTING 1,599,269
DRILL RIG/HAMMER EFF./DATE SME R-2 DIEDRICH D-50 87% 6/2/2011		DRILL METHOD SPT Core Boring	HAMMER TYPE Automatic
DRILLER Moseley, M.	START DATE 03/29/12	COMP. DATE 03/29/12	SURFACE WATER DEPTH N/A

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)		
			0.5ft	0.5ft	0.5ft	0	25	50	75	100						
695																
690	690.3	1.0												691.3	GROUND SURFACE	0.0
	687.8	3.5	1	2	3										ALLUVIAL	
	685.3	6.0	2	2	3										Tan Clayey Fine SAND with Trace of SILT	
685															Tan-Brown and Gray Silty Fine to Coarse SAND	
	682.8	8.5	2	1	2											
680																
	679.3	12.0	1	WOH	1											
675																
	674.3	17.0	4	16	51											
670																
	669.3	22.0	47	49	51/0.3										RESIDUAL	
															Green-Black Silty Fine SAND	
665															WEATHERED ROCK	
	664.3	27.0													(Meta-diorite)	
	661.5	29.8													CRYSTALLINE ROCK	
660															(Meta-diorite)	
655																
650																
645																
640																

ICDDOT BORE DOUBLE U2707_GEO_BRD0656_GINT.GPJ_NC_DOT.GDT 5/29/12


WBS 34845.1.1	TIP U-2707	COUNTY FORSYTH	GEOLOGIST Brandsen, J.
SITE DESCRIPTION Bridge No. 656 on SR 3000 (Idols Road) Over Muddy Creek			GROUND WTR (ft)
BORING NO. B3-A	STATION 90+01	OFFSET 16 ft LT	ALIGNMENT -L-
COLLAR ELEV. 691.3 ft	TOTAL DEPTH 54.8 ft	NORTHING 827,598	EASTING 1,599,269
DRILL RIG/HAMMER EFF./DATE SME R-2 DIEDRICH D-50 87% 6/2/2011		DRILL METHOD SPT Core Boring	HAMMER TYPE Automatic
DRILLER Moseley, M.	START DATE 03/29/12	COMP. DATE 03/29/12	SURFACE WATER DEPTH N/A

ELEV (ft)	RUN ELEV (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	RUN		SAMP. NO.	STRATA		LOG	DESCRIPTION AND REMARKS	DEPTH (ft)
					REC. (%)	RQD (%)		REC. (%)	RQD (%)			
661.5												
660	661.5	29.8	5.0	N=60/0.0 1:15/1.0 1:15/1.0 1:15/1.0 1:15/1.0 1:15/1.0	(3.3)	(2.3)		(12.9)	(7.9)		Begin Coring @ 29.8 ft	
	656.5	34.8									CRYSTALLINE ROCK	
					66%	46%		64%	39%		Very Slight to Moderately Weathered	
											Hard to Medium Hard Black-Gray	
											(Meta-diorite) with Close Fracture Spacing	
655			5.0	1:30/1.0 1:30/1.0 1:30/1.0 1:30/1.0 1:30/1.0	(1.8)	(1.0)					Moderately Severely Weathered between 48.9' to 49.8'	
	651.5	39.8									with 1 Joint @ 50°, 3 joints @ 60° and 19 joints @ 75 to 90°	
650			5.0	1:15/1.0 1:15/1.0 1:15/1.0 1:30/1.0	(4.0)	(2.8)						
	646.5	44.8										
645			5.0	1:30/1.0 1:30/1.0 1:30/1.0 1:30/1.0	(3.6)	(1.8)						
	641.5	49.8			72%	36%						
640			5.0	1:45/1.0 1:45/1.0 1:45/1.0 1:45/1.0	(5.0)	(4.6)		(4.8)	(4.6)		Very Slight to Freshly Weathered	
	636.5	54.8			100%	92%		100%	98%		Hard to Very Hard Black-Gray	
											(Meta-diorite) with Close Fracture Spacing	
											with 2 joints @ 90°	
											qu=2425 KSF Axial	
											R1=12, R2=20, R3=10, R4=12, R5=4 RMR=58	
											Rock Type E	
											Boring Terminated at Elevation 636.5 ft in Crystalline Rock (Meta-diorite)	


NCDOT CORE SINGLE U2707_GEO_BRD0656_GINT.GPJ_NC_DOT.GDT 5/29/12

- 1) Advanced 3-1/4" HSA to 29.8 Feet.
- 2) Advanced 2-15/16" Tricone to 29.8 Feet.
- 3) Advanced N Casing to 29.8 ft, 32.0 ft total used.
- 4) Advanced NQ Core From 29.8 to 54.8 ft.

Project No.:34845.1.1	ID No.: U-2707	Location: Clemmons, NC	Boring No.: B3-A
Site Description: Bridge No. 656 on SR 3000 (Idols Road) over Muddy Creek			Driller: M. Moseley
Collar Elev.: 691.3 ft.	Core Size: NQ	Equipment: D-50	Geologist: J. Brandsen
Elev. at T.D.: 636.5 ft.	Total Depth: 54.8 ft.	Total Run: 25.0 ft.	Date: 3/29/12



Box 1 of 2
 Top of Box @ 29.8 feet; Bottom of Box @ 44.8 feet



Box 2 of 2
 Top of Box @ 44.8 feet; Bottom of Box @ 54.8 feet

WBS 34845.1.1	TIP U-2707	COUNTY FORSYTH	GEOLOGIST Brandsen, J.
SITE DESCRIPTION Bridge No. 656 on SR 3000 (Idols Road) Over Muddy Creek			GROUND WTR (ft)
BORING NO. B3-B	STATION 90+01	OFFSET 16 ft RT	ALIGNMENT -L-
COLLAR ELEV. 693.0 ft	TOTAL DEPTH 53.7 ft	NORTHING 827,577	EASTING 1,599,294
DRILL RIG/HAMMER EFF./DATE SME R-2 DIEDRICH D-50 87% 6/2/2011		DRILL METHOD SPT Core Boring	HAMMER TYPE Automatic
DRILLER Moseley, M.	START DATE 03/28/12	COMP. DATE 03/28/12	SURFACE WATER DEPTH N/A

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				
695													GROUND SURFACE	0.0
690	692.0	1.0	1	1	1							M	ALLUVIAL Tan-Brown and Gray Silty Fine to Coarse SAND	
685	689.5	3.5	1	2	2							M		
680	687.0	6.0	2	3	2							M		
675	684.5	8.5	2	1	2							M		
670	679.5	13.5	1	3	4							Sat.		
665	674.5	18.5	1	2	8							Sat.		
660	669.5	23.5	19	80	20/0.1								RESIDUAL Black-Gray Silty Fine SAND	24.0
655	664.5	28.5											WEATHERED ROCK (Meta-diorite)	
650		60/0.0											CRYSTALLINE ROCK (Meta-diorite)	29.4
645														
640														

NCDOT BORE DOUBLE U2707_GEO_BRD0656_GINT.GPJ NC_DOT_GDT 5/29/12

WBS 34845.1.1	TIP U-2707	COUNTY FORSYTH	GEOLOGIST Brandsen, J.
SITE DESCRIPTION Bridge No. 656 on SR 3000 (Idols Road) Over Muddy Creek			GROUND WTR (ft)
BORING NO. B3-B	STATION 90+01	OFFSET 16 ft RT	ALIGNMENT -L-
COLLAR ELEV. 693.0 ft	TOTAL DEPTH 53.7 ft	NORTHING 827,577	EASTING 1,599,294
DRILL RIG/HAMMER EFF./DATE SME R-2 DIEDRICH D-50 87% 6/2/2011		DRILL METHOD SPT Core Boring	HAMMER TYPE Automatic
DRILLER Moseley, M.	START DATE 03/28/12	COMP. DATE 03/28/12	SURFACE WATER DEPTH N/A


ELEV (ft)	RUN ELEV (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	RUN		SAMP. NO.	STRATA		LOG	DESCRIPTION AND REMARKS	DEPTH (ft)
					REC (%)	RQD (%)		REC (%)	RQD (%)			
663.6	663.6	29.4	4.3	1:00/1.0	(0.7)	(0.0)		(9.4)	(4.1)		Begin Coring @ 29.4 ft	
660	659.3	33.7	5.0	1:00/1.0	16%	0%		42%	18%		CRYSTALLINE ROCK	29.4
655	654.3	38.7	5.0	1:30/1.0	56%	20%					Moderate to Very Slightly Weathered Moderately Hard to Hard Black-Gray (Meta-diorite) with Close to Very Close Fracture Spacing with 6 joints @ 30 to 40°, 11 joints @ 80 to 90°	
650	649.3	43.7	5.0	1:30/1.0	6%	0%						
645	644.3	48.7	5.0	1:30/1.0	(3.1)	(1.5)						
640	639.3	53.7	5.0	2:10/1.0	90%	72%		(2.0)	(2.0)		Very Slight to Slightly Weathered Hard to Very Hard Black-Gray (Meta-diorite) with Close Fracture Spacing with 1 joint @ 10°, 2 joints @ 70° and 1 joint @ 90°	53.7

NCDOT CORE SINGLE U2707_GEO_BRD0656_GINT.GPJ NC_DOT_GDT 5/29/12


- Boring Terminated at Elevation 639.3 ft in Crystalline Rock (Meta-diorite)
- 1) Advanced 3-1/4" HSA to 28.5 Feet.
 - 2) Advanced 2-15/16" Tricone to 29.4 Feet.
 - 3) Advanced N Casing to 29.4 ft, 32.0 ft total used.
 - 4) Advanced NQ Core From 29.4 to 53.7 ft.

- 1) Advanced 3-1/4" HSA to 28.5 Feet.
- 2) Advanced 2-15/16" Tricone to 29.4 Feet.
- 3) Advanced N Casing to 29.4 ft, 32.0 ft total used.
- 4) Advanced NQ Core From 29.4 to 53.7 ft.

Project No. 34845.1.1	ID No.: U-2707	Location: Clemmons, NC	Boring No.: B3-B
Site Description: Bridge No. 656 on SR 3000 (Idols Road) over Muddy Creek			Driller: M. Moseley
Collar Elev.: 693.0 ft.	Core Size: NQ	Equipment: D-50	Geologist: J. Brandsen
Elev. at T.D.: 639.3 ft.	Total Depth: 53.7 ft.	Total Run: 24.3 ft.	Date: 3/28/12



Box 1 of 2
Top of Box @ 29.4 feet; Bottom of Box @ 48.7 feet



Box 2 of 2
Top of Box @ 48.7 feet; Bottom of Box @ 53.7 feet

WBS 34845.1.1	TIP U-2707	COUNTY FORSYTH	GEOLOGIST Brandsen, J.
SITE DESCRIPTION Bridge No. 656 on SR 3000 (Idols Road) Over Muddy Creek			GROUND WTR (ft)
BORING NO. B4-A	STATION 91+05	OFFSET 16 ft LT	ALIGNMENT -L-
COLLAR ELEV. 694.1 ft	TOTAL DEPTH 50.2 ft	NORTHING 827,677	EASTING 1,599,336
DRILL RIG/HAMMER EFF./DATE SME R-2 DIEDRICH D-50 87% 6/2/2011		DRILL METHOD SPT Core Boring	HAMMER TYPE Automatic
DRILLER Moseley, M.	START DATE 03/21/12	COMP. DATE 03/21/12	SURFACE WATER DEPTH N/A

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				
695													GROUND SURFACE	0.0
	693.1	1.0	1	1	2						M		ALLUVIAL Tan Silty Fine SAND	
	690.6	3.5	3	5	7						M		Tan Clayey Fine SAND	4.5
	688.1	6.0	5	7	11						Sat.			
	685.6	8.5	7	10	10									
	680.6	13.5	25	55	45						M		RESIDUAL Brown-Green Silty Fine SAND	12.0
	675.6	18.5	8	29	41						M			
	670.6	23.5	14	20	80/0.4									
	665.6	28.5	100/0.4										WEATHERED ROCK (Meta-diorite)	24.5
	662.0	32.1	60/0.0										CRYSTALLINE ROCK (Meta-diorite)	32.1
													(Meta-diorite)	38.4
											RS-4			


Boring Terminated at Elevation 643.9 ft in Crystalline Rock (Meta-diorite)

- Advanced 3-1/4" HSA to 32.1 Feet.
- Advanced 2-15/16" Tricone to 32.1 Feet.
- Advanced N Casing to 32.0 ft, 33.0 ft total used.
- Advanced NQ Core From 32.1 to 50.2 ft.


WBS 34845.1.1	TIP U-2707	COUNTY FORSYTH	GEOLOGIST Brandsen, J.
SITE DESCRIPTION Bridge No. 656 on SR 3000 (Idols Road) Over Muddy Creek			GROUND WTR (ft)
BORING NO. B4-A	STATION 91+05	OFFSET 16 ft LT	ALIGNMENT -L-
COLLAR ELEV. 694.1 ft	TOTAL DEPTH 50.2 ft	NORTHING 827,677	EASTING 1,599,336
DRILL RIG/HAMMER EFF./DATE SME R-2 DIEDRICH D-50 87% 6/2/2011		DRILL METHOD SPT Core Boring	HAMMER TYPE Automatic
DRILLER Moseley, M.	START DATE 03/21/12	COMP. DATE 03/21/12	SURFACE WATER DEPTH N/A

ELEV (ft)	RUN ELEV (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	RUN		SAMP. NO.	STRATA		LOG	DESCRIPTION AND REMARKS	DEPTH (ft)
					REC. (%)	RQD (%)		REC. (%)	RQD (%)			
											Begin Coring @ 32.1 ft	
	662.0	32.1	3.1	N=60/0.0 0:15/0.1 1:05/1.0 1:05/1.0 1:05/1.0	(2.4) 77%	(1.3) 42%		(5.0) 79%	(3.1) 49%		CRYSTALLINE ROCK	32.1
	658.9	35.2	5.0	1:05/1.0 1:15/1.0 1:15/1.0 1:15/1.0 1:15/1.0	(4.4) 88%	(3.6) 72%					Moderately to Slightly Weathered Moderately Hard to Hard Black-Gray (Meta-diorite) with Close Fracture Spacing with 3 joints @ 70° & 4 joints @ 40 to 50°	
	653.9	40.2	5.0	1:45/1.0 1:45/1.0 1:45/1.0 1:45/1.0	(4.9) 98%	(4.0) 80%		(11.7) 99%	(9.8) 83%		Very Slight to Freshly Weathered Hard to Very Hard Black-Gray (Meta-diorite) with Close to Moderately Close Fracture Spacing with 1 joint @50°, 5 joints @ 60 to 70°, 9 @ 80 to 90° qu=2128 KSF Axial R1=7, R2=17, R3=10, R4=12, R5=4 RMR=50 Rock Type E	38.4
	648.9	45.2	5.0	1:45/1.0 1:45/1.0 1:45/1.0	(5.0) 100%	(4.0) 80%						
	643.9	50.2					RS-4				Boring Terminated at Elevation 643.9 ft in Crystalline Rock (Meta-diorite)	50.2

Project No.:34845.1.1	ID No.: U-2707	Location: Clemmons, NC	Boring No.: B4-A
Site Description: Bridge No. 656 on SR 3000 (Idols Road) over Muddy Creek			Driller: M. Moseley
Collar Elev.: 694.1 ft.	Core Size: NQ	Equipment: D-50	Geologist: J. Brandsen
Elev. at T.D.: 643.9 ft.	Total Depth: 54.8 ft.	Total Run: 18.1 ft.	Date: 3/21/12



Box 1 of 2
Top of Box @ 32.1 feet; Bottom of Box @ 40.2 feet



Box 2 of 2
Top of Box @ 40.2 feet; Bottom of Box @ 50.2 feet



NCDOT GEOTECHNICAL ENGINEERING UNIT
BORELOG REPORT

WBS 34845.1.1	TIP U-2707	COUNTY FORSYTH	GEOLOGIST Brandsen, J.
SITE DESCRIPTION Bridge No. 656 on SR 3000 (Idols Road) Over Muddy Creek			GROUND WTR (ft)
BORING NO. B4-B	STATION 91+05	OFFSET 16 ft RT	ALIGNMENT -L-
COLLAR ELEV. 693.1 ft	TOTAL DEPTH 50.3 ft	NORTHING 827,657	EASTING 1,599,361
DRILL RIG/HAMMER EFF./DATE SME R-2 DIEDRICH D-50 87% 6/2/2011		DRILL METHOD SPT Core Boring	HAMMER TYPE Automatic
DRILLER Moseley, M.	START DATE 03/21/12	COMP. DATE 03/22/12	SURFACE WATER DEPTH N/A

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100					
695															
693.1														GROUND SURFACE	0.0
692.1	692.1	1.0	1	WOH	1									ALLUVIAL	
689.6	689.6	3.5	2		2	4								Tan-Brown Silty Fine SAND	
687.1	687.1	6.0	6		8	12								RESIDUAL	
684.6	684.6	8.5	6		16	24								Brown-Green-Black Silty Fine SAND	
682.1														WEATHERED ROCK	11.0
682.1														(Meta-diorite)	
679.6	679.6	13.5	48		50	50/0.4									
677.5	674.6	18.5	52		74	26/0.2									
671.7	671.7	21.4	60/0.0											CRYSTALLINE ROCK	21.4
670														(Meta-diorite)	
665															
660															
655															
650															
645															

Boring Terminated at Elevation 642.8 ft in Crystalline Rock (Meta-diorite)

- 1) Advanced 3-1/4" HSA to 21.4 Feet.
- 2) Advanced 2-15/16" Tricone to 21.4 Feet.
- 3) Advanced N Casing to 21.4 ft, 22.0 ft total used.
- 4) Advanced NQ Core From 21.4 to 50.3 ft.

ICDOT BORE DOUBLE U2707_GEO_BRDG0656_GINT.GPJ_NC_DOT.GDT 5/29/12




NCDOT GEOTECHNICAL ENGINEERING UNIT
CORE BORING REPORT

WBS 34845.1.1	TIP U-2707	COUNTY FORSYTH	GEOLOGIST Brandsen, J.
SITE DESCRIPTION Bridge No. 656 on SR 3000 (Idols Road) Over Muddy Creek			GROUND WTR (ft)
BORING NO. B4-B	STATION 91+05	OFFSET 16 ft RT	ALIGNMENT -L-
COLLAR ELEV. 693.1 ft	TOTAL DEPTH 50.3 ft	NORTHING 827,657	EASTING 1,599,361
DRILL RIG/HAMMER EFF./DATE SME R-2 DIEDRICH D-50 87% 6/2/2011		DRILL METHOD SPT Core Boring	HAMMER TYPE Automatic
DRILLER Moseley, M.	START DATE 03/21/12	COMP. DATE 03/22/12	SURFACE WATER DEPTH N/A


ELEV (ft)	RUN ELEV (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	RUN		SAMP. NO.	STRATA		LOG	DESCRIPTION AND REMARKS	DEPTH (ft)
					REC (%)	RQD (%)		REC (%)	RQD (%)			
671.7												
670	671.7	21.4	3.9	N=60/0.0 0:30/0.9 1:00/1.0 1:00/1.0 1:00/1.0	(2.0)	(1.0)		(3.3)	(1.4)		Begin Coring @ 21.4 ft	
665	667.8	25.3	5.0	0:45/1.0 0:45/1.0 0:45/1.0 0:45/1.0	(1.0)	(0.4)					CRYSTALLINE ROCK	21.4
660	662.8	30.3	5.0	0:30/1.0 0:30/1.0 0:30/1.0 0:30/1.0	(0.3)	(0.0)					Moderate to Slightly Weathered Moderately Hard to Hard Black-Gray (Meta-diorite) with Close Fracture Spacing with 1 joint @ 50°, 1 joint @ 70° and 3 joints @ 80 to 90°	
655	657.8	35.3	5.0	1:15/1.0 1:15/1.0 1:15/1.0 1:15/1.0	(3.3)	(1.9)		(10.9)	(5.8)		Slightly to Very Slightly Weathered Moderately Hard to Hard Black-Gray (Meta-diorite) with Very Close to Close Fracture Spacing Quartzite Between 45.4' and 46.8' with 4 joints @ 40°, 3 joints @ 55 to 60° and 10 joints @ 80 to 90°	35.3
650	652.8	40.3	5.0	2:00/1.0 2:00/1.0 2:00/1.0 2:00/1.0	(3.8)	(2.0)						
645	647.8	45.3	5.0	1:45/1.0 1:45/1.0 1:45/1.0 1:45/1.0	(3.8)	(1.9)						
642.8	642.8	50.3									Boring Terminated at Elevation 642.8 ft in Crystalline Rock (Meta-diorite)	50.3

NCDOT CORE SINGLE U2707_GEO_BRDG0656_GINT.GPJ_NC_DOT.GDT 5/29/12

Project No.: 34845.1.1	ID No.: U-2707	Location: Clemmons, NC	Boring No.: B4-B
Site Description: Bridge No. 656 on SR 3000 (Idols Road) over Muddy Creek			Driller: M. Moseley
Collar Elev.: 693.1 ft.	Core Size: NQ	Equipment: D-50	Geologist: J. Brandsen
Elev. at T.D.: 642.8 ft.	Total Depth: 50.3 ft.	Total Run: 28.9 ft.	Date: 3/22/12



Box 1 of 2
Top of Box @ 21.4 feet; Bottom of Box @ 40.3 feet



Box 2 of 2
Top of Box @ 40.3 feet; Bottom of Box @ 50.3 feet

WBS 34845.1.1		TIP U-2707		COUNTY FORSYTH		GEOLOGIST Brandsen, J.							
SITE DESCRIPTION Bridge No. 656 on SR 3000 (Idols Road) Over Muddy Creek							GROUND WTR (ft)						
BORING NO. B5-A		STATION 91+75		OFFSET 16 ft LT		ALIGNMENT -L-							
COLLAR ELEV. 695.0 ft		TOTAL DEPTH 44.9 ft		NORTHING 827,731		EASTING 1,599,382							
DRILL RIG/HAMMER EFF./DATE SME R-2 DIEDRICH D-50 87% 6/2/2011		DRILL METHOD SPT Core Boring		HAMMER TYPE Automatic									
DRILLER Moseley, M.		START DATE 03/15/12		COMP. DATE 03/19/12		SURFACE WATER DEPTH N/A							
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT				SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)
			0.5ft	0.5ft	0.5ft	0	25	50	75				
695												GROUND SURFACE	0.0
	694.0	1.0	3	2	3						M	ALLUVIAL Tan-Orange Fine Sandy Silty CLAY	
	691.5	3.5	5	8	12						M		
690	689.0	6.0	5	6	6						M	Tan-Orange Clayey Fine SAND	5.5
	686.5	8.5	15	16	13						M	RESIDUAL Gray-Orange Silty Coarse to Fine SAND	8.0
685	681.5	13.5	11	15	27						M		
680	676.5	18.5	40	60/0.4							M		
675	671.5	23.5	100/0.5									WEATHERED ROCK (Meta-diorite)	19.0
670	666.5	28.5	100/0.4										
665	665.1	29.9	60/0.0									CRYSTALLINE ROCK (Meta-diorite)	29.9
660												(Meta-diorite)	34.4
655													44.9

WBS 34845.1.1		TIP U-2707		COUNTY FORSYTH		GEOLOGIST Brandsen, J.					
SITE DESCRIPTION Bridge No. 656 on SR 3000 (Idols Road) Over Muddy Creek							GROUND WTR (ft)				
BORING NO. B5-A		STATION 91+75		OFFSET 16 ft LT		ALIGNMENT -L-					
COLLAR ELEV. 695.0 ft		TOTAL DEPTH 44.9 ft		NORTHING 827,731		EASTING 1,599,382					
DRILL RIG/HAMMER EFF./DATE SME R-2 DIEDRICH D-50 87% 6/2/2011		DRILL METHOD SPT Core Boring		HAMMER TYPE Automatic							
DRILLER Moseley, M.		START DATE 03/15/12		COMP. DATE 03/19/12		SURFACE WATER DEPTH N/A					
ELEV (ft)	RUN ELEV (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	RUN		STRATA		LOG	DESCRIPTION AND REMARKS	DEPTH (ft)
					REC (%)	RQD (%)	REC (%)	RQD (%)			
695											
	665.1	29.9	5.0	1:05/1.0	(3.0)	(1.0)	(3.3)	(1.4)		Begin Coring @ 29.9 ft	29.9
	660.1	34.9		1:05/1.0	60%	20%	73%	31%		CRYSTALLINE ROCK	
660				1:05/1.0						Slight to Very Slightly Weathered	
				1:05/1.0						Hard Gray-Black	
				1:05/1.0						(Meta-diorite) with Close to Moderately Close Fracture Spacing	34.4
				1:05/1.0						with 4 joints @ 60 to 70° and 1 joint @ 90°	
665	655.1	39.9		1:20/1.0	(4.5)	(3.9)	(9.9)	(8.8)		Very Slightly to Freshly Weathered	
				1:20/1.0	90%	78%	94%	84%		Very Hard Gray-Black	
				1:20/1.0						(Meta-diorite) with Moderately Close Fracture Spacing	
				1:20/1.0						with 1 joint @ 30°, 2 joints @ 50° and 5 joints @ 90°	
				1:55/1.0	(4.9)	(4.4)					
	650.1	44.9		1:55/1.0	98%	88%				Boring Terminated at Elevation 650.1 ft in Crystalline Rock (Meta-diorite)	44.9
				1:55/1.0							
				1:55/1.0							
				1:55/1.0							

CDDT BORE DOUBLE U2707_GEO_BRD0656_GINT.GPJ NC_DOT.GDT 5/29/12


NCDOT CORE SINGLE U2707_GEO_BRD0656_GINT.GPJ NC_DOT.GDT 5/29/12

Boring Terminated at Elevation 650.1 ft in Crystalline Rock (Meta-diorite)


- 1) Advanced 3-1/4" HSA to 29.2 Feet.
- 2) Advanced 2-15/16" Tricone to 29.9 Feet.
- 3) Advanced N Casing to 30.0, 32.0 ft total used.
- 4) Advanced NQ Core From 29.9 to 44.9 ft.

- 1) Advanced 3-1/4" HSA to 29.2 Feet.
- 2) Advanced 2-15/16" Tricone to 29.9 Feet.
- 3) Advanced N Casing to 30.0, 32.0 ft total used.
- 4) Advanced NQ Core From 29.9 to 44.9 ft.

Project No.:34845.1.1	ID No.: U-2707	Location: Clemmons, NC	Boring No.: B5-A
Site Description: Bridge No. 656 on SR 3000 (Idols Road) over Muddy Creek			Driller: M. Moseley
Collar Elev.: 695.0 ft.	Core Size: NQ	Equipment: D-50	Geologist: J. Brandsen
Elev. at T.D.: 650.1 ft.	Total Depth: 54.8 ft.	Total Run: 44.9 ft.	Date: 3/15/12




Box 1 of 2
 Top of Box @ 29.9 feet; Bottom of Box @ 39.9 feet



Box 2 of 2
 Top of Box @ 39.9 feet; Bottom of Box @ 44.9 feet

WBS 34845.1.1	TIP U-2707	COUNTY FORSYTH	GEOLOGIST Brandsen, J.
SITE DESCRIPTION Bridge No. 656 on SR 3000 (Idols Road) Over Muddy Creek			GROUND WTR (ft)
BORING NO. B5-B	STATION 91+75	OFFSET 16 ft RT	ALIGNMENT -L-
COLLAR ELEV. 694.5 ft	TOTAL DEPTH 45.4 ft	NORTHING 827,710	EASTING 1,599,406
DRILL RIG/HAMMER EFF./DATE SME R-2 DIETRICH D-50 87% 6/2/2011		DRILL METHOD SPT Core Boring	HAMMER TYPE Automatic
DRILLER Moseley, M.	START DATE 03/20/12	COMP. DATE 03/21/12	SURFACE WATER DEPTH N/A

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				
695													694.5 GROUND SURFACE 0.0	
	693.5	1.0											693.0 ALLUVIAL Tan-Orange Clayey Fine SAND 1.5	
	691.0	3.5	4	25	40								689.0 RESIDUAL Gray-White-Tan Silty Fine SAND 5.5	
690			23	33	32								Tan-Gray-White-Brown Clayey Fine SAND with Some Rock Fragments and Trace of Mica	
	688.5	6.0	7	9	14									
	686.0	8.5	18	20	12									
685														
	681.0	13.5	14	23	47									
	676.0	18.5	50	88	12/0.1									
675														
	671.0	23.5												
	670.3	24.2	100/0.3											
670														
665														
660														
655														
650														



Boring Terminated at Elevation 649.1 ft in Crystalline Rock (Meta-diorite)

- 1) Advanced 3-1/4" HSA to 24.2 Feet.
- 2) Advanced 2-15/16" Tricone to 24.2 Feet.
- 3) Advanced N Casing to 24.2 ft, 25.0 ft total used.
- 4) Advanced NQ Core From 24.2 to 45.4 ft.

ICDOT BORE DOUBLE U2707_GEO_BRD0656_GINT.GPJ NC_DOT.GDT 5/29/12

WBS 34845.1.1	TIP U-2707	COUNTY FORSYTH	GEOLOGIST Brandsen, J.
SITE DESCRIPTION Bridge No. 656 on SR 3000 (Idols Road) Over Muddy Creek			GROUND WTR (ft)
BORING NO. B5-B	STATION 91+75	OFFSET 16 ft RT	ALIGNMENT -L-
COLLAR ELEV. 694.5 ft	TOTAL DEPTH 45.4 ft	NORTHING 827,710	EASTING 1,599,406
DRILL RIG/HAMMER EFF./DATE SME R-2 DIETRICH D-50 87% 6/2/2011		DRILL METHOD SPT Core Boring	HAMMER TYPE Automatic
DRILLER Moseley, M.	START DATE 03/20/12	COMP. DATE 03/21/12	SURFACE WATER DEPTH N/A


ELEV (ft)	RUN ELEV (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	RUN		SAMP. NO.	STRATA		LOG	DESCRIPTION AND REMARKS	DEPTH (ft)
					REC. (%)	RQD (%)		REC. (%)	RQD (%)			
670.3												
	670.3	24.2	1.2	N=60/0.0	(0.6)	(0.8)		(8.8)	(4.2)		Begin Coring @ 24.2 ft	
	668.1	25.4	5.0	0:15/0.2	50%	67%		79%	38%		CRYSTALLINE ROCK	24.2
				1:10/1.0	(3.4)	(1.5)					Moderately to Very Slightly Weathered	
				1:10/1.0	68%	30%					Moderately Hard to Hard Black-Gray	
665				1:10/1.0							(Meta-diorite) with Moderately Close To Very Close Fracture Spacing	
	664.1	30.4	5.0	1:10/1.0	(4.8)	(1.9)					with 1 joint @ 30°, 4 joint @ 50 to 60°, 15 joints @ 80 to 90°	
				1:10/1.0								
				1:15/1.0	96%	38%						
660				1:15/1.0								
	659.1	35.4	5.0	1:15/1.0	(4.8)	(4.3)		(9.8)	(9.0)		Very Slightly to Freshly Weathered	35.4
				2:05/1.0	96%	86%		98%	90%		Hard to Very Hard Black-Gray	
				1:15/1.0							(Meta-diorite) with Moderately Close Fracture Spacing	
655				2:30/1.0							with 2 joints @ 30 to 40°, 1 joint @ 60°, 5 joints @ 90°	
	654.1	40.4	5.0	2:30/1.0	(5.0)	(4.7)						
				2:05/1.0								
				2:05/1.0	100%	94%						
650				2:05/1.0								
	649.1	45.4		2:05/1.0							Boring Terminated at Elevation 649.1 ft in Crystalline Rock (Meta-diorite)	45.4

Boring Terminated at Elevation 649.1 ft in Crystalline Rock (Meta-diorite)


- 1) Advanced 3-1/4" HSA to 24.2 Feet.
- 2) Advanced 2-15/16" Tricone to 24.2 Feet.
- 3) Advanced N Casing to 24.2 ft, 25.0 ft total used.
- 4) Advanced NQ Core From 24.2 to 45.4 ft.

NCDOT CORE SINGLE U2707_GEO_BRD0656_GINT.GPJ NC_DOT.GDT 5/29/12



Project No.: 34845.1.1	ID No.: U-2707	Location: Clemmons, NC	Boring No.: B5-B
Site Description: Bridge No. 656 on SR 3000 (Idols Road) over Muddy Creek			Driller: M. Moseley
Collar Elev.: 694.5 ft.	Core Size: NQ	Equipment: D-50	Geologist: J. Brandsen
Elev. at T.D.: 649.1 ft.	Total Depth: 45.4 ft.	Total Run: 21.2 ft.	Date: 3/20/12



Box 1 of 2
Top of Box @ 24.2 feet; Bottom of Box @ 35.4 feet



Box 2 of 2
Top of Box @ 35.4 feet; Bottom of Box @ 45.4 feet



NCDOT BORE DOUBLE U2707 GEO_BRDG0656_GINT.GPJ NC_DOT.GDT 5/29/12

SUMMARY OF LABORATORY TEST DATA
Soil Classification and Gradation




Quality Assurance

S&ME, Inc. Raleigh, 3201 Spring Forest Road, Raleigh, North Carolina 27616			
S&ME Project #:	1051-12-089B	Date Report:	4/13/2012
State Project No.:	34845.1.1	County: Forsyth	Date Tested: 4/11 - 4/13/12
Federal ID No.:	STP-3000(1)	TIP No. U-2707	
Project Name:	Bridge No.656 on -L- SR 3000 (Idols Road) over Muddy Creek		
Client Name:	NCDOT	Client Address:	Raleigh, North Carolina

Boring No.	Sample No.	Sample Depth (ft)	AASHTO Classification	Total % Passing					Total Mortar Fraction (%)				LL	PL	PI	Organic Content %	Moisture Content %
				Sieve #					Coarse Sand	Fine Sand	Silt	Clay					
				10	40	60	200	270									
EB2-A	ST-1	3 - 5 ft.	A-6 (13)	100	99	97	68.8	56.8	3	40	18	39	39	18	21	ND	19.4

References / Comments / Deviations: ND=Not Determined.

AASHTO T88: Particle Size Analysis of Soils as Modified by the NCDOT AASHTO T89: Determining the Liquid Limit of Soils
AASHTO T90: Determining the Plastic Limit & Plasticity Index of Soils AASHTO T265: Laboratory Determination of Moisture Content of Soils
AASHTO M145: The Classification of Soils and Soil Aggregate Mixtures for Highway Construction Purposes

<u>Mal Krajan, ET</u>		<u>104-01-0703</u>	<u>Abner F. Riggs, Jr., P.E.</u>	<u>Senior Engineer</u>
<i>Technician Name:</i>	<i>Signature</i>	<i>Certification #</i>	<i>Technical Responsibility:</i>	<i>Position</i>

This report shall not be reproduced, except in full, without the written approval of S&ME, Inc.

**UNCONFINED COMPRESSION
(ASTM D7012 Method C)**



S&ME, Inc. - Knoxville 1413 Topside Road, Louisville, TN 37777

Project: 34845.1.1, TIP No. U-2707
Description: Bridge No. 656 on - L - (SR3000) Idols Road over Muddy Creek
County: Forsyth County, North Carolina
Federal ID No.: STP-3000(1)
S&ME Job No.: 1051-12-089B
Date: 4/13/2012
Tested By: Jason B. Burgess
Rock Type: Meta-diorite

Sample No.	Boring Location	Depth (ft)	Specimen Dimension, in.		Area (in ²)	Bulk Density (lb/ft ³)	Loading Rate (psi/sec)	Max. Load (lb)	Strength (psi)	Moisture (%)
			Length	Diameter						
RS-1	B1-A	36.1 - 37.1	4.35	1.98	3.08	181.3	94	27,550	8,945	0.1
RS-2	B2-B	43.8 - 45.1	4.35	1.97	3.05	182.9	89	53,260	17,462	0.1

NOTES: Bulk Density includes any moisture that is within the specimen.



Bridge No. 656 - L - (SR3000)
Idols Road over Muddy Creek
1051-12-089B

B1-A RS-1

36.1' - 37.1'



Bridge No. 656 - L - (SR3000)
Idols Road over Muddy Creek
1051-12-089B

B1-A RS-1

36.1' - 37.1'



Bridge No. 656 - L - (SR3000)
Idols Road over Muddy Creek
1051-12-089B

B2-B RS-2

43.8' - 45.1'



Bridge No. 656 - L - (SR3000)
Idols Road over Muddy Creek
1051-12-089B

B2-B RS-2

43.8' - 45.1'

**UNCONFINED COMPRESSION
(ASTM D7012 Method C)**




S&ME, Inc. - Knoxville 1413 Topside Road, Louisville, TN 37777

Project: 34845.1.1, TIP No. U-2707
Description: Bridge No. 656 on - L - (SR3000) Idols Road over Muddy Creek
County: Forsyth County, North Carolina
Federal ID No.: STP-3000(1)
S&ME Job No.: 1051-12-089B
Date: 4/13/2012
Tested By: Jason B. Burgess
Rock Type: Meta-diorite

Sample No.	Boring Location	Depth (ft)	Specimen Dimension, in.		Area (in ²)	Bulk Density (lb/ft ³)	Loading Rate (psi/sec)	Max. Load (lb)	Strength (psi)	Moisture (%)
			Length	Diameter						
RS-3	B3-A	53.2 - 55.2	4.39	1.99	3.11	182.3	94	52,380	16,842	0.1
RS-4	B4-A	47.2 - 48.2	4.27	1.98	3.08	177.1	92	45,510	14,776	0.1

NOTES: Bulk Density includes any moisture that is within the specimen.





Photograph No. 1: This photograph was taken from the South approach along the centerline of the -L- alignment looking Northeast.



Photograph No. 2: This photograph was taken from the North approach along the centerline of the -L- alignment looking Southwest.