

PROJECT NO.	SHEET NO.	TOTAL NO.
2016CPT.14.13.10501.1	4	

### SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	AGGREGATE SHOULDER BORROW TONS	SHOULDER RECONSTRUCTION SMI	3" MILLING SY	SHOULDER MILLING SY	INCIDENTAL MILLING SY	BASE COURSE, B25.0B TONS	INTER-MEDIATE COURSE, I19.0C TONS	SURFACE COURSE, S9.5C TONS	ASPHALT BINDER FOR PLANT MIX TONS
2016CPT.14.13.10501.1	Jackson	1	US 23/441 SOUTH TO FRANKLIN	FROM .05 MILES WEST OF MACON CO. LINE TO SR-1300 PUMPKIN TOWN RD	1	2	MU	YES	NO	2.2	68	675	4.4	73,250	950	100	350	13,777	8,570	1,182
<b>GRAND TOTAL FOR PROJ NO. 2016CPT.14.13.10501.1</b>										<b>2.2</b>		<b>675</b>	<b>4.4</b>	<b>73,250</b>	<b>950</b>	<b>100</b>	<b>350</b>	<b>13,777</b>	<b>8,570</b>	<b>1,182</b>

### THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP	LANES	LANE TYPE	LENGTH	WIDTH	4413000000-E	4457000000-N	4695000000-E	4710000000-E	4721000000-E	4725000000-E		4810000000-E		4890000000-E		4905000000-N
										WORK ZONE ADVANCE/GENERAL WARNING SIGNING SF	TEMPORARY TRAFFIC CONTROL LS	8" X 90 M WHITE THERMO LF	24" X 120 M WHITE THERMO LF	THERMO MSG SCHOOL 120 M EA	THERMO LT ARROW 90 M EA	THERMO RT ARROW 90 M EA	4" YELLOW PAINT LF	4" WHITE PAINT LF	4" X 50 M WHITE THERMO LF	4" X 50 M YELLOW THERMO LF	SNOW PLOWABLE MARKERS EA
2016CPT.14.13.10501.1	Jackson	1	US 23/441 SOUTH TO FRANKLIN	FROM .05 MILES WEST OF MACON CO. LINE TO SR-1300 PUMPKIN TOWN RD	1	2	MU	2.2	68	246	*	120	200	12	66	3	26,112	26,112	26,112	26,112	620
<b>GRAND TOTAL FOR PROJ NO. 2016CPT.14.13.10501.1</b>								<b>2.2</b>		<b>246</b>	<b>1</b>	<b>120</b>	<b>200</b>	<b>12</b>	<b>66</b>	<b>3</b>	<b>26,112</b>	<b>26,112</b>	<b>26,112</b>	<b>26,112</b>	<b>620</b>
															<b>69</b>		<b>52,224</b>		<b>52,224</b>		