PROJECT NO.	SHEET NO.	TOTAL NO.
2016CPT.10.57.10131.1, ETC.	16	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	BORROW CY	SOIL CEMENT BASE (FDR) SY	PORTLAND CEMENT FOR SOIL CEMENT BASE TON	INCIDENTAL STONE BASE TONS	SHOULDER RECONSTRUCTION SMI	2" MILLING SY	1½" MILLING SY	0" TO 2.0" MILLING SY	0" TO 1.5" MILLING SY	INCIDENTAL MILLING SY	SURFACE COURSE, S9.5B TONS	LEVELING COURSE, S9.5B TONS	SURFACE COURSE, S9.5C TONS	LEVELING COURSE, S9.5C TONS	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A (LEVELING COURSE) TON	ASPHALT BINDER FOR PLANT MIX TON	PATCHING EXISTING PAVEMENT TONS	ASPHALT SURFACE TREATMENT, MATCOAT, #78M STONE SY	ASPHALT SURFACE TREATMENT, MATCOAT, #67 STONE SY	ASPHALT SURFACE TREATMENT, DOUBLE SEAL SY	EMULSION FOR ASPHALT SURFACE TREATMENT GAL	6" DRIVEWAYS SY	RETROFIT EXISTING CURB RAMPS EA	ADJ. OF MANHOLES EA	ADJ. OF METER OR VALVE BOX EA	TEMPORARY SILT FENCE LF	WATTLE LF
2016CPT.10.57.10131.1	Cabarrus	1	US 601	FROM SR 1002 (CABARRUS AVE) TO SR 1335 (OLD CHARLOTTE RD) MP 16.36 TO MP 17.40	1,2,3	2		NO	NO	1.04	26'-41'	250				2.08	4,000		230		600			2,638	200			169	300		22,422		7,850						
TOTAL FOR MAP NO. 1										**1.04**		**250**				**2.08**	**4,000**		**230**		**600**			**2,638**	**200**			**169**	**300**		**22,422**		**7,850**						
TOTAL FOR PROJ NO. 2016CPT.10.57.10131.1										**1.04**		**250**				**2.08**	**4,000**		**230**		**600**			**2,638**	**200**			**169**	**300**		**22,422**		**7,850**						
2016CPT.10.57.10131.2	Cabarrus	2	NC 49	FROM SR 2444 (ST STEPHENS CH RD) TO SR 2450 (GOLD HILL RD) MP 18.73 TO MP 22.43	3	2		NO	NO	3.6	24'	828				7.20					500			6,398	500			410	800		52,596		18,410					200	300
TOTAL FOR MAP NO. 2										**3.6**		**828**				**7.20**					**500**			**6,398**	**500**			**410**	**800**		**52,596**		**18,410**					**200**	**300**
TOTAL FOR PROJ NO. 2016CPT.10.57.10131.2										**3.6**		**828**				**7.20**					**500**			**6,398**	**500**			**410**	**800**		**52,596**		**18,410**					**200**	**300**
2016CPT.10.57.10131.3	Cabarrus	3	NC 73	FROM SR 1507 (LAFOREST LN TO SR 1442 (ODELL SCHOOL RD) MP 3.54 TO MP 2.13	4,5,6	2		NO	NO	1.36	28'-33'	315				2.72		10,800		230	450			2,362	200			152	300									200	320
TOTAL FOR MAP NO. 3										**1.36**		**315**				**2.72**		**10,800**		**230**	**450**			**2,362**	**200**			**152**	**300**									**200**	**320**
TOTAL FOR PROJ NO. 2016CPT.10.57.10131.3										**1.36**		**315**				**2.72**		**10,800**		**230**	**450**			**2,362**	**200**			**152**	**300**									**200**	**320**
2016CPT.10.57.20131.1	Cabarrus	4	SR 1613 (EARNHARDT LAKE RD)	FROM NC 3 TO NC 3 MP 0.00 TO MP 2.12	9	2		NO	NO	2.12	20'	212			75	4.24					450					1,665	100	118	100										
TOTAL FOR MAP NO. 4										**2.12**		**212**			**75**	**4.24**					**450**					**1,665**	**100**	**118**	**100**										
TOTAL FOR PROJ NO. 2016CPT.10.57.20131.1										**2.12**		**212**			**75**	**4.24**					**450**					**1,665**	**100**	**118**	**100**										
2016CPT.10.57.20131.2	Cabarrus	5	SR 1309 (STOUGH RD)	FROM NC 49 TO PAVEMENT JOINT BEFORE SR 1304 (ROBERTA RD) MP 0.00 TO MP 1.84	10	2		NO	NO	1.56	22'-28'	300			117	3.12					1,000	2,146	200					142	300									200	320
TOTAL FOR MAP NO. 5										**1.56**		**300**			**117**	**3.12**					**1,000**	**2,146**	**200**					**142**	**300**									**200**	**320**
TOTAL FOR PROJ NO. 2016CPT.10.57.20131.2										**1.56**		**300**			**117**	**3.12**					**1,000**	**2,146**	**200**					**142**	**300**									**200**	**320**
2016CPT.10.57.20131.4	Cabarrus	6	SR 1307 (BLACKWELDER RD)	FROM SR 1304 (ROBERTA RD) NC 49 PAVEMENT JOINT MP 0.00 TO MP 0.95	9	2		NO	NO	0.95	20'	110			25	1.90					300					856	100	63	150										160
TOTAL FOR MAP NO. 6										**0.95**		**110**			**25**	**1.90**					**300**					**856**	**100**	**63**	**150**										**160**
TOTAL FOR PROJ NO. 2016CPT.10.57.20131.4										**0.95**		**110**			**25**	**1.90**					**300**					**856**	**100**	**63**	**150**										**160**
2016CPT.10.57.20131.5	Cabarrus	7	SR 1100 (BARRIER GEORGEVILLE RD)	FROM SR 2622 (BARRIER STORE RD) TO PAST SR 1132 (MIAMI CH RD) MP 0.00 TO MP 1.65	8	2		NO	NO	1.65	21'-22'	180			83	3.30					600					1,317	200	100										400	560
TOTAL FOR MAP NO. 7										**1.65**		**180**			**83**	**3.30**					**600**					**1,317**	**200**	**100**										**400**	**560**
TOTAL FOR PROJ NO. 2016CPT.10.57.20131.5										**1.65**		**180**			**83**	**3.30**					**600**					**1,317**	**200**	**100**										**400**	**560**
2016CPT.10.57.20131.6	Cabarrus	8	SR 1199 (OAK HOLLOW LN EXT)	FROM SR 1168 (ROBINSON CH RD) TO END OF MAINTENANCE MP 0.00 TO MP 0.43	7	2		NO	NO	0.39	20'							4,676								426		29										200	80
TOTAL FOR MAP NO. 8										**0.39**								**4,676**								**426**		**29**										**200**	**80**
TOTAL FOR PROJ NO. 2016CPT.10.57.20131.6										**0.39**								**4,676**								**426**		**29**										**200**	**80**
2016CPT.10.57.20131.7	Cabarrus	9	SR 1203 (ROCKWOOD RD)	FROM SR 1200 (LAREWOOD DR) TO DEAD END MP 0.00 TO MP 0.51	7	2		NO	NO	0.51	22'							6,582								601		40	50					50					
TOTAL FOR MAP NO. 9										**0.51**								**6,582**								**601**		**40**	**50**					**50**					
2016CPT.10.57.20131.7	Cabarrus	10	SR 1210 (RIVER FALLS DR)	FROM SR 1204 (ARBOR DALE AVE) TO SR 1203 (ROCKWOOD RD) MP 0.11 TO MP 0.40	7	2		NO	NO	0.25	20'							3,226								294		20											
TOTAL FOR MAP NO. 10										**0.25**								**3,226**								**294**		**20**											
2016CPT.10.57.20131.7	Cabarrus	11	SR 2330 (GREENWOOD CT)	FROM SR 1210 (RIVER FALLS DR) TO DEAD END MP 0.00 TO MP 0.18	7	2		NO	NO	0.18	20'							2,500								227		15	20							2			
TOTAL FOR MAP NO. 11										**0.18**								**2,500**								**227**		**15**	**20**							**2**			
2016CPT.10.57.20131.7	Cabarrus	12	SR 2340 (MIDVALE TERRACE)	FROM SR 1204 (ARBOR DALE AVE) TO DEAD END MP 0.00 TO MP 0.08	7	2		NO	NO	0.08	20'-30'				20			1,400								129		9											
TOTAL FOR MAP NO. 12										**0.08**					**20**			**1,400**								**129**		**9**											
2016CPT.10.57.20131.7	Cabarrus	13	SR 3031 (COLD SPRINGS RD)	FROM SR 1176 (PLAZA RD EXT) TO SR 1204 (ARBOR DALE AVE) MP 0.00 TO MP 0.29	7	2		NO	NO	0.29	20'-30'				20			3,703								315		21						100		4	2		
TOTAL FOR MAP NO. 13										**0.29**					**20**			**3,703**								**315**		**21**						**100**		**4**	**2**		
2016CPT.10.57.20131.7	Cabarrus	14	SR 3032 (HOLLY TREE DR)	FROM SR 1210 (RIVER FALLS DR) TO SR 3033 (WHITTINGTON DR) MP 0.00 TO MP 0.19	7	2		NO	NO	0.18	20'				20			2,200								201		13						20		2			
TOTAL FOR MAP NO. 14										**0.18**					**20**			**2,200**								**201**		**13**						**20**		**2**			
TOTAL FOR PROJ NO. 2016CPT.10.57.20131.7										**1.49**					**60**			**19,611**								**1,767**		**118**	**70**					**170**		**8**	**2**		
2016CPT.10.57.20131.8	Cabarrus	15	SR 1241 (WINTERCREST DR)	FROM SR 1153 (ZION CH RD) TO SR 1250 (FLINTRIDGE DR) MP 0.00 TO MP 0.48	7	2		NO	NO	0.48	20'				50			6,300								571		38	120					30					160
TOTAL FOR MAP NO. 15										**0.48**					**50**			**6,300**								**571**		**38**	**120**					**30**					**160**
2016CPT.10.57.20131.8	Cabarrus	16	SR 1250 (FLINTRIDGE DR)	FROM SR 1241 (WINTERCREST DR) TO END OF MAINTENANCE MP 0.00 TO MP 0.41	7	2		NO	NO	0.42	20'				40			5,500								465		31											
TOTAL FOR MAP NO. 16										**0.42**					**40**			**5,500**								**465**		**31**											
TOTAL FOR PROJ NO. 2016CPT.10.57.20131.8										**0.9**					**90**			**11,800**								**1,036**		**69**	**120**					**30**					**160**
2016CPT.10.57.20131.9	Cabarrus	17	SR 1244 (SEARCH DR)	FROM SR 1152 (ZION CH ROAD) TO END OF MAINTENANCE MP 0.00 TO MP 0.32	7	2		NO	NO	0.32	20'	32				0.64		4,206								382		26	200										
TOTAL FOR MAP NO. 17										**0.32**		**32**				**0.64**		**4,206**								**382**		**26**	**200**										
2016CPT.10.57.20131.9	Cabarrus	18	SR 1245 (MOUNTAINER LN)	FROM SR 1244 (SEARCH DR) TO END OF MAINTENANCE MP 0.00 TO MP 0.44	7	2		NO	NO	0.44	20'	30				0.22		5,300								480		32	200										240
TOTAL FOR MAP NO. 18										**0.44**		**30**				**0.22**		**5,300**								**480**		**32**	**200**										**240**
TOTAL FOR PROJ NO. 2016CPT.10.57.20131.9										**0.76**		**62**				**0.86**		**9,506**								**862**		**58**	**400**										**240**
2016CPT.10.57.20131.10	Cabarrus	19	SR 1254 (CENTRAL HEIGHTS DR)	FROM SR 1153 (ZION CH RD) TO SR 1255 (LARCHLEA PL) MP 0.00 TO MP 0.38	7	2		NO	NO	0.38	20'				40			4,500								407		27	80										240
TOTAL FOR MAP NO. 19										**0.38**					**40**			**4,500**								**407**		**27**	**80**										**240**
2016CPT.10.57.20131.10	Cabarrus	20	SR 1255 (LARCHLEA DR)	FROM SR 1254 (CENTRAL HEIGHTS DR) TO SR 1254 (CENTRAL HEIGHTS DR) MP 0.00 TO MP 0.29	7	2		NO	NO	0.3	20'							3,600								327		22	60										160
TOTAL FOR MAP NO. 20										**0.3**								**3,600**								**327**		**22**	**60**										**160**
TOTAL FOR PROJ NO. 2016CPT.10.57.20131.10										**0.68**					**40**			**8,100**								**734**		**49**	**140**										**400**
2016CPT.10.57.20131.11	Cabarrus	21	SR 1269 (FALCON DR)	SR 1152 (ZION CH RD) TO PAVEMENT JOINT @ CULVERT MP 0.00 TO MP 0.39	7	2		NO	NO	0.34	20'							4,100								373		25											
TOTAL FOR MAP NO. 21										**0.34**								**4,100**								**373**		**25**											
TOTAL FOR PROJ NO. 2016CPT.10.57.20131.11										**0.34**								**4,100**								**373**		**25**											
2016CPT.10.57.20131.12	Cabarrus	22	SR 1300 (MOREHEAD RD)	FROM US 29 TO MECKLENBURG CO LINE MP 3.23 TO MP 0.53	11, 12	2		NO	NO	0.5	22'-48'	115				1.00			200		1,368	1,316	100					85	250		5,852		2,050		5				160
TOTAL FOR MAP NO. 22										**0.5**		**115**				**1.00**			**200**		**1,368**	**1,316**	**100**					**85**	**250**		**5,852**		**2,050**		**5**				**160**
TOTAL FOR PROJ NO. 2016CPT.10.57.20131.12										**0.5**		**115**				**1.00**			**200**		**1,368**	**1,316**	**100**					**85**	**250**		**5,852**		**2,050**		**5**				**160**