

PROJECT NO.	SHEET NO.
I-5731	3B-2

### SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	ASB TON	SHOULDER RECONSTRUCTION SMI	2" MILLING SY	0" TO 2" MILLING SY	INCIDENTAL MILLING SY	BASE COURSE, B25.0B TONS	SURFACE COURSE, S9.5D TONS	ASPHALT BINDER FOR PLANT MIX TONS	POLYMER MODIFIED ASPHALT BINDER FOR PLANT MIX TON	PATCHING EXISTING PAVEMENT TONS	MILLED RUMBLE STRIPS (ASPHALT CONCRETE) LF	REMOVE & REPLACE MASONRY DRAINAGE STRUCTURES EA	MASONRY DRAINAGE STRUCTURE LF	FRAME WITH TWO GRATES, STD 840.22 EA	RETROFIT EXISTING CURB RAMP EA	GUARDRAIL ANCHOR UNITS, TYPE 350 EA	REMOVE EXISTING GUARDRAIL LF	WOVEN WIRE FENCE, 47" FABRIC LF	4" TIMBER FENCE POSTS, 7'-6" LONG EA	5" TIMBER FENCE POSTS, 8'-0" LONG EA	ADDITIONAL BARBED WIRE LF	PORTABLE LIGHTING LS	
I-5731	Cumberland	1	I-95	FROM: MM 40 TO: MM 53		1, 2, 3, 4	4	MD	NO	NO	13	78	7,700	59.00	814,217	1,956	1,000	261	92,606	12	5,280	4,600	274,560	19	36.19	19	16	11	550	137,280	9,810	3,300	750	1
<b>TOTAL FOR MAP NO. 1</b>										13		7,700	59.00	814,217	1,956	1,000	261	92,606	12	5,280	4,600	274,560	19	36.19	19	16	11	550	137,280	9,810	3,300	750	1	
<b>TOTAL FOR PROJ NO. I-5731</b>										13		7,700	59.00	814,217	1,956	1,000	261	92,606	12	5,280	4,600	274,560	19	36.19	19	16	11	550	137,280	9,810	3,300	750	1	
<b>GRAND TOTAL</b>										13		7,700	59.00	814,217	1,956	1,000	261	92,606	12	5,280	4,600	274,560	19	36.19	19	16	11	550	137,280	9,810	3,300	750	1	