

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

SUMMARY OF AGGREGATE SUBGRADE/STABILIZATION

LINE	STATION	STATION	AGGREGATE TYPE ASU/AST	AGGREGATE THICKNESS INCHES	SHALLOW UNDERCUT CY	CLASS IV SUBGRADE STABILIZATION TONS	GEOTEXTILE FOR SOILD STABILIZATION SY	STABILIZER AGGREGATE TONS	CLASS IV AGGREGATE STABILIZATION TONS
-L- (LT)	21 + 25	22 + 00	AST	3"				19	
-L- (LT)	23 + 65	28 + 52	AST	3"				171	
-L- (RT)	10 + 60	28 + 70	AST	3"				231	
-Y1-	10 + 25	18 + 90	AST	3"				533	
-Y1-	20 + 65	25 + 15	AST	3"				706	
-Y2-	10 + 28	11 + 50	AST	3"				85	
-Y2-	13 + 35	15 + 75	AST	3"				199	
-Y3A-	17 + 30	18 + 72	AST	3"				405	
-Y4-	11 + 56	15 + 90	AST	3"				42	
ROUND			AST	3"				105	
	CONTINGENCY							500	
	TOTAL				0	0	0	2,996	0
	SAY							3,000	