

Print Full Size

Print Half Size

STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS

PROJ. REFERENCE NO. W-5510 SHEET NO. X-1A

Kimley»Horn P.O. Box 33068 Raleigh, N.C. 27636-3068

CROSS-SECTION SUMMARY

STATION	UNCLASSIFIED EXCAVATION VOLUMES (CU. YARDS)	EMBANKMENT VOLUMES (CU. YARDS)			STATION	UNCLASSIFIED EXCAVATION VOLUMES (CU. YARDS)	EMBANKMENT VOLUMES (CU. YARDS)			STATION	UNCLASSIFIED EXCAVATION VOLUMES (CU. YARDS)	EMBANKMENT VOLUMES (CU. YARDS)			STATION	UNCLASSIFIED EXCAVATION VOLUMES (CU. YARDS)	EMBANKMENT VOLUMES (CU. YARDS)
-L-					-Y1-					-Y2-					-Y4-		
12+25					10+92					10+29					10+51		
13+00	0.0	15.1			11+00	0.9	9.0			10+50	35.7	0.0			11+00	3.5	0.8
13+50	0.6	16.0			11+50	7.6	40.2			10+62	32.6	0.3			11+50	3.9	0.5
14+00	0.5	9.6			12+00	7.5	40.6			11+00	42.2	61.9			12+00	70.7	0.6
14+50	16.8	4.9			12+50	8.9	134.3			11+50	4.7	318.9			12+50	163.9	0.3
15+00	26.6	1.4			13+00	9.2	208.8			11+74	2.1	224.4			13+00	182.0	0.0
15+50	23.4	0.1			13+50	7.1	165.8								13+50	155.6	0.0
16+00	30.4	0.0			13+84	6.5	70.2			break for roundabout					14+00	131.6	0.0
16+50	18.9	1.4			14+00	3.0	23.7								14+50	78.8	0.1
17+00	3.0	7.9			14+50	11.8	72.2			13+13					15+00	45.4	0.1
17+50	1.5	9.8			14+85	25.1	50.0			13+50	0.0	222.3			15+50	46.1	0.0
18+00	0.8	16.6			15+00	12.7	21.6			14+00	25.1	223.4			15+90	13.2	0.0
18+50	0.2	16.7			15+50	18.6	73.6			14+20	21.8	73.7					
19+00	0.6	4.9			15+85	7.0	89.7			14+50	22.8	116.4					
20+00	32.9	24.1			16+00	2.9	45.2			15+00	20.8	139.3					
20+50	36.2	16.5			16+50	11.1	107.8			15+50	20.6	75.0			-Y5-		
21+00	37.2	20.1			17+00	11.3	137.9			16+00	11.3	21.8			10+45		
21+50	40.3	24.4			17+31	4.9	104.5			16+46	2.6	1.1			10+50	32.1	0.0
22+00	58.4	19.7			17+50	3.0	72.2								10+93	203.7	0.0
22+50	35.1	9.5			17+72	3.4	93.2			-Y3-							
23+00	17.1	8.9			17+89	1.3	68.5			17+30							
23+50	69.7	10.7			18+00	0.1	45.7			17+50	3.8	0.0					
24+00	112.8	1.8			18+50	0.0	338.0			18+00	20.9	2.9					
24+50	115.3	0.1			19+00	0.0	516.3			18+10	5.2	1.2					
24+72	59.4	0.0			19+17	0.0	193.2										
25+00	86.3	0.2															
25+50	149.0	1.3			break for roundabout					-Y3A-							
26+00	140.6	4.5								18+00							
26+50	112.9	11.8			20+42					18+25	8.3	1.0			-Roundabout-		
27+00	84.2	8.2			20+50	2.0	72.8			18+50	27.6	1.3					1523.9
27+50	59.6	0.0			21+00	91.5	243.8			18+85	27.1	0.5					
27+75	23.6	0.0			21+50	249.9	8.4										
28+00	19.0	0.0			22+00	410.8	0.3										
28+50	21.6	0.0			22+50	447.7	0.0										
28+70	3.3	0.0			23+00	420.3	0.0										
					23+50	354.7	3.2										
					24+00	229.8	13.8										
					24+50	228.8	15.1										
					25+00	236.4	11.4										
					25+15	29.9	2.0										
					25+50	0.0	0.0										
					25+84	0.0	0.0										
					26+00	9.0	3.3										
					26+50	49.9	33.6										
					26+55	2.1	2.3										

Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.

Note: Embankment column does not include backfill for undercut.