PROJECT NO.	SHEET NO.	TOTAL NO.
2016CPT.05.09.10351.1,	13	
2016CPT.05.09.20351.1		

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	BORROW CY	INCIDENTAL STONE BASE TONS	SHOULDER RECONSTRUCTION SMI	1½" MILLING SY	0" TO 1.5" MILLING SY	0" TO 4" MILLING SY	INCIDENTAL MILLING SY	SURFACE COURSE, S9.5B TONS	ASPHALT BINDER FOR PLANT MIX TON	PATCHING EXISTING PAVEMENT TONS	CONCRETE CURB RAMP (Std. 848.05) EA	ADJUST DROP INLET EA	ADJUST MANHOLES EA	ADJUST METER OR VALVE BOX EA	TEMPORARY SILT FENCE LF	WATTLE LF	SEED & MULCHING AC	INDUCTIVE LOOP LF
2016CPT.05.09.10351.1	Franklin	1	NC 39	JT WEST OF SR 1731 - CHEVES RD TO US 401	1	2	NO	YES	10.22	25-44	1,989	497	19.89		2,262		1,160	14,212	853	250		1	12	7	1,447	3,620	14.47	
TOTAL FOR MAP NO. 1									**10.22**		**1,989**	**497**	**19.89**		**2,262**		**1,160**	**14,212**	**853**	**250**		**1**	**12**	**7**	**1,447**	**3,620**	**14.47**	
2016CPT.05.09.10351.1	Franklin	2	NC 56	JT WEST OF US 1 TO SR 1222 - WILL MITCHINER RD	1,2	2	NO	YES	4.46	26-50	741	185	7.41		1,800	16,413	3,195	7,072	424	20	1		10	18	539	1,350	5.39	1,850
TOTAL FOR MAP NO. 2									**4.46**		**741**	**185**	**7.41**		**1,800**	**16,413**	**3,195**	**7,072**	**424**	**20**	**1**		**10**	**18**	**539**	**1,350**	**5.39**	**1,850**
TOTAL FOR PROJ NO. 2016CPT.05.09.10351.1									**14.68**		**2,730**	**682**	**27.30**		**4,062**	**16,413**	**4,355**	**21,284**	**1,277**	**270**	**1**	**1**	**22**	**25**	**1,986**	**4,970**	**19.86**	**1,850**
2016CPT.05.09.20351.1	Franklin	3	SR 1002 - SEVEN PATHS RD	NC 581 TO NASH CO	1	2	NO	NO	7.765	19-20	1,553	388	15.53	640			420	7,589	455	300					1,126	2,820	11.26	
TOTAL FOR MAP NO. 3									**7.765**		**1,553**	**388**	**15.53**	**640**			**420**	**7,589**	**455**	**300**					**1,126**	**2,820**	**11.26**	
2016CPT.05.09.20351.1	Franklin	4	SR 1127 - POCOMOKE RD	NC 56 TO SR 1141 - GORDON MOORE RD	1	2	NO	YES	4.88	20-21	972	244	9.72		90		566	5,206	312			2			707	1,770	7.07	220
TOTAL FOR MAP NO. 4									**4.88**		**972**	**244**	**9.72**		**90**		**566**	**5,206**	**312**			**2**			**707**	**1,770**	**7.07**	**220**
2016CPT.05.09.20351.1	Franklin	5	SR 1141 - POCOMOKE RD	SR 1127 - POCOMOKE RD TO GRANVILLE CO	1	2	NO	YES	0.531	20-21	106	27	1.06				325	577	35	10					77	200	0.77	
TOTAL FOR MAP NO. 5									**0.531**		**106**	**27**	**1.06**				**325**	**577**	**35**	**10**					**77**	**200**	**0.77**	
2016CPT.05.09.20351.1	Franklin	6	SR 1235 - DYKING RD	SR 1003 - SIMS BRIDGE RD TO NC 39	1	2	NO	NO	5.326	20-32	1,080	266	10.65	2,500			746	5,929	356	300					783	1,960	7.72	
TOTAL FOR MAP NO. 6									**5.326**		**1,080**	**266**	**10.65**	**2,500**			**746**	**5,929**	**356**	**300**					**783**	**1,960**	**7.72**	
2016CPT.05.09.20351.1	Franklin	7	SR 1418 - T K ALLEN RD	SR 1002 - DUKE VALENTINE WYNNE RD TO NC 561	1	2	NO	NO	3	19	600	150	6.00				156	2,969	178	5					435	1,090	4.35	
TOTAL FOR MAP NO. 7									**3**		**600**	**150**	**6.00**				**156**	**2,969**	**178**	**5**					**435**	**1,090**	**4.35**	
2016CPT.05.09.20351.1	Franklin	8	SR 1436 - LAUREL MILL CENTERVILLE RD	NC 561 TO NC 561	1	2	NO	NO	7.42	19-20	1,484	371	14.84				330	7,533	452	10					1,076	2,690	10.76	
TOTAL FOR MAP NO. 8									**7.42**		**1,484**	**371**	**14.84**				**330**	**7,533**	**452**	**10**					**1,076**	**2,690**	**10.76**	
2016CPT.05.09.20351.1	Franklin	9	SR 1438 - RAYMOND THARRINGTON RD	SR 1436 - LAUREL MILL RD TO NC 561	1	2	NO	NO	2.1	19	420	105	4.20				156	2,078	125	350					304	760	3.05	
TOTAL FOR MAP NO. 9									**2.1**		**420**	**105**	**4.20**				**156**	**2,078**	**125**	**350**					**304**	**760**	**3.05**	
2016CPT.05.09.20351.1	Franklin	10	SR 1457 - DOUGLAS WILLIAMS RD	SR 1456 - BALDY MURPHY RD TO SR 1451 - LEONARD RD	3	2	NO	NO	1.948	20-21	488	97	3.90				913	2,912	175						195	490	2.82	
TOTAL FOR MAP NO. 10									**1.948**		**488**	**97**	**3.90**				**913**	**2,912**	**175**						**195**	**490**	**2.82**	
2016CPT.05.09.20351.1	Franklin	11	SR 1602 - LEONARD FARM RD	SR 1601 - GEORGE LEONARD RD TO NC 56	1	2	NO	NO	1.43	18	286	72	2.86				164	1,341	80	400					207	520	2.07	
TOTAL FOR MAP NO. 11									**1.43**		**286**	**72**	**2.86**				**164**	**1,341**	**80**	**400**					**207**	**520**	**2.07**	
2016CPT.05.09.20351.1	Franklin	12	SR 1611 - SLEDGE RD	SR 1609 - BAPTIST CHURCH RD TO SR 1636 - SYKES RD	1	2	NO	NO	2.33	19-20	466	117	4.66				183	2,365	142	300					338	850	3.38	
TOTAL FOR MAP NO. 12									**2.33**		**466**	**117**	**4.66**				**183**	**2,365**	**142**	**300**					**338**	**850**	**3.38**	
2016CPT.05.09.20351.1	Franklin	13	SR 1203 - GREEN HILL RD	VANCE COUNTY TO NC 56	3	2	NO	NO	5.025	19-20	1,257	503	10.05				867	6,697	402	100					729	1,830	7.29	
TOTAL FOR MAP NO. 13									**5.025**		**1,257**	**503**	**10.05**				**867**	**6,697**	**402**	**100**					**729**	**1,830**	**7.29**	
TOTAL FOR PROJ NO. 2016CPT.05.09.20351.1									**41.755**		**8,712**	**2,340**	**83.47**	**3,140**	**90**		**4,826**	**45,196**	**2,712**	**1,775**		**2**			**5,977**	**14,980**	**60.54**	**220**
GRAND TOTAL									**56.435**		**11,442**	**3,022**	**110.77**	**3,140**	**4,152**	**16,413**	**9,181**	**66,480**	**3,989**	**2,045**	**1**	**3**	**22**	**25**	**7,963**	**19,950**	**80.40**	**2,070**