

**NOTES**

FOR BRIDGE APPROACH FILL INCLUDING GEOTEXTILE, 4" Ø DRAINAGE PIPE, AND #78M STONE BACKFILL, SEE ROADWAY PLANS.

GEOTEXTILE SHALL BE TYPE 1 IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS SECTION 1056.


#78M STONE BACKFILL (CLASS V SELECT MATERIAL) SHALL BE IN ACCORDANCE WITH STANDARD SPECIFICATIONS SECTION 1016.

#78M STONE BACKFILL IS TO BE CONTINUOUS ALONG FILL FACE OF BACKWALL FROM OUTSIDE EDGE TO OUTSIDE EDGE OF APPROACH SLAB.

FOR THE 4" Ø DRAINAGE PIPE OUTLET(S), SEE ROADWAY STANDARD DRAWINGS.


AREA BETWEEN THE WINGWALL AND APPROACH SLAB SHALL BE GRADED TO DRAIN THE WATER AWAY FROM THE FILL FACE OF THE BRIDGE AND SHALL BE PAVED. SEE ROADWAY PLANS.

APPROACH SLAB GROOVING IS NOT REQUIRED.



NOTE: IF THE APPROACH SLAB IS NOT CONSTRUCTED IMMEDIATELY AFTER THE BACKFILLING OF THE END BENT EXCAVATION, GRADE TO DRAIN TO THE BOTTOM OF THE SLOPE AND PROVIDE EROSION RESISTANT MATERIAL, SUCH AS FIBERGLASS ROVING OR AS DIRECTED BY THE ENGINEER TO PREVENT SOIL EROSION AND TO PROTECT THE AREA ADJACENT TO THE STRUCTURE. THE CONTRACTOR WILL BE REQUIRED TO REMOVE THESE MATERIALS PRIOR TO CONSTRUCTION OF THE APPROACH SLAB.


**TEMPORARY DRAINAGE DETAIL**



**PLAN VIEW**

**TEMPORARY BERM AND SLOPE DRAIN DETAILS**


(TO BE USED WHEN SHOULDER BERM GUTTER IS REQUIRED)




**PLAN @ END BENT 1**

**PLAN @ END BENT 2**

DIMENSIONS SHOWN ARE TYPICAL FOR BOTH APPROACH SLABS



**SECTION THRU SLAB**



**CURB DETAILS**

SPLICE LENGTHS		
BAR SIZE	EPOXY COATED	UNCOATED
#4	2'-0"	1'-9"
#5	2'-6"	2'-2"
#6	3'-10"	2'-7"

**BILL OF MATERIAL**

**APPROACH SLAB AT EB 1**

BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT
*A1	26	#4	STR	17'-8"	307
A2	26	#4	STR	17'-7"	305
*B1	58	#5	STR	11'-1"	670
B2	58	#6	STR	11'-7"	1009

REINFORCING STEEL	LBS.	1314
*EPOXY COATED REINFORCING STEEL	LBS.	977

CLASS AA CONCRETE	C. Y.	18.0
-------------------	-------	------

**APPROACH SLAB AT EB 2**

BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT
*A1	26	#4	STR	17'-8"	307
A2	26	#4	STR	17'-7"	305
*B1	58	#5	STR	11'-1"	670
B2	58	#6	STR	11'-7"	1009

REINFORCING STEEL	LBS.	1314
*EPOXY COATED REINFORCING STEEL	LBS.	977

CLASS AA CONCRETE	C. Y.	18.0
-------------------	-------	------

ASSEMBLED BY : A. SORSENGINH DATE : 11/2015  
 CHECKED BY : J.P. ADAMS DATE : 11/2015  
 DRAWN BY : SHS/MAA 5-09  
 CHECKED BY : BCH 5-09

REV. 9-15 MAA/TMG

22-MAR-2016 08:09  
 R:\Structures\Plans\Misc\B5171.SD.AS.dgn  
 jpodams



DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

PROJECT NO. B-5171  
 GRANVILLE COUNTY  
 STATION: 15+12.00 -L-

STATE OF NORTH CAROLINA  
 DEPARTMENT OF TRANSPORTATION  
 RALEIGH  
 STANDARD  
 BRIDGE APPROACH SLAB  
 FOR PRESTRESSED CONCRETE  
 CORED SLAB UNIT  
 (SUB-REGIONAL TIER)  
 60° SKEW

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	S-18
1			3			TOTAL SHEETS 18
2			4			