

PROJECT REFERENCE NO.		SHEET NO.
I-5756		6
STATE PROJECT	F.A. PROJECT NO	DESCRIPTION
52034.3.1	NHPP-0040(018)23	I-5756

SURFACING SCHEDULE

ITEM NO	DESCRIPTION
C1	ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 168 LBS. PER SQ. YD. (1 1/2")
C2	ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5D, AT AN AVERAGE RATE OF 168 LBS. PER SQ. YD. (1 1/2")
D1	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE I19.0D, AT AN AVERAGE RATE OF 342 LBS. PER SQ. YD. (3")
F1	OPEN GRADED ASPHALT FRICTION COURSE, TYPE FC-2 MOD, AT AN AVERAGE RATE OF 90 LBS. PER SQ. YD.
R	MILLED RUMBLE STRIPS
V1	MILLING ASPHALT PAVEMENT 1 1/2 " IN DEPTH AS DIRECTED BY PROJECT ENGINEER.
V2	MILLING ASPHALT PAVEMENT 3" IN DEPTH AS DIRECTED BY PROJECT ENGINEER.
U	EXISTING PAVEMENT