## STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

# SIGNING PLAN SCOTLAND AND HOKE COUNTIES

LOCATION: BRIDGE NO. 8 OVER DROWNING CREEK ON SR 1412/SR 1203 (TURNPIKE ROAD)

PROJECT REFERENCE NO. SIGN-1 B-4967 Pocusigned by:
Ronald W king
13E7AF7B9AA4448... DATE: 3/4/2016 | 6:53 AM PT

**UNLESS ALL SIGNATURES COMPLETED** 

### ROADWAY STANDARD DRAWING

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" -PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2012 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD.	NO.	TITLE

901.50

ARROWS AND SHIELDS

904.10 904.50

ORIENTATION OF GROUND MOUNTED SIGNS MOUNTING OF TYPE 'D', 'E' AND 'F' SIGNS ON 'U' CHANNEL POSTS

#### GENERAL NOTES

- . SIGNS FURNISHED BY STATE
- . ALL TYPE 'D' SIGNS SHALL BE MOUNTED ON TWO U-CHANNEL POSTS UNLESS OTHERWISE INDICATED ON THE PLANS.
- . WHEN NOT STATIONED OR DIMENSIONED ON PLANS, ALL 'E' AND 'F' SIGNS SHALL BE FIELD LOCATED BY THE ENGINEER
- . ALL EXISTING SIGNS ON "U" CHANNEL POST WITHIN THE PROJECT LIMITS SHALL BE REMOVED AND DISPOSED OF UNLESS OTHERWISE NOTED ON PLANS.
- . THE BACKGROUND FOR TYPE E & F SIGNS SHALL BE TYPE C REFLECTIVE SHEETING.
- . SEE ROADWAY PLANS FOR GUARD/GUIDE RAIL DETAILS.

## SUMMARY OF QUANTITIES

ITEM NO.		TTEM DECODEDETON	OHANTITY	LINITT
DESC. NO.	SECT. NO.	ITEM DESCRIPTION	QUANTITY	UNIT
4072000000	903	SUPPORTS, 3 LB STEEL U-CHANNEL	199	L.F.
4096000000	904	SIGN ERECTION, TYPE D	4	EA.
4102000000	904	SIGN ERECTION, TYPE E	2	EA.
4108000000	904	SIGN ERECTION, TYPE F	1	EA.
4155000000	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	11	EA.


## PROJECT NOTES

DISPOSAL OF SIGN SYSTEM, U-CHANNEL

PLAN PREPARED BY: N.C.D.O.T. SIGNING AND DELINEATION UNIT

R. B. ROACH, PE SIGNING & DELINEATION REGIONAL ENGINEER

A. N. KIDD SIGNING & DELINEATION PROJECT DESIGN ENGINEER



## **INDEX**

**DESCRIPTION** SHEET NO. SIGN-1 TITLE SHEET D, E, F SHEETS SIGN-2 SIGN-3 SIGN DETAIL SHEET