STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

SIGNING PLAN IREDELL COUNTY

LOCATION: BRIDGE No. 69 OVER ROCKY CREEK ON NC 115

PROJECT REFERENCE NO.	SHEET NO.
B-4766	SIGN-1
APPROVED: Ronald W. King 0695D7A9577C4DC	
DATE:	
SEAL	
SEAL 022959 WE INEED TO WE KINGHING	

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

SUMMARY OF QUANTITIES

ITEM NO.		ITEM DESCRIPTION	OHANTITY	UNIT
DESC. NO.	SECT. NO.	TILW DESCRIFTION	QUANTITY	UNII
4025000000	901	CONTRACTOR FURNISHED, TYPE D SIGN	12	S.F.
4072000000	903	SUPPORTS, 3 LB STEEL U-CHANNEL	50	L.F.
4096000000	904	SIGN ERECTION, TYPE D	2	EA.
4155000000	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	2	EA.

ROADWAY STANDARD DRAWING

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" -PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2012 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

ORIENTATION OF GROUND MOUNTED SIGNS 904.10

MOUNTING OF TYPE 'D', 'E' AND 'F' SIGNS ON 'U' CHANNEL POSTS 904.50

GENERAL NOTES

- . SIGNS FURNISHED BY CONTRACTOR
- . ALL TYPE 'D' SIGNS SHALL BE MOUNTED ON TWO U-CHANNEL POSTS UNLESS OTHERWISE INDICATED ON THE PLANS.
- . IF REMOVAL OR RELOCATION OF SIGNS ON PRIVATE STREET (NON-STATE MAINTAINED) IS REQUIRED DUE TO CONSTRUCTION, THE CONTRACTOR SHALL INFORM THE ENGINEER. THE WORK WILL BE COMPLETED BY OTHERS.
- . ALL EXISTING SIGNS ON "U" CHANNEL POST WITHIN THE PROJECT LIMITS SHALL BE REMOVED AND DISPOSED OF UNLESS OTHERWISE NOTED ON PLANS.
- . SEE ROADWAY PLANS FOR GUARD/GUIDE RAIL DETAILS.

INDEX

SHEET NO.

<u>DESCRIPTION</u>

SIGN-1 SIGN-2 TITLE SHEET SIGN DESIGN AND

EXISTING & PROPOSED SIGNS

PLAN PREPARED BY: N.C.D.O.T. SIGNING AND DELINEATION UNIT

KELVIN JORDAN SIGNING & DELINEATION REGIONAL ENGINEER

DERRICK BEARD SIGNING & DELINEATION PROJECT DESIGN ENGINEER

