

PROJECT NO.	SHEET NO.	TOTAL NO.
2016CPT.08.18.10531	7	
2016CPT.08.18.20531		

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	BORROW EXCAVATION CY	INCIDENTAL STONE BASE TONS	SHOULDER RECONSTRUCTION SMI	1.5" MILLING SY	INCIDENTAL MILLING SY	SURFACE COURSE, S9.5B TONS	SURFACE COURSE, S9.5C TONS	SURFACE COURSE, SF9.5A TON	ASPHALT BINDER FOR PLANT MIX TONS	PATCHING EXISTING PAVEMENT TONS	ADJUST MANHOLES EA	PORTABLE LIGHTING LS	TEMPORARY SILT FENCE LF	WATTLE LF	SEED & MULCHING AC	INDUCTIVE LOOP SAWCUT LF		
2016CPT.08.18.10531	Lee	1	US 1 SBL	FROM CONST JOINT @ SR 1334 (PENDERGRASS RO) TO CONST JOINT @ SR 1198 (BRYAN DR)		2	MD	NO	NO	0.681	24-50	100		1.40	12,580	120		1,260		74			*	68	20	0.99	400		
TOTAL FOR MAP NO. 1										0.681		100		1.40	12,580	120		1,260		74				68	20	0.99	400		
2016CPT.08.18.10531	Lee	2	US 1 NBL	FROM CONST JOINT @ SR 1198 (BRYAN DR) TO CONST JOINT @ SR 1334 (PENDERGRASS RD)		2	MD	NO	NO	0.592	24-42	87		1.20	4,725	85		1,155		68			*	59	10	0.86	375		
TOTAL FOR MAP NO. 2										0.592		87		1.20	4,725	85		1,155		68				59	10	0.86	375		
2016CPT.08.18.10531	Lee	3	NC 42	FROM SR 1535 (BERKE THOMAS ROAD) TO CHATHAM COUNTY LINE		2	2WU	NO	NO	5.581	24	819	270	11.16		450	7,800			468	1,255			558	90	8.12			
TOTAL FOR MAP NO. 3										5.581		819	270	11.16		450	7,800			468	1,255			558	90	8.12			
TOTAL FOR PROJ NO. 2016CPT.08.18.10531										6.854		1,006	270	13.76	17,305	655	7,800	2,415		610	1,255		1	685	120	9.97	775		
2016CPT.08.18.20531	Lee	4	SR 1300 (CHRIS COLE RD)	FROM CONST JOINT @ SR 1007 (PLANK RD) TO CONST JOINT @ US 1		2	2WU	NO	NO	4.043	24	593	385	8.09		534		5,460		366	1,432			404	70	5.88			
TOTAL FOR MAP NO. 4										4.043		593	385	8.09		534		5,460		366	1,432			404	70	5.88			
2016CPT.08.18.20531	Lee	5	SR 1144 (GREENWOOD RD)	FROM SR 1162 (SHERIFF WATSON RD) TO CONST JOINT @ SR 1001 (EDWARDS RD)		2	2WU	NO	NO	0.856	24	126	50	1.71		267		1,230		83	770			86	20	1.25	240		
TOTAL FOR MAP NO. 5										0.856		126	50	1.71		267		1,230		83	770			86	20	1.25	240		
2016CPT.08.18.20531	Lee	6	SR 1531 (SWANN STATION ROAD)	FROM HARNETT COUNTY LINE TO CONST JOINT @ US 421		2	2WU	NO	NO	1.078	20	159	65	2.16		195		1,140		76	114			108	20	1.56			
TOTAL FOR MAP NO. 6										1.078		159	65	2.16		195		1,140		76	114			108	20	1.56			
2016CPT.08.18.20531	Lee	7	SR 1481 (NORTH LAKES DR)	FROM CONST JOINT @ SR 1466 (DEEP RIVER RD) TO SR 1476 (CLYDE RHYNE DR)		2	2WU	NO	NO	0.389	20	58	40	0.78		267		485		32	404	1		39	10	0.57			
TOTAL FOR MAP NO. 7										0.389		58	40	0.78		267		485		32	404	1		39	10	0.57			
2016CPT.08.18.20531	Lee	8	SR 1537 (POPLAR SPRINGS CH RD)	FROM SR 1505 (GUNTHER RD) TO CONST JOINT @ SR 1508 (LICK CREEK RD)		2	2WU	NO	NO	3.993	18	586	250	7.99		200		3,930		263	2,359			400	60	5.81			
TOTAL FOR MAP NO. 8										3.993		586	250	7.99		200		3,930		263	2,359			400	60	5.81			
2016CPT.08.18.20531	Lee	9	SR 1309 (DYCUS RD)	FROM CONST JOINT @ SR 1305 (HENLEY RD) TO CONST JOINT @ SR 1313 (BLACKSTONE RD)		2	2WU	NO	NO	1.436	18	211	120	2.87		223		1,490		100	680			144	30	2.09			
TOTAL FOR MAP NO. 9										1.436		211	120	2.87		223		1,490		100	680			144	30	2.09			
TOTAL FOR PROJ NO. 2016CPT.08.18.20531										11.795		1,733	910	23.60		1,686		13,735		920	5,759		1	1,181	210	17.16	240		
GRAND TOTAL										18.649		2,739	1,180	37.36		17,305	2,341	7,800	2,415	13,735	1,530	7,014		1	1	1,866	330	27.13	1,015