DocuSign Envelope ID: C748AF11-4B9C-4EAF-82E5-35D73BADED32

PROJECT REFERENCE NO.	SHEET NO.
B-4490	11
R/W SHEET NO.	

ROADWAY DESIGN ENGINEER

NORTH CAROLINA PROFESSIONAL SEAL 19563 ENGINEER TIMOTHY SCOTT HAYES

Docusigned by: Timothy Scott Hayes 8/17/2016

HYDRAULICS ENGINEER

NORTH CAROLINA PROFESSIONAL SEAL 039785 ENGINEER Craig A. Freeman Jr.

Docusigned by: Craig A. Freeman Jr. 8/17/2016

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

PLANS PREPARED BY:

PARSONS BRINCKERHOFF
434 FAYETTEVILLE STREET
SUITE 1500
RALEIGH, NC 27601
LICENSE NO. F-0165

REVISIONS

8/17/99

NAD 83/NSRS 2007

-Y3-
PI Sta 17+09.63
△ = 43° 13' 24.1" (RT)
D = 8° 48' 53.0"
L = 490.35'
T = 257.51'
R = 650.00'
DS = 40 MPH
SE = 4.0%
RO = 124

-Y11A-
PI Sta 10+98.78
△ = 55° 05' 13.9" (RT)
D = 143° 14' 22.0"
L = 38.46'
T = 20.86'
R = 40.00'
SE = n/a
RO = n/a

LONNIE MELVIN
DB 863 PG 13

MARY S. HARRIS
DB 6040 PG 861

JIMMIE SMITH
DB 3228 PG 518

RICHARD BROWN
DB 500 PG 182
TRACT 1

CITY OF FAYETTEVILLE
DB 9742 PG 379
(36)

ALBRTTA MCMILLAN
DB 495 PG 127

INEZ JONES
DB 495 PG 171

ALVIN ELLIOTT
DB 4588 PG 592

ELLEN GLADDEN
DB 6403 PG 374

CITY OF FAYETTEVILLE
DB 9742 PG 379
(37)

COUNCIL & WILLIFORD PROPERTIRS, LLC
DB 5754 PG 200
(38)

(5)

DURHAM ST 24' BST

MURCHISON RD 40' BST

DURHAM ST -Y11A-

MURCHISON RD -Y3-

BRUNNER ST -Y11-

-Y11A- POT Sta. 10+00.00

-Y11A- PC Sta. 10+77.92

-Y11A- PT Sta. 11+16.38

-Y3- POT Sta. 10+00.00

-Y3- POT Sta. 13+23.43 = -Y11A- POT Sta. 11+65.79

-Y3- POT Sta. 13+65.00

-Y3- POT Sta. 14+10.60 = -Y11- POT Sta. 12+31.02

-Y3- PC Sta. 14+52.13

BEGIN CONSTRUCTION -Y11- POT Sta. 11+45.00

BEGIN CONSTRUCTION -Y11A- POT Sta. 10+73.27

PUE TO BE OBTAINED BY OTHERS

PROPOSED 5' SIDEWALK

PROP. 5' SIDEWALK

50' TAPER

RETAIN

REMOVE CB

REMOVE PIPE

REMOVE MH

REMOVE JB

GRADE TO DRAIN

SIZE & TYPE UNKNOWN

ABANDONED ACCORDING TO UTILITY OWNER

MATCH LINE SEE SHEET 12 -Y3- STA. 14+80.00

SEE SHEET No. 23 FOR -Y3- PROFILE
SEE SHEET No. 25 FOR -Y11A- PROFILE
SEE SHEET No. 25 FOR -Y11- PROFILE

8/5/2016 8:55:59 AM
C:\Projects\4490\Roadway\Plan\Sheets\4490_rdy_plan_sht_11.dgn
8/22/2016