PROJECT REFERENCE NO.	SHEET NO.
U-3308	EC-3
R/W SHEET NO.	
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

SOIL STABILIZATION SUMMARY SHEET

EROSION CONTROL MATTING FOR SLOPES 2:1 OR STEEPER

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
4	-LALT-	14+50	15+85	LT	700
4	-LALT-	14+50	15+85	RT	410
4	-LALT-	17+15	20+00	LT	775
4	-LALT-	14+50	18+50	RT	580
5/6	-LALT-	21+30	28+50	LT	2100
5	-LALT-	21+30	24+80	RT	1030
7	-LALT-	34+00	35+50	LT	225
10	-LALT-	50+00	53+00	LT	290
10	-LALT-	48+25	48+50	RT	45
12	-LALT-	59+25	61+85	LT	400
12	-LALT-	62+55	63+00	RT	80
4	-R1-	11+00	14+15	LT	1070
4	-R1-	11+00	12+00	RT	230
4	-R3-	10+75	13+50	LT	630
8	-Y7-	11+00	11+50	RT	30
11	-Y18-	11+50	13+25	RT	210
11	-Y18-	12+35	13+00	LT	70
			SUBTOTAL		8875
MISC. MATTING TO BE INSTALLED AS DIRECTED BY ENGINEER					6100
				TOTAL	14975
				SAY	15000

REVISIONS

8/17/99

PLOT DRIVER: $PLTDRVS$
USER: $USER$ DATE: 4/10/2015
FILE: $PWVARVAULTPATHDESC$

PENTABLE: $PENTBLS$
TIME: 10:41:16 AM SCALE: $SCALESHORT$