

PROJECT NO.	SHEET NO.	TOTAL NO.
2017CPT.13.03.10571, 2017CPT.13.03.20571, 2017CPT.13.03.20572	12	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	INCIDENTAL STONE BASE TON	SHOULDER RECONSTRUCTION SMI	MILLING ASPHALT PAVEMENT, 0" TO 1-1/2" DEPTH SY	INCIDENTAL MILLING SY	ASPHALT CONC SURFACE COURSE, TYPE S9.5B TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A TON	ASPHALT BINDER FOR PLANT MIX TON	PATCHING EXISTING PAVEMENT TON	ASPHALT SURFACE TREATMENT, DOUBLE SEAL SY	ASPHALT SURFACE TREATMENT, FOG SEAL SY	EMULSION FOR ASPHALT SURFACE TREATMENT GAL	
2017CPT.13.03.10571	Madison	1	NC 63	FROM 1.5 MILES WEST OF SR 1100 TO SR 1162 (MP 4.12 - MP 8.22)	1	2	2WU	NO	NO	4.1	20	205	8.20		500	4,473		268	55				
		2	US 25/70 BUS	FROM NC 251 TO PVMT CHANGE AT MARSHALL (MP 1.47 - MP 3.55)	1	2	2WU	NO	NO	2.08	20	104	4.16		500	2,269		136	25				
		3	NC 251	FROM BRIDGE NO.'S 8 & 9 TO US 25/70 (MP 4.10 - MP 4.91)	1	2	2WU	NO	NO	0.81	44	41	1.62		1,655	1,937		116	25				
		4	US 25/70	FROM SR 1135 TO SR 1439 (MP 7.34 - MP 10.76)	1	2	2WU	NO	NO	3.42	30	171	6.84		950	5,585		335	25				
		5	NC 213	FROM SR 1611 TO SR 1426 (MP 7.92 - MP 9.92)	1,4,5,6	3	MU	NO	NO	2	42	100	3.23	5,000	1,500	4,567		274	20				
TOTAL FOR PROJ NO. 2017CPT.13.03.10571										12.41		621	24.05		5,105	18,831		1,129	150				
2017CPT.13.03.20571	Madison	6	SR 1318	FROM SR 1395 TO SR 1341 (MP 7.94 - MP 12.80)	2	2	2WU	NO	NO	4.86	18	243	9.72				4,690	314	50				
		7	SR 1318	FROM SR 1341 TO SR 1636 (MP 12.80 - MP 18.20)	2	2	2WU	NO	NO	5.4	20	270	10.80				5,786	388	40				
		8	SR 1370	FROM SR 1364 TO SR 1372 (MP 1.28 - MP 4.45)	2	2	2WU	NO	NO	3.17	18	159	6.34				3,059	205	40				
		9	SR 1364	FROM SR 1370 TO SR 1366 (MP 0.00 - MP 3.10)	2	2	2WU	NO	NO	3.1	18	155	6.20				2,991	200	30				
		10	SR 1346	FROM I-26 TO EOM (MP 0.00 - MP 1.30)	2	2	2WU	NO	NO	1.3	18	65	2.60				1,254	84	20				
		11	SR 1624	FROM SR 1604 TO EOM (MP 0.00 - MP 0.33)	2	2	2WU	NO	NO	0.33	20	17	0.66				354	24	10				
		12	SR 1604	FROM SR 1582 TO EOM (MP 0.00 - MP 0.45)	2	2	2WU	NO	NO	0.45	20	23	0.90				482	32	20				
		13	SR 1180	FROM SR 1181 TO SR 1181 (MP 0.00 - MP 3.23)	2	2	2WU	NO	NO	3.23	20	162	6.46				3,461	232	20				
		14	SR 1431	FROM SR 1346 TO EOP (MP 0.00 - MP 0.21)	3	2	2WU	NO	NO	0.21	19								5	2,341	2,341	1,290	
TOTAL FOR PROJ NO. 2017CPT.13.03.20571										22.05		1,094	43.68				22,077	1,479	235	2,341	2,341	1,290	
2017CPT.13.03.20572	Madison	15	SR 1374	FROM SR 1375 TO EOP (MP 0.00 - MP 0.60)	3	2	2WU	NO	NO	0.6	18								10	6,336	6,336	3,485	
		16	SR 1376	FROM SR 1375 TO EOP (MP 0.00 - MP 0.20)	3	2	2WU	NO	NO	0.2	18								6	2,112	2,112	1,162	
		17	SR 1382	FROM SR 1383 TO SR 1380 (MP 0.00 - MP 0.51)	3	2	2WU	NO	NO	0.51	18								10	5,386	5,386	2,963	
		18	SR 1107	FROM SR 1001 TO BUNCOMBE COUNTY LINE (MP 0.00 - MP 2.51)	3	2	2WU	NO	NO	2.51	18								35	26,506	26,506	14,579	
		19	SR 1453	FROM US 25/70 TO US 25/70 (MP 0.00 - MP 0.78)	3	2	2WU	NO	NO	0.78	20								8	9,152	9,152	5,034	
		20	SR 1622	FROM SR 1509 TO EOM (MP 0.00 - MP 0.20)	3	2	2WU	NO	NO	0.2	18								6	2,112	2,112	1,162	
		21	SR 1152	FROM SR 1153 TO EOP (MP 0.00 - MP 0.61)	3	2	2WU	NO	NO	0.61	18								6	6,442	6,442	3,543	
		22	SR 1153	FROM SR 1151 TO SR 1152 (MP 0.00 - MP 0.37)	3	2	2WU	NO	NO	0.37	18								1	3,907	3,907	2,149	
		23	SR 1375	FROM SR 1370 TO EOP (MP 0.00 - MP 1.85)	3	2	2WU	NO	NO	1.85	18								30	19,536	19,536	10,745	
		24	SR 1457	FROM US 23A TO SR 1503 (MP 0.00 - MP 0.40)	3	2	2WU	NO	NO	0.4	18								12	4,224	4,224	2,325	
		25	SR 1136	SR 1135 TO SR 1203 (MP 1.10 - MP 1.55)	3	2	2WU	NO	NO	0.45	19								25	5,016	5,016	2,760	
TOTAL FOR PROJ NO. 2017CPT.13.03.20572										8.48									149	90,729	90,729	49,907	
GRAND TOTAL										42.94		1,715	67.73		5,000	5,105	18,831	22,077	2,608	534	93,070	93,070	51,197