

PROJECT NO.	SHEET NO.	TOTAL NO.
2017CPT.13.02.10121, 2017CPT.13.02.20121, 2017CPT.13.02.20122, 51209.1B	23	

SUMMARY OF MILL & FILL ON I-40

I-40 WEST BOUND				
APPROXIMATE MILE MARKER LOCATION	LANE	APPROXIMATE LENGTH OF REPAIR LF	APPROXIMATE WIDTH OF REPAIR LF	ASPHALT CONC SURFACE COURSE, TYPE S9.5C TON
115.75	RT	50	12.5	8.0
113.64	RT	50	12.5	8.0
112.4	RT	50	12.5	8.0
111.1	RT	100	12.5	16.0
110.4	LT	50	12.0	7.0
107.6	LT	50	12.0	7.0
107.05	RT	50	12.5	8.0
104.78	RT	400	12.5	62.0
104.5	RT	300	12.5	47.0
103.84	LT	800	12.0	119.0
103.84	RT	800	12.5	124.0
103.66	LT	200	12.0	30.0
103.34	LT	50	12.0	7.0
101.41	LT	600	12.0	90.0
98.95	RT	50	12.5	8.0
98.57	RT	50	12.5	8.0
97.59	RT	850	12.5	132.0
96.55	RT	50	12.5	8.0
96.37	RT	100	12.5	16.0
96.25	LT	50	12.0	7.0
95.85	RT	50	12.5	8.0
95.41	RT	50	12.5	8.0

I-40 EAST BOUND				
APPROXIMATE MILE MARKER LOCATION	LANE	APPROXIMATE LENGTH OF REPAIR LF	APPROXIMATE WIDTH OF REPAIR LF	ASPHALT CONC SURFACE COURSE, TYPE S9.5C TON
96.35	RT	100	12.5	16.0
98.5	RT	250	12.5	39.0
100	RT	100	12.5	16.0
100.54	RT	500	12.5	78.0
102.28	RT	50	12.5	8.0
102.41	RT	1250	12.5	194.0
102.7	RT	900	12.5	140.0
103.07	RT	50	12.5	8.0
103.13	RT	100	12.5	16.0
103.58	RT	200	12.5	31.0
104.18	LT	50	12.0	7.0
104.5	RT	800	12.5	124.0
105.8	RT	150	12.5	23.0
107.25	RT	100	12.5	16.0
108.55	RT	50	12.5	8.0
108.6	RT	50	12.5	8.0
110.67	RT	50	12.5	8.0
111.4	RT	50	12.5	8.0
111.59	RT	50	12.5	8.0
111.67	RT	50	12.5	8.0
112.24	RT	50	12.5	8.0
112.75	RT	100	12.5	16.0
114.35	RT	50	12.5	8.0
115.33	RT	50	12.5	8.0
115.51	RT	50	12.5	8.0

NOTE - SEE "SUMMARY OF QUANTITIES" FOR ASPHALT TOTAL