

PROJECT NO.	SHEET NO.	TOTAL NO.
2017CPT.14.03.10221.1, etc.	35	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	SHOULDER RECONSTRUCTION SMI	3" MILLING SY	4" MILLING SY	2" MILLING SY	0" TO 2" MILLING SY	BASE COURSE, B25.0B TONS	INTER-MEDIATE COURSE, I19.0B TONS	INTER-MEDIATE COURSE, (WEDGING) I19.0B TONS	SURFACE COURSE, S9.5B TONS	LEVELING COURSE, S9.5B TONS	SURFACE COURSE, SF9.5A TONS	LEVELING COURSE, SF9.5A TON	ASPHALT BINDER FOR PLANT MIX TONS	PATCHING EXISTING PAVEMENT TONS	CURB RAMPS (Std. 848.06 or details) EA	PAVEMENT INTERLAYER SY	ASPHALT FOR PAVEMENT INTERLAYER TONS		
2017CPT.14.03.10871.1	Swain	1	NC 28	FROM MACON LINE TO US 19/74	1	2	2WU	NO	NO	7.146	20	14.29	33,989					5,876				6,490	5,092	1,022						
TOTAL FOR PROJ NO. 2017CPT.14.03.10871.1										7.146		14.29	33,989					5,876				6,490	5,092	1,022						
2017CPT.14.03.20381.1	Graham	2	SR-1117	FROM NC143 BUS TO US129	2	2	2WU	NO	NO	1.39	20	2.78										1,206	687	122	513					
		3	SR-1110	FROM NC143 TO END OF PAVEMENT	2	2	2WU	NO	NO	2.6	18	5.20											2,031	1,157	206	625				
		4	SR-1232	FROM NC28 TO SR-1268	2	2	2WU	NO	NO	1.6	19	3.20											1,319	1,003	149					
		5	SR-1247	FROM US129 TO END OF MAINT.	3	2	2WU	NO	NO	4.25	18	8.50												4,434	266					
		6	SR-1246	FROM 1 MILE WEST OF NC28 TO SR-1247	3	2	2WU	NO	NO	5	19	10.00													5,834	350	150			
TOTAL FOR PROJ NO. 2017CPT.14.03.20381.1										14.84		29.68										4,556	13,115	1,093	1,288					
2017CPT.14.03.20201.1	Cherokee	7	SR-1580	FROM US19 TO SR-1556	12	2	2WU	NO	NO	4.2	20	8.40										3,746	2,282	388	300		49,280	420		
		8	SR-1559	FROM SR-1560 TO SR-1611	6	2		NO	NO	0.42	18	0.84											348		23					
		9	SR-1304	FROM US19 TO US19	2	2	2WU	NO	NO	2.56	19	5.12											2,196	1,605	243	435				
		10	SR-1453	FROM SR-1454 TO END OF MAINT.	4	2	2WU	NO	NO	0.78	18	1.60		8,237				2,066					732		140					
		11	SR-1454	FROM SR-1453 TO END OF MAINT.	4	2	2WU	NO	NO	0.55	18	1.10		5,808				1,457					521		99					
TOTAL FOR PROJ NO. 2017CPT.14.03.20201.1										8.51		17.06		14,045			3,523					7,543	3,887	893	735		49,280	420		
2017CPT.14.03.10221.1	Clay	12	US 64	FROM .44 MILES WEST OF SR-1349 TO 1.51 MILES EAST OF SR-1349	5	2	2WU	NO	NO	1.94	30	3.88	7,895					1,485			3,226	2,301			414					
TOTAL FOR PROJ NO. 2017CPT.14.03.10221.1										1.94		3.88	7,895					1,485			3,226	2,301			414					
2017CPT.14.03.20221.1	Clay	13	SR-1300	FROM US 64 TO SR-1344	6	2	2WU	NO	NO	3.98	20	7.98										3,693		247	70					
		14	SR-1305	FROM US64 TO SR-1307	7	2	2WU	NO	NO	3.61	18	7.22											2,961	1,800	320	855				
TOTAL FOR PROJ NO. 2017CPT.14.03.20221.1										7.59		15.20										6,654	1,800	567	925					
2017CPT.14.03.20561.1	Macon	15	SR-1538	FROM 1.7 MILES WEST OF SR1535 TO SR-1535	8	2	2WU	NO	NO	1.7	19	3.40									1,730	1,130			177	250				
		16	SR-1540	FROM SR-1538 TO END OF PAVEMENT	2	2	2WU	NO	NO	1.16	19	2.22											995	599	103	330				
		17	SR-1310	FROM US 19/74 TO USFS ROAD 308	2	2	2WU	NO	NO	4.96	19	9.12											4,294	2,734	452	45				
		18	SR-1689	FORM SR-1603 TO END OF MAINT.	11	2	2WU	NO	NO	0.34	20													330		22	300	5		
		19	SR-1579	FROM US64 TO END OF MAINT	12	2	2WU	NO	NO	0.23	20	0.46												212	159	25	200			
		20	SR-1616	FROM NC106 TO END OF MAINT	6	2	2WU	NO	NO	1.14	16	2.28												780		52	200			
		21	SR-1615	FROM SR-1616 TO END OF MAINT.	6	2	2WU	NO	NO	0.97	16	1.94												706		47	100			
		22	SR-1617	FROM NC106 TO END OF MAINT.	2	2	2WU	NO	NO	0.55	18	1.10												495	282	50	50			
		23	SR-1619	FROM NC106 TO NC106	2	2	2WU	NO	NO	1.48	16	2.96												1,078	687	113	50			
24	SR-1694	FROM US64 TO END OF MAINT.	2	2	2WU	NO	NO	0.15	18	0.30												123	77	13	200					
TOTAL FOR PROJ NO. 2017CPT.14.03.20561.1										12.68		23.78				3,191				1,730	1,130	9,013	4,538	1,054	1,725	5				
2017CPT.14.03.10871.2	Swain	25	US 19	FROM SR-1195 TO JACKSON LINE	8	2	2WU	NO	NO	2.131	20	4.26									2,325	1,406			231	1,251				
		27	US 19	FROM JACKSON CO. LINE TO .38 MILES WEST OF US 441 SOUTH	9	2	2WU	NO	NO	1.27	20	2.54										1,392				133	525			
		28	US 19	FROM .38 MILES WEST OF US 441 SOUTH TO SR-1360 & US 441 NORTH	10	2	MU	NO	NO	0.861	36					18,184						2,210				133				
TOTAL FOR PROJ NO. 2017CPT.14.03.10871.2										4.262		6.80			18,184					5,927	1,406			497	1,776					
2017CPT.14.03.10501.1	Jackson	26	US 19	FROM SWAIN LINE TO SWAIN LINE	8	2	2WU	NO	NO	0.241	20	0.48									263	159			26	120				
TOTAL FOR PROJ NO. 2017CPT.14.03.10501.1										0.241		0.48									263	159			26	120				
GRAND TOTAL										57.209		111.17	41,884	14,045	18,184	3,191	3,523	7,361	277	11,146	4,996	34,256	28,432	5,566	6,569	5	49,280	420		