

SHOULDER DRAIN SUMMARY

PROJECT #	MAP #	STATION	STATION	AGGREGATE SHOULDER DRAIN				SHOULDER DRAIN OUTLET LOCATIONS						Remove & Replace Concrete Apron EA	FLOWABLE FILL CY	ASPHALT PLANT MIX, PAVEMENT REPAIR TON
				LOCATION		SHOULDER DRAIN	4" SHOULDER DRAIN PIPE	STATION	LOCATION		LENGTH OF OUTLET PIPE	OUTLET TYPE				
				LANE	LT or RT	FT	FT		LANE	LT or RT	FT	TIE TO DI	PAD EA			
I-5821	2	10+00	79+54	NB	RT	6,954	6,954									
I-5821	2							10+00	SB	RT	30		1			
I-5821	2							14+00	SB	RT	30		1			
I-5821	2							21+00	SB	RT	30		1			
I-5821	2							26+00	SB	RT	30		1			
I-5821	2							31+00	SB	RT	30		1			
I-5821	2							36+00	SB	RT	30		1			
I-5821	2							41+00	SB	RT	30		1			
I-5821	2							46+00	SB	RT	30		1			
I-5821	2							51+00	SB	RT	30		1			
I-5821	2							56+00	SB	RT	30		1			
I-5821	2							60+25	SB	RT	30	X		1		
I-5821	2							65+25	SB	RT	30		1			
I-5821	2							70+50	SB	RT	30	X		1		
I-5821	2							75+00	SB	RT	30		1			
I-5821	2							79+25	SB	RT	30		1			
I-5821	2	79+54	83+19					BRIDGE OVER DEEP RIVER								
I-5821	2	83+19	121+30	SB	RT	3,811	3,811									
I-5821	2							88+00	SB	RT	30		1			
I-5821	2							93+00	SB	RT	30		1			
I-5821	2							97+00	SB	RT	30		1			
I-5821	2							100+00	SB	RT	30		1			
I-5821	2							105+00	SB	RT	30		1			
I-5821	2							110+00	SB	RT	30		1			
I-5821	2							115+25	SB	RT	30	X		1		
I-5821	2							120+50	SB	RT	30	X		1		
I-5821	2	121+30	136+15					NO SHOULDER DRAIN NEEDED IN THIS LOCATION								
I-5821	2	136+15	162+67	SB	RT	2,652	2,652									
I-5821	2							136+15	SB	RT		X				11
I-5821	2							140+00	SB	RT	30	X		1		
I-5821	2			Concrete Apron Repair					143+50	SB	LT			1		
I-5821	2							145+00	SB	RT	30		1			
I-5821	2							150+00	SB	RT	30		1			
I-5821	2			Concrete Apron Repair					150+00	SB	LT			1	2	
I-5821	2							154+75	SB	RT	30	X		1		
I-5821	2	162+67	169+56					NO SHOULDER DRAIN NEEDED IN THIS LOCATION								
I-5821	2	169+56	200+76	SB	RT	3,120	3,120	187+11 to 200+76 in new Asp. Sh.								96
I-5821	2							169+50	SB	RT	30		1			
I-5821	2							175+00	SB	RT	30	X		1		
I-5821	2							178+00	SB	RT	30	X		1		
I-5821	2							185+00	SB	RT	30	X		1		
I-5821	2							190+23	SB	RT		X				
I-5821	2	200+76	242+16					NO NEW SHOULDER DRAIN NEEDED IN THIS LOCATION								
I-5821	2			Concrete Apron Repair					237+25	NB	LT			1		
I-5821	2			Concrete Apron Repair					240+75	NB	LT			1		
MAP 2 TOTALS						16,537	16,537				930		22	13	2	107
I-5821 TOTALS						29,870	29,870				1,740		34	30	6	203