PROJECT REFERENCE NO.	SHEET NO.
I-5821, I-5738, I-5789	8

SHOULDER DRAIN SUMMARY

AGGREGATE SHOULDER DRAIN								SHOULDER DRAIN OUTLET LOCATIONS								
PROJECT #	MAP #	STATION	STATION	LOCATION		SHOULDER DRAIN	4" SHOULDER DRAIN PIPE	STATION	LOCATION		LENGTH OF OUTLET PIPE	OUTLET TYPE		Remove & Replace Concrete Apron	FLOWABLE FILL	ASPHALT PLANT MIX, PAVEMENT REPAIR
				LANE	LT or RT	FT	FT		LANE	LT or RT	FT	TIE TO DI	PAD	EA	CY	TON
I-5738	3	10+00	15+00					NO NEW SHOULDER DRAIN NEEDED IN THIS LOCATION								
I-5738	3	Concrete Apron Repair						13+20	NB	LT				1		
I-5738	3	15+00	65+13	NB	RT	5,013	5,013									
I-5738	3							15+00	NB	RT	30		1			
I-5738	3							17+40	NB	RT	30	X		1		
I-5738	3							26+80	NB	RT	30	X		1		
I-5738	3							32+30	NB	RT	30	X		1		
I-5738	3							37+30	NB	RT	30		1			
I-5738	3							42+30	NB	RT	30		1			
I-5738	3							47+30	NB	RT	30		1			
I-5738	3							53+60	NB	RT	30		1			
I-5738	3							55+60	NB	RT	30		1			
I-5738	3							60+60	NB	RT	30	X		1		
MAP 3 TOTALS						5,013	5,013				300		6	5	0	0
I-5738	6	10+00	31+50					NO NEW SHOULDER DRAIN NEEDED IN THIS LOCATION								
I-5738	6	Concrete Apron Repair						12+00	SB	LT				1		
I-5738	6	Concrete Apron Repair						15+50	SB	LT				1		
I-5738	6	Concrete Apron Repair						18+50	SB	LT				1		
I-5738	6	Concrete Apron Repair						22+50	SB	LT				1		
I-5738	6	31+50	52+00	SB	RT	2,050	2,050									
I-5738	6							31+50	SB	RT	30		1			
I-5738	6							36+50	SB	RT	30		1			
I-5738	6							40+50	SB	RT	30		1			
I-5738	6							44+50	SB	RT	30	X		1		
I-5738	6							49+50	SB	RT	30	X		1		
I-5738	6	52+00	55+50					NO SHOULDER DRAIN NEEDED IN THIS LOCATION								
I-5738	6	55+00	67+13	SB	RT	1,213	1,213									
I-5738	6							59+50	SB	RT	30		1			
I-5738	6							62+50	SB	RT	30	X		1		
I-5738	6							67+50	SB	RT	100		1			
MAP 6 TOTALS						3,263	3,263				310		5	7	0	0
I-5738 TOTALS						**8,276**	**8,276**				**610**		**11**	**12**	**0**	**0**