

STATE OF NORTH CAROLINA  
 DIVISION OF HIGHWAYS

**SUMMARY OF EARTHWORK**

STATION	STATION	UNCL. EXCAV.	UNDERCUT	EMBANK.	BORROW	WASTE
W-5203AA						
-L- 416 + 00.00	-L- 437 + 10.00	610		688	78	
SUBTOTALS:		610		688	78	
W-5601BB						
-L- 482 + 00.00	-L- 484 + 50.00	23				23
SUBTOTALS:		23				23
SUBTOTALS:						
PROJECT TOTALS:		633		688	78	23
EST. SHOULDER MATERIAL (W-5203AA /W-5601BB)				388	388	
WASTE IN LIEU OF BORROW					-23	-23
PROJECT TOTAL		633		1,076	443	
EST. 5% TO REPLACE TOP SOIL ON BORROW PIT					22	
GRAND TOTALS:		633		1,076	465	
SAY:		635			470	

UNDERCUT EXCAVATION (W-5203AA): 600 CY

Note: Approximate quantities only. Unclassified Excavation, Borrow Excavation, Fine Grading, and Clearing & Grubbing will be paid for at the contract lump sum price for "Grading."

5/28/99  
 05-MAY-2016 15:30  
 C:\W-5203AA\Drawings\Proc\W-5203AA.RDY\_SUM\_03B-1.dgn  
 USER:DLW