



SECTION A-A




SECTION B-B

FOR CLARITY, SECTIONS "A-A" AND "B-B" OMIT DETAILS OF TEST INSTRUMENTATION.



BOTTOM PLATE


NOTE: NOMINAL 6" SLICK LINE BETWEEN O-CELL & INSIDE OF REBAR (~6.25")



TOP PLATE


46.50" Ø X 2" THICK PLATE

(46.50" OR INSIDE DIAMETER OF REBAR CAGE - TEST PIER 1)



BOTTOM PLATE


NOTE: NOMINAL 5" SLICK LINE BETWEEN O-CELL & INSIDE OF REBAR (~5.75")



TOP PLATE


35.50" Ø X 2" THICK PLATE

(35.50" OR INSIDE DIAMETER OF REBAR CAGE - TEST PIER 2)




ELEVATION

(LOAD TEST #1 - TEST PIER 1)  
SG LEVEL # DENOTES STRAIN GAUGE ELEVATIONS




ELEVATION

(LOAD TEST #2 - TEST PIER 2)  
SG LEVEL # DENOTES STRAIN GAUGE ELEVATIONS




DETAIL "B"



DETAIL "C"

ASSEMBLY STEPS:

1. O-CELL FITTED WITH TOP AND BOTTOM STEEL PLATES.
2. TOP AND BOTTOM STEEL PLATES OF O-CELL ASSEMBLY WELDED TO NON-CONTINUOUS REINFORCING CAGE WITH FILLET WELDS ON BOTH SIDES OF REBAR.
3. CONSTRUCT TREMIE GUIDE TO DIRECT TREMIE PAST THE O-CELL ASSEMBLY.
4. REINFORCING CAGE LOWERED INTO EXCAVATION AND SECURED AT REQUIRED ELEVATION.



BILL OF MATERIAL

TEST PIER 1					
BAR	NUMBER	SIZE	TYPE	LENGTH	WEIGHT
V1	20	#11	STR	8'-8"	921
V2	40	#11	STR	47'-6"	10095
SP-1	1	#5	1	303'-6"	317
SP-2	1	#5	1	2770'-11"	2890


REINFORCING STEEL	(LBS.)	11016
SPIRAL REINFORCING STEEL	(LBS.)	3207
TEST PIER CONCRETE	(C.Y.)	69.4
5'-0" Ø TEST PIER	(LIN. FT.)	95.50
SID INSPECTIONS	EACH	1
SPT TESTING	EACH	1
CSL TESTING	EACH	1
SONIC CALIPER TESTING	EACH	1
PERMANENT STEEL CASING	(LIN. FT.)	22.0
CSL TUBES	(LIN. FT.)	388.0
AXIAL LOAD TEST NO.1	LUMP SUM	

TEST PIER 2					
BAR	NUMBER	SIZE	TYPE	LENGTH	WEIGHT
V3	16	#11	STR	32'-8"	2777
V4	32	#11	STR	27'-6"	4675
SP-3	1	#5	1	835'-8"	872
SP-4	1	#5	1	1176'-2"	1227

REINFORCING STEEL	(LBS.)	7452
SPIRAL REINFORCING STEEL	(LBS.)	2099
TEST PIER CONCRETE	(C.Y.)	37.0
4'-0" Ø TEST PIER	(LIN. FT.)	79.50
SID INSPECTIONS	EACH	1
SPT TESTING	EACH	1
CSL TESTING	EACH	1
SONIC CALIPER TESTING	EACH	1
PERMANENT STEEL CASING	(LIN. FT.)	22.0
CSL TUBES	(LIN. FT.)	324.0
AXIAL LOAD TEST NO.2	LUMP SUM	

PROJECT NO. B-4929  
PENDER COUNTY  
STATION: 38+13.81 -L2-

SHEET 2 OF 2



DocuSigned by:  
David Stutts  
AA2998B0C84F2

STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION  
RALEIGH

SUBSTRUCTURE  
AXIAL LOAD TEST

DRAWN BY :	T.R. PETERSON	DATE :	4/2016
CHECKED BY :	W.D. CRUTCHER	DATE :	4/2016
DESIGN ENGINEER OF RECORD:	D.S. STUTTS	DATE :	4/2016

REVISIONS						SHEET NO.	
NO.	BY:	DATE:	NO.	BY:	DATE:	S-211	
1			3			TOTAL SHEETS	
2			4			278	

DOCUMENT NOT CONSIDERED  
FINAL UNLESS ALL  
SIGNATURES COMPLETED

\*\*\*\*\*SYSTEM TIME\*\*\*\*\*  
\*\*\*\*\*DCN\*\*\*\*\*  
\*\*\*\*\*USERNAME\*\*\*\*\*