



PLAN OF FLOOR SLAB - STAGE I (PART A) & STAGE II

FOR PLAN OF FLOOR SLAB -STAGE I (PART B), SEE SHEET 9 OF 18.
 SILLS FOR STAGES VI & VII NOT SHOWN FOR CLARITY. SEE "SILL DETAILS" ON SHEET 6 OF 18.
 THE 18" Ø R.C. PIPE THROUGH THE SIDEWALL OF THE CULVERT SHALL BE LOCATED BY THE ENGINEER.
 THE REINFORCING STEEL SHALL BE FIELD BENT AS NECESSARY TO CLEAR PIPE. SEE DETAILS ON SHEET 15 OF 18.

PROJECT NO. B-4490
CUMBERLAND COUNTY
 STATION: 19+26.42 -L-

SHEET 7 OF 18

STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH

**TRIPLE 14 FT. X 9 FT.
 CONCRETE BOX CULVERT**



DocuSigned by:
 Kristy W. Alford
 3/29/2016

DRAWN BY :	I.L. AVERETTE	DATE :	07-15
CHECKED BY :	J.P. ADAMS	DATE :	08-15
DESIGN ENGINEER OF RECORD:	I.L. AVERETTE	DATE :	09-15

DOCUMENT NOT CONSIDERED
 FINAL UNLESS ALL
 SIGNATURES COMPLETED

REVISIONS						SHEET NO.	
NO.	BY:	DATE:	NO.	BY:	DATE:	C-7	
1			3			TOTAL SHEETS	
2			4			18	