

SHOULDER DRAIN SUMMARY

LINE	STATION TO STATION	LOCATION		SHOULDER DRAIN PIPE (FT)	SHOULDER DRAINS (FT)	OUTLET PIPES (FT)	CONCRETE PADS (EA)	OUTLET LOCATIONS						
		LANE	SHLD					422+25	425+25	428+25	431+25	434+25	437+00 (2GI)	440+00
-L-	422+25 TO 444+00 RT OUTSIDE	EBL	OUTSIDE	2400	2175	250	6	422+25	425+25	428+25	431+25	434+25	437+00 (2GI)	440+00
								442+25 (2GI)	444+00 (2GI)					
-L-/LREV-	462+00 TO 493+75 RT OUTSIDE	EBL	OUTSIDE	3405	3175	150	5	467+00 (2GI)	470+00	473+25	467+50 (2GI)	480+50 (2GI)	483+75	486+00
								488+50	491+00 (2GI)					
-LREV-/L-	496+75 TO 517+93 RT OUTSIDE	EBL	OUTSIDE	2300	2118	300	2	499+30 (2GI)	502+75	506+00	509+25 (2GI)	511+50 (2GI)	515+50 (2GI)	
-L-	444+00 TO 467+00 RT INSIDE	EBL	MEDIAN	2500	2300	120	1	444+00 (2GI)	448+40 (2GI)	451+50 (2GI)	456+50	461+50 (2GI)	467+00 (2GI)	
-L-/LREV-	431+00 TO 490+60 LT OUTSIDE	WBL	OUTSIDE	6750	5960	500	7	431+00	434+00	437+00 (2GI)	441+50 (2GI)	444+00 (2GI)	446+10 (2GI)	448+40 (2GI)
								451+50 (2GI)	456+50	460+00	463+50	467+00 (2GI)	470+00	472+50 (2GI)
								467+50 (2GI)	479+50 (2GI)	483+75 (2GI)	487+00			
-LREV-/L-	502+15 TO 517+93 LT OUTSIDE	WBL	OUTSIDE	1675	1578	180	3	502+15	505+50	509+25 (2GI)	512+25	515+50 (2GI)		
-L-	422+25 TO 431+00 LT INSIDE	WBL	MEDIAN	900	875	30	2	422+25	427+00					
-LREV-	491+00 TO 493+75 LT INSIDE	WBL	MEDIAN	290	275	20		491+00 (2GI)						
-LREV-	496+75 TO 501+00 LT INSIDE	WBL	MEDIAN	440	425	30		499+30 (2GI)	501+00 (2GI)					
	TOTAL			20660	18881	1580	26							
	SAY			20660	18890	1580	30							

C:\Users\jw2016\Documents\Projects\U2524D_RDY_SUM_03B-3.dgn
 5/4/2016 15:12
 \$\$\$\$ USER NAME \$\$\$\$.