PROJECT REFERENCE NO.	SHEET NO.
U-2524D	X-1E

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.

Earthwork quantities are calculated by the Roadway Design Unit. These earthwork quantities are based in part on subsurface data provided by the Geotechnical Engineering Unit.

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station Spdy8	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
0+96.44	0	0	0
1+64.10	0	338	0
2+28.06	0	253	0
2+54.48	0	99	0
3+01.10	0	243	0
3+90.14	0	526	0

Station Y8_Det	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
12+00.00	0	0	0
12+50.00	0	0	0
13+00.00	156	0	0
13+50.000	188	0	0
14+00.00	269	0	0
14+50.00	376	0	0
15+00.00	372	0	0
15+50.00	169	17	0
16+00.00	24	227	0
16+50.00	34	303	0
17+00.00	47	145	0
17+50.00	40	121	0
18+00.00	17	335	0
18+50.00	45	649	0
19+00.00	143	383	0
19+50.00	251	0	0
20+00.00	345	0	0
20+50.00	349	0	0
21+00.00	301	0	0
21+50.00	158	3	0
22+00.00	61	27	0
22+50.00	81	41	0
23+00.00	49	27	0
23+50.00	71	10	0
24+00.00	0	0	0

Station Y6A_Det	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
10+16.56	0	0	0
10+50.00	138	0	0
11+00.00	186	0	0
11+50.00	163	0	0
12+00.00	128	0	0
12+50.00	58	5	0
13+00.00	27	8	0
13+50.00	46	3	0
14+00.00	29	0	0

8/17/99
15-JUN-2016 16:21
J:\U-2524D\Roadway\XSC\Y8_XSECTIONS\U2524D_rdy_xpl_1E.dgn
$$$$$ISCFNAME$$$$