| PROJECT NO. | SHEET NO. |
|---|---|
| 2017CPT.03.02.10821, ETC. | 18 |

# SUMMARY OF QUANTITIES

| PROJECT NO | COUNTY | MAP NO | ROUTE | DESCRIPTION | TYP NO | LANES | LANE TYPE | FINAL SURFACE TESTING REQUIRED | REMOVE & REPLACE 4" SIDEWALK SY | 2'-6" CURB & GUTTER, REMOVE & REPLACE LF | REMOVE AND REPLACE CURB RAMP EA | ADJ. OF DROP INLET EA | ADJ. OF MANHOLES EA | ADJ. OF METER OR VALVE BOX EA | ADD GR POSTS EA | REMOVE & RESET EXISTING GR LF | REMOVE & REPLACE EXISTING GR LF | TEMP. SILT FENCE LF | STONE FOR EC CLASS B TON | SEDIMENT CONTROL STONE TON | TEMP. MULCHING ACR | SEED FOR TEMP. SEEDING LBS | FERTILIZER FOR TEMP. SEEDING TON | MATTING FOR EROSION CONTROL SY | 1/4" HARDWARE CLOTH LF | WATTLE LF | SEED & MULCHING AC | SEED FOR REPAIR SEEDING LB |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 2017CPT.03.02.10821 | Sampson | 1 | NC 242 (SALEMBURG HWY) | FROM NC 24 TO NORTHERN TOWN LIMITS SALEMBURG (MP 5.438 - MP 10.434) NO ASPHALT WORK TIP R-2303C (MP 6.352 - MP 6.674) & BRIDGE NO.19 [MP 7.014 - MP 7.044) | 1,2 | 2 - 3 | 2WU | NO | 8 | 70 | 1 | 2 | 2 | 13 | 10.00 | 2,400.00 | 100.00 | 344 | 86 | 86 | 2.50 | 172 | 0.86 | 30 | 172 | 60 | 2.50 | 172 |
| **TOTAL FOR MAP NO. 1** | | | | | | | | | **8** | **70** | **1** | **2** | **2** | **13** | **10.00** | **2,400.00** | **100.00** | **344** | **86** | **86** | **2.50** | **172** | **0.86** | **30** | **172** | **60** | **2.50** | **172** |
| 2017CPT.03.02.10821 | Sampson | 2 | NC 411 (HARRELLS HWY.) | FROM NC 903 TO 0.32 MI. SOUTH OF GARLAND NORTHERN CITY LIMITS (MP 8.984 - MP 13.764) | 3,4 | 2 | 2WU | NO | 4 | 40 | | 2 | 10 | 8 | | | | 425 | 106 | 106 | 3.00 | 213 | 3.09 | 30 | 213 | 70 | 3.09 | 213 |
| **TOTAL FOR MAP NO. 2** | | | | | | | | | **4** | **40** | | **2** | **10** | **8** | | | | **425** | **106** | **106** | **3.00** | **213** | **3.09** | **30** | **213** | **70** | **3.09** | **213** |
| **TOTAL FOR PROJ NO. 2017CPT.03.02.10821** | | | | | | | | | **12** | **110** | **1** | **4** | **12** | **21** | **10.00** | **2,400.00** | **100.00** | **769** | **192** | **192** | **5.50** | **385** | **3.95** | **60** | **385** | **130** | **5.59** | **385** |
| 2017CPT.03.02.20821 | Sampson | 3 | SR 1842 (BROWNS CHURCH RD.) | FROM US 421 TO SR 1827 (BASSTOWN RD.) MP 1.820 - MP 2.650 | 5 | 2 | 2WU | NO | | | | | | | | | | 166 | 42 | 42 | 0.60 | 83 | 0.42 | 20 | 83 | 30 | 0.60 | 83 |
| **TOTAL FOR MAP NO. 3** | | | | | | | | | | | | | | | | | | **166** | **42** | **42** | **0.60** | **83** | **0.42** | **20** | **83** | **30** | **0.60** | **83** |
| 2017CPT.03.02.20821 | Sampson | 4 | SR 1827 (BASSTOWN RD.) | FROM SR 1842 (BROWNS CHURCH RD) TO SR 1746 (KEENER RD.) MP 0.000 - MP 4.650) NO WORK ON BRIDGE 181 - MP 1.800 - MP 1.928 | 6 | 2 | 2WU | NO | | | | | | | | | | 930 | 233 | 233 | 3.38 | 465 | 2.33 | 60 | 465 | 140 | 3.38 | 465 |
| **TOTAL FOR MAP NO. 4** | | | | | | | | | | | | | | | | | | **930** | **233** | **233** | **3.38** | **465** | **2.33** | **60** | **465** | **140** | **3.38** | **465** |
| 2017CPT.03.02.20821 | Sampson | 5 | SR 1742 (MCCULLEN RD.) | FROM SR 1746 (KEENER RD.) TO SR 1731 (GOSHEN CHURCH RD.) MP 5.854 - MP 9.989 - NO ASPHALT WORK ON BRIDGE 233 (MP 8.854 - MP 8.904) | 6,7 | 2 | 2WU | NO | | | | | | | | | | 827 | 207 | 207 | 3.00 | 414 | 2.07 | 60 | 414 | 130 | 3.01 | 414 |
| **TOTAL FOR MAP NO. 5** | | | | | | | | | | | | | | | | | | **827** | **207** | **207** | **3.00** | **414** | **2.07** | **60** | **414** | **130** | **3.01** | **414** |
| 2017CPT.03.02.20821 | Sampson | 6 | SR 1441 (WELCOME SCHOOL RD.) | FROM SR 1006 (MAXWELL RD.) TO US 13 [MP 2.420 - MP 6.550] | 6 | 2 | 2WU | NO | | | | | | | | | | 826 | 207 | 207 | 3.00 | 413 | 2.07 | 60 | 413 | 130 | 3.00 | 413 |
| **TOTAL FOR MAP NO. 6** | | | | | | | | | | | | | | | | | | **826** | **207** | **207** | **3.00** | **413** | **2.07** | **60** | **413** | **130** | **3.00** | **413** |
| 2017CPT.03.02.20821 | Sampson | 7 | SR 1729 (BILL WALTERS RD.) | FROM NC 50 TO SR 1725 (GIDDENSVILLE RD.) MP 0.000 - MP 1.800 | 6 | 2 | 2WU | NO | | | | | | | | | | 360 | 90 | 90 | 1.31 | 180 | 0.90 | 30 | 180 | 60 | 1.31 | 180 |
| **TOTAL FOR MAP NO. 7** | | | | | | | | | | | | | | | | | | **360** | **90** | **90** | **1.31** | **180** | **0.90** | **30** | **180** | **60** | **1.31** | **180** |
| 2017CPT.03.02.20821 | Sampson | 8 | SR 1342 (WORLEY RD.) | FROM NC 242 TO SR 1006 (MAXWELL RD.) MP 0.000 - MP 0.810 | 6 | 2 | 2WU | NO | | | | | | | | | | 162 | 41 | 41 | 0.59 | 81 | 0.41 | 20 | 81 | 30 | 0.59 | 81 |
| **TOTAL FOR MAP NO. 8** | | | | | | | | | | | | | | | | | | **162** | **41** | **41** | **0.59** | **81** | **0.41** | **20** | **81** | **30** | **0.59** | **81** |
| **TOTAL FOR PROJ NO. 2017CPT.03.02.20821** | | | | | | | | | | | | | | | | | | **3,271** | **820** | **820** | **11.88** | **1,636** | **8.19** | **250** | **1,636** | **520** | **11.89** | **1,636** |
| 44735 | Sampson | 9 | S. FAYETTEVILLE ST. | FROM SR 1409 TO HOWARD ST. | 8 | 2 | 2WU | NO | | | | | | | | | | 25 | | | | | | | | 10 | 0.19 | |
| **TOTAL FOR MAP NO. 9** | | | | | | | | | | | | | | | | | | **25** | | | | | | | | **10** | **0.19** | |
| 44735 | Sampson | 10 | S. FAYETTEVILLE ST. | FROM HOWARD ST. TO SR 1233 | 9 | 2 | 2WU | NO | | | | | | 3 | | | | | | | | | | | | | | |
| **TOTAL FOR MAP NO. 10** | | | | | | | | | | | | | | **3** | | | | | | | | | | | | | | |
| 44735 | Sampson | 11 | N. FAYETTEVILLE ST. | FROM JACKSON ST. TO W. PINE ST. | 9 | 2 | 2WU | NO | | | | | | | | | | | | | | | | | | | | |
| **TOTAL FOR MAP NO. 11** | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 44735 | Sampson | 12 | N. FAYETTEVILLE ST. | FROM W. PINE ST. TO SR 1499 | 8 | 2 | 2WU | NO | | | | | | | | | | | | | | | | | | | | |
| **TOTAL FOR MAP NO. 12** | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 44735 | Sampson | 13 | JONES ST. | FROM CHURCH ST. TO SR 1492 | 8 | 2 | 2WU | NO | | | | | | | | | | | | | | | | | | | | |
| **TOTAL FOR MAP NO. 13** | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 44735 | Sampson | 14 | PARKER ST. | FROM W. TURLINGTON ST. TO W. PINE ST. | 8 | 2 | 2WU | NO | | | | | | | | | | | | | | | | | | | | |
| **TOTAL FOR MAP NO. 14** | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 44735 | Sampson | 15 | GORDON ST. | FROM SR 1233 TO DEAD END | 8 | 2 | 2WU | NO | | | | | | | | | | | | | | | | | | | | |
| **TOTAL FOR MAP NO. 15** | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 44735 | Sampson | 16 | SESSOMS ST. | FROM SR 1322 TO BESIN ROCK RD. | 8 | 2 | 2WU | NO | | | | | | 1 | | | | | | | | | | | | | | |
| **TOTAL FOR MAP NO. 16** | | | | | | | | | | | | | | **1** | | | | | | | | | | | | | | |
| 44735 | Sampson | 17 | BRADLEY ST. | FROM SR 1323 TO COOPER ST. | 8 | 2 | 2WU | NO | | | | | | 1 | | | | | | | | | | | | | | |
| **TOTAL FOR MAP NO. 17** | | | | | | | | | | | | | | **1** | | | | | | | | | | | | | | |
| 44735 | Sampson | 18 | COOPER ST. | FROM BRADLEY ST. TO SR 1323 | 8 | 2 | 2WU | NO | | | | | | | | | | | | | | | | | | | | |
| **TOTAL FOR MAP NO. 18** | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 44735 | Sampson | 19 | TEW LOOP | FROM NC 242 TO NC 242 | 8 | 2 | 2WU | NO | | | | | | | | | | | | | | | | | | | | |
| **TOTAL FOR MAP NO. 19** | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 44735 | Sampson | 20 | GOODRICH ST. | FROM CHURCH ST. TO W. TURLINGTON ST. | 8 | 2 | 2WU | NO | | | | | | | | | | | | | | | | | | | | |
| **TOTAL FOR MAP NO. 20** | | | | | | | | | | | | | | | | | | | | | | | | | | | | |