PROJECT NO.	SHEET NO.
2017CPT.03.02.10821, ETC.	23

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	4413000000-E WORK ZONE ADVANCE/GENERAL WARNING SIGNING SF	4457000000-N TEMPORARY TRAFFIC CONTROL LS	4510000000-N LAW ENFORCEMENT HR	4685000000-E 4" X 90 M WHITE THERMO LF	4686000000-E 4" X 120 M WHITE THERMO LF	4686000000-E 4" X 120 M YELLOW THERMO LF	4695000000-E 8" X 90 M WHITE THERMO LF	4695000000-E 8" X 90 M YELLOW THERMO LF	4697000000-E 8" X 120 M WHITE THERMO LF	4710000000-E 24" X 120 M WHITE THERMO LF	4721000000-E THERMO MSG SCHOOL 120 M EA	4721000000-E THERMO MSG ONLY 120 M EA	4725000000-E THERMO LT ARROW 90 M EA	4725000000-E THERMO STR ARROW 90 M EA	4725000000-E THERMO STR & RT ARROW 90 M EA	4725000000-E THERMO RT ARROW 90 M EA	4725000000-E YIELD LINE TRIANGLE 90 M EA
44735	Sampson	21	HALL ST.	FROM SR 1409 TO S. FAYETTEVILLE ST.	8	2	2WU	0.118	18		0.01															
TOTAL FOR MAP NO. 21								**0.118**			**0.01**															
44735	Sampson	22	MATTHEW ST.	FROM NC 242 TO FAYETTEVILLE ST.	8	2	2WU	0.122	18		0.01															
TOTAL FOR MAP NO. 22								**0.122**			**0.01**															
44735	Sampson	23	HOWARD ST.	FROM NC 242 TO S. FAYETTEVILLE ST.	8	2	2WU	0.117	20		0.01															
TOTAL FOR MAP NO. 23								**0.117**			**0.01**															
44735	Sampson	24	W. CLINTON ST.	FROM NC 242 TO SR 1492	8	2	2WU	0.123	28		0.01															
TOTAL FOR MAP NO. 24								**0.123**			**0.01**															
44735	Sampson	25	CHURCH ST.	FROM SR 1492 TO SR 1492	8	2	2WU	0.095	18		0.01															
TOTAL FOR MAP NO. 25								**0.095**			**0.01**															
44735	Sampson	26	HOLLAND ST.	FROM NC 242 TO GOODRICH ST.	8	2	2WU	0.057	19		0.01															
TOTAL FOR MAP NO. 26								**0.057**			**0.01**															
44735	Sampson	27	W. TURLINGTON ST.	FROM NC 242 TO SR 1492	8	2	2WU	0.324	18 - 19		0.02															
TOTAL FOR MAP NO. 27								**0.324**			**0.02**															
44735	Sampson	28	JACKSON ST.	FROM NC 242 TO SR 1492	8	2	2WU	0.097	19		0.01															
TOTAL FOR MAP NO. 28								**0.097**			**0.01**															
44735	Sampson	29	W. PINE ST.	FROM NC 242 TO N. FAYETTEVILLE ST.	8	2	2WU	0.35	18 - 26		0.02															
TOTAL FOR MAP NO. 29								**0.35**			**0.02**															
44735	Sampson	30	CHURCH ST.	FROM SR 1492 TO JONES ST.	8	2	2WU	0.229	19		0.01															
TOTAL FOR MAP NO. 30								**0.229**			**0.01**															
44735	Sampson	31	E. CLINTON ST.	FROM SR 1233 TO NC 242	8	2	2WU	0.32	19		0.01															
TOTAL FOR MAP NO. 31								**0.32**			**0.01**															
44735	Sampson	32	E. TURLINGTON ST.	FROM NC 242 TO SR 1323	8	2	2WU	0.081	20		0.01															
TOTAL FOR MAP NO. 32								**0.081**			**0.01**															
44735	Sampson	33	E. PINE ST.	FROM NC 242 TO SR 1323	8	2	2WU	0.174	20		0.01															
TOTAL FOR MAP NO. 33								**0.174**			**0.01**															
TOTAL FOR PROJ NO. 44735								**3.895**			**0.28**															
GRAND TOTAL								**30.000**		**3,110**	**1.00**	**70**	**268,157**	**1,120**	**183,025**	**2,874**	**228**	**288**	**328**	**12**	**4**	**19**	**3**	**2**	**1**	**14**
														184,145		**3,102**				**16**				**39**		