PROJECT NO.	SHEET NO.
2017CPT.03.02.10821, ETC.	24

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	4810000000-E 4" WHITE PAINT LF	4" YELLOW PAINT LF	4820000000-E 8" WHITE PAINT LF	4835000000-E 24" WHITE PAINT LF	4840000000-N PAINT MSG ONLY EA	4845000000-N PAINT LT ARROW EA	PAINT STR & RT ARROW EA	PAINT YIELD LINE TRIANGLE EA	PAINT STR ARROW EA	4847000000-E 4" WHITE POLYUREA (HIGHLY REFLECTIVE ELEMENTS) LF	4" YELLOW POLYUREA (HIGHLY REFLECTIVE ELEMENTS) LF	4850000000-E REMOVAL OF PAVEMENT MARKING LINES (4") LF	4900000000-N YELLOW & YELLOW MARKERS EA	4905000000-N SNOW PLOWABLE MARKERS (Y/Y) EA	SNOW PLOWABLE MARKERS (C/R) EA
2017CPT.03.02.10821	Sampson	1	NC 242 (SALEMBURG HWY)	FROM NC 24 TO NORTHERN TOWN LIMITS SALEMBURG (MP 5.464 - MP 10.434) NO ASPHALT TIP R-2303C MP 6.352 - MP 6.674 & BRIDGE NO.19 [MP 7.014 - MP 7.044)	1,2	2 - 3	2WU	4.97	24 - 37	9,590	17,285	3,162	180	4	3	2	14	3	340	215	555	36	482	22
TOTAL FOR MAP NO. 1								**4.97**		**9,590**	**17,285**	**3,162**	**180**	**4**	**3**	**2**	**14**	**3**	**340**	**215**	**555**	**36**	**482**	**22**
2017CPT.03.02.10821	Sampson	2	NC 411 (HARRELLS HWY.)	FROM NC 903 TO 0.32 MI. SOUTH OF GARLAND NORTHERN CITY LIMITS (MP 8.984 - MP 13.764)	3,4	2	2WU	4.78	20 - 40	50,916	35,904		48										324	
TOTAL FOR MAP NO. 2								**4.78**		**50,916**	**35,904**		**48**										**324**	
TOTAL FOR PROJ NO. 2017CPT.03.02.10821								**9.75**		**60,506**	**53,189**	**3,162**	**228**	**4**	**3**	**2**	**14**	**3**	**340**	**215**	**555**	**36**	**806**	**22**
										113,695					**22**				**555**				**828**	
2017CPT.03.02.20821	Sampson	3	SR 1842 (BROWNS CHURCH RD.)	FROM US 421 TO SR 1827 (BASSTOWN RD.) MP 1.820 - MP 2.650	5	2	2WU	0.83	18.5														55	
TOTAL FOR MAP NO. 3								**0.83**															**55**	
2017CPT.03.02.20821	Sampson	4	SR 1827 (BASSTOWN RD.)	FROM SR 1842 (BROWNS CHURCH RD) TO SR 1746 (KEENER RD.) MP 0.000 - MP 4.650) NO WORK ON BRIDGE 181 - MP 1.800 - MP 1.928	6	2	2WU	4.65	18.5														307	
TOTAL FOR MAP NO. 4								**4.65**															**307**	
2017CPT.03.02.20821	Sampson	5	SR 1742 (MCCULLEN RD.)	FROM SR 1746 (KEENER RD.) TO SR 1731 (GOSHEN CHURCH RD.) MP 5.854 - MP 9.989 - NO ASPHALT WORK ON BRIDGE 233 (MP 8.854 - MP 8.904)	6,7	2	2WU	4.135	19.25														273	
TOTAL FOR MAP NO. 5								**4.135**															**273**	
2017CPT.03.02.20821	Sampson	6	SR 1441 (WELCOME SCHOOL RD.)	FROM SR 1006 (MAXWELL RD.) TO US 13 [MP 2.420 - MP 6.550]	6	2	2WU	4.13	20.5														273	
TOTAL FOR MAP NO. 6								**4.13**															**273**	
2017CPT.03.02.20821	Sampson	7	SR 1729 (BILL WALTERS RD.)	FROM NC 50 TO SR 1725 (GIDDENSVILLE RD.) MP 0.000 - MP 1.800	6	2	2WU	1.8	20														119	
TOTAL FOR MAP NO. 7								**1.8**															**119**	
2017CPT.03.02.20821	Sampson	8	SR 1342 (WORLEY RD.)	FROM NC 242 TO SR 1006 (MAXWELL RD.) MP 0.000 - MP 0.810	6	2	2WU	0.81	20														53	
TOTAL FOR MAP NO. 8								**0.81**															**53**	
TOTAL FOR PROJ NO. 2017CPT.03.02.20821								**16.355**															**1,080**	
																							1,080	
44735	Sampson	9	S. FAYETTEVILLE ST.	FROM SR 1409 TO HOWARD ST.	8	2	2WU	0.264	20															
TOTAL FOR MAP NO. 9								**0.264**																
44735	Sampson	10	S. FAYETTEVILLE ST.	FROM HOWARD ST. TO SR 1233	9	2	2WU	0.268	28															
TOTAL FOR MAP NO. 10								**0.268**																
44735	Sampson	11	N. FAYETTEVILLE ST.	FROM JACKSON ST. TO W. PINE ST.	9	2	2WU	0.047	30															
TOTAL FOR MAP NO. 11								**0.047**																
44735	Sampson	12	N. FAYETTEVILLE ST.	FROM W. PINE ST. TO SR 1499	8	2	2WU	0.191	20															
TOTAL FOR MAP NO. 12								**0.191**																
44735	Sampson	13	JONES ST.	FROM CHURCH ST. TO SR 1492	8	2	2WU	0.169	20															
TOTAL FOR MAP NO. 13								**0.169**																
44735	Sampson	14	PARKER ST.	FROM W. TURLINGTON ST. TO W. PINE ST.	8	2	2WU	0.11	18 - 19															
TOTAL FOR MAP NO. 14								**0.11**																
44735	Sampson	15	GORDON ST.	FROM SR 1233 TO DEAD END	8	2	2WU	0.106	20															
TOTAL FOR MAP NO. 15								**0.106**																
44735	Sampson	16	SESSOMS ST.	FROM SR 1322 TO BESIN ROCK RD.	8	2	2WU	0.041	20															
TOTAL FOR MAP NO. 16								**0.041**																
44735	Sampson	17	BRADLEY ST.	FROM SR 1323 TO COOPER ST.	8	2	2WU	0.152	18															
TOTAL FOR MAP NO. 17								**0.152**																
44735	Sampson	18	COOPER ST.	FROM BRADLEY ST. TO SR 1323	8	2	2WU	0.091	19															
TOTAL FOR MAP NO. 18								**0.091**																
44735	Sampson	19	TEW LOOP	FROM NC 242 TO NC 242	8	2	2WU	0.133	18															
TOTAL FOR MAP NO. 19								**0.133**																
44735	Sampson	20	GOODRICH ST.	FROM CHURCH ST. TO W. TURLINGTON ST.	8	2	2WU	0.116	19															
TOTAL FOR MAP NO. 20								**0.116**																