PROJ. REFERENCE NO.	SHEET NO.
B-5380	X-1A

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Approximate quantities only. Unclassified excavation, fine grading and clearing and grubbing will be paid for at the lump sum price for "Grading".

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
11+00.00	0	0
11+25.00	69	2
11+50.00	171	0
11+75.00	260	0
12+00.00	159	0
12+04.62	6	0

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
12+57.98	0	0
12+75.00	3	3
13+00.00	7	8
13+25.00	9	6
13+50.00	5	4
13+65.00	2	2