




| | | | |
|---------|-------------|-----------|--------------|
| STATE | PROJECT NO. | SHEET NO. | TOTAL SHEETS |
| N.C. | I-5768 | 16 | |
| WBS NO. | 530IL3J | | |



| PAVEMENT SCHEDULE | |
|-------------------|--|
| B1 | PROP. APPROX. 5/8" ULTRATHIN HOT MIX ASPHALT COURSE, AT AN AVERAGE RATE OF 70 LBS. PER SQ. YD. |
| C1 | PROP. APPROX. 2.0" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5D, AT AN AVERAGE RATE OF 224 LBS. PER SQ. YD. |
| C2 | PROP. APPROX. 1.5" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5C, AT AN AVERAGE RATE OF 168 LBS. PER SQ. YD. |
| V1 | MILLING 1.5" DEPTH |
| V2 | PROFILE MILLING, 0" to 1.5" DEPTH |
| V3 | PROFILE MILLING, 1.5" to 2.0" DEPTH |
| V4 | MILLING, 2.0" DEPTH |
| V5 | MILLING, 2.5" DEPTH |
| T | SHOULDER RECONSTRUCTION |
| M | MILLED RUMBLE STRIPS |

I-5768 Interstate 77 Pavement Rehabilitation

SCALE -NA-
DATE 8/16
DWG. BY TJP
DESIGN BY TJP
APPROVED WAT



REVISIONS

| | |
|--|--|
| | |
| | |
| | |