PROJ. REFERENCE NO.	SHEET NO.
B-5360	X-1

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

Approximate quantities only. Unclassified excavation, fine grading, clearing and grubbing, and removal of existing pavement will be paid for at the lump sum price for "Grading".

NOTE: EMBANKMENT COLUMN INCLUDES BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station -L-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)	Station -DRV3-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
13+00.00	0	0	0	10+00.00	0	0	0
13+50.00	15	3	0	10+06.00	5	2	0
14+00.00	11	8	0	10+25.00	32	7	0
14+50.00	19	19	0	10+50.00	85	0	0
15+00.00	43	52	0	10+75.00	100	0	0
15+50.00	81	87	0	11+00.00	80	0	0
16+00.00	88	84	0	11+25.00	44	6	0
16+50.00	64	118	0	11+34.00	8	13	0
17+00.00	54	204	0	11+50.00	9	31	0
17+50.00	66	215	0	11+75.00	13	46	0
18+00.00	95	143	0	12+00.00	7	53	0
18+50.00	190	110	60	12+25.00	0	51	0
19+00.00	348	100	100				
19+50.00	382	85	85				
20+00.00	249	90	80				
20+40.00	66	112	25				
20+50.00	8	42	0				
21+00.00	41	420	0				
21+50.00	0	993	0				
22+00.00	0	2067	0				
22+21.70	0	914	0				

Station -L-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
25+14.30	0	0	0
25+50.00	5	1101	0
26+00.00	7	1479	0
26+50.00	0	700	0
27+00.00	37	295	0
27+50.00	89	114	0
27+74.31	59	18	0
28+00.00	75	15	0
28+50.00	122	57	0
29+00.00	79	71	0
29+30.00	34	88	5
29+50.00	20	88	40
29+60.00	9	32	20
30+00.00	20	131	80
30+50.00	22	132	90
31+00.00	36	123	90
31+30.00	24	77	65
31+50.00	20	49	45
32+00.00	56	121	115
32+50.00	37	119	105
33+00.00	23	124	105
33+15.70	3	45	40