

* TOTAL BILL OF MATERIAL													
BRIDGE	MOBILIZATION	INCIDENTAL MILLING	ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B	ASPHALT BINDER FOR PLANT MIX	△ REINFORCING STEEL	SHOTCRETE REPAIRS	EPOXY RESIN INJECTION	BRIDGE JOINT REMOVAL	PILE JACKETS	REJACKETS	SILICONE JOINT SEALANT	CONCRETE DECK REPAIR FOR EPOXY OVERLAY	EPOXY OVERLAY SYSTEM-MECHANICALLY DISTRIBUTED
	LUMP SUM	SQ.YDS.	TONS	TONS	LBS.	CU. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	SQ. FT.	SQ. FT.
TYRRELL #7	LUMP SUM	267	22.5	1.5	10	1,363.5	98.1	9,429	7,013.5	438	9,489	473	387,507

* EXCLUDES BILL OF MATERIAL FOR PIVOT PIER PILE REPAIRS AND FOR MECHANICAL AND ELECTRICAL PLANS, SEE SHT'S SA-1 THRU SA-3 AND SHT'S G-1 THRU M-23.

△ REINFORCING STEEL QUANTITY IS NOT ANTICIPATED, A TOKEN PAY ITEM IS INDICATED FOR PRICING PURPOSES, IN CASE UNANTICIPATED REPAIRS ARE ENCOUNTERED.

PROJECT NO. B-5936
TYRRELL COUNTY
 BRIDGE NO. 7

DocuSigned by:
Robbie Weisz 10/2016
 CEA153463B6D43D...



STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH

TOTAL BILL OF MATERIAL

DRAWN BY : S. T. SANDOR DATE : 06/2016
 CHECKED BY : R. N. WEISZ DATE : 06/2016

DOCUMENT NOT CONSIDERED
 FINAL UNLESS ALL
 SIGNATURES COMPLETED

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			S-1
2			4			TOTAL SHEETS 394