U.	
\	ı
_	1
$\leftarrow$	

PROJECT REFERENCE NO.		SHEET NO.			
B-4945		/A			
	- DocuSign	ed by:			
	Bruce	rayue 37 137 2010			
DOCUMENT NOT CONSIDERED FINAL					

**UNLESS ALL SIGNATURES COMPLETED** 

II	NDEX OF SHEETS
SHEET NUMBER	SHEET
1	TITLE SHEET
1 A	INDEX OF SHEETS, GENERAL NOTES, AND STANDARD DRAWINGS
1B	CONVENTIONAL SYMBOLS
1 C - 1	SURVEY CONTROL SHEET
2A-1	PAVEMENT SCHEDULE AND TYPICAL SECTIONS
2C-1	DETAIL SHEET FOR TYPE III ANCHOR UNIT
2G-1	GEOTECHNICAL DETAILS
3B-1	ROADWAY SUMMARIES
3D-1	DRAINAGE SUMMARIES
4 THRU 5	PLAN AND PROFILE SHEET
TMP-1 THRU TMP-4	TRAFFIC MANAGEMENT PLANS
PMP-1	PAVEMENT MARKING PLANS

EROSION CONTROL PLANS

CROSS-SECTIONS

STRUCTURE PLANS

CROSS-SECTION SUMMARY SHEET

EC-1 THRU EC-5

X-1 THRU X-3

S-1 THRU S-15

X-O

NERAL	NOTES:	2012	SPECIFICA	ATIONS
		EFFE(	CTIVE:	01-17-201
		REVIS	SED:	10-31-201

#### GRADE LINE: GRADING AND SURFACING:

THE GRADE LINES SHOWN DENOTE THE FINISHED ELEVATION OF THE PROPOSED SURFACING AT GRADE POINTS SHOWN ON THE TYPICAL SECTIONS. GRADE LINES MAY BE ADJUSTED AT THEIR BEGINNING AND ENDING AND AT STRUCTURES AS DIRECTED BY THE ENGINEER IN ORDER TO SECURE A PROPER TIE-IN.

## CLEARING:

CLEARING ON THIS PROJECT SHALL BE PERFORMED TO THE LIMITS ESTABLISHED BY

## SUPERELEVATION:

ALL CURVES ON THIS PROJECT SHALL BE SUPERELEVATED IN ACCORDANCE WITH STD. NO. 225.04 USING THE RATE OF SUPERELEVATION AND RUNOFF SHOWN ON THE PLANS. SUPERELEVATION IS TO BE REVOLVED ABOUT THE GRADE POINTS SHOWN ON THE TYPICAL SECTIONS.

## SHOULDER CONSTRUCTION:

ASPHALT, EARTH, AND CONCRETE SHOULDER CONSTRUCTION ON THE HIGH SIDE OF SUPERELEVATED CURVES SHALL BE IN ACCORDANCE WITH STD. NO. 560.01

#### GUARDRAIL:

THE GUARDRAIL LOCATIONS SHOWN ON THE PLANS MAY BE ADJUSTED DURING CONSTRUCTION AS DIRECTED BY THE ENGINEER. THE CONTRACTOR SHOULD CONSULT WITH THE ENGINEER PRIOR TO ORDERING GUARDRAIL MATERIAL.

#### TEMPORARY SHORING:

SHORING REQUIRED FOR THE MAINTENANCE OF TRAFFIC WILL BE PAID FOR AS "EXTRA WORK" IN ACCORDANCE WITH SECTION 104-7.

### END BENTS:

THE ENGINEER SHALL CHECK THE STRUCTURE END BENT PLANS, DETAILS, AND CROSS-SECTION PRIOR TO SETTING OF THE SLOPE STAKES FOR THE EMBANKMENT OR EXCAVATION APPROACHING A BRIDGE.

## RIGHT-OF-WAY MARKERS:

ALL RIGHT-OF-WAY MARKERS ON THIS PROJECT SHALL BE PLACED BY CONTRACT.

# 2012 ROADWAY ENGLISH STANDARD DRAWINGS

The following Roadway Standards as appear in "Roadway Standard Drawings" Highway Design Branch - N. C. Department of Transportation - Raleigh, N. C., Dated January, 2012 are applicable to this project and by reference hereby are considered a part of these plans:

REV. 02-29-2016

# STD.NO. TITLE

DIVISION 2 - EARTHWORK
200.03 Method of Clearing - Method III

225.02 Guide for Grading Subgrade - Secondary and Local 225.04 Method of Obtaining Superelevation - Two Lane Pavement

DIVISION 3 - PIPE CULVERTS

300.01 Method of Pipe Installation
DIVISION 4 - MAJOR STRUCTURES

422.11 Bridge Approach Fills - Sub Regional Tier

DIVISION 5 - SUBGRADE, BASES AND SHOULDERS

560.01 Method of Shoulder Construction – High Side of Superelevated Curve – Method I

840.35 Traffic Bearing Grated Drop Inlet – for Cast Iron Double Frame and Grates

DIVISION 8 - INCIDENTALS

806.01 Concrete Right-of-Way Marker 806.02 Granite Right-of-Way Marker

840.24 Frames and Narrow Slot Sag Grates

840.25 Anchorage for Frames - Brick or Concrete or Precast

840.46 Traffic Bearing Precast Drainage Structure

846.01 Concrete Curb, Gutter and Curb & Gutter

846.04 Drop Inlet Installation in Shoulder Berm Gutter

862.01 Guardrail Placement

862.02 Guardrail Installation

876.02 Guide for Rip Rap at Pipe Outlets

JSFRYAMF\$\$\$\$